

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000						CODE NO	ITEM		UNIT				
42101300	PROTECTIVE COAT	SO YD	5887	5887													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150													
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	4833	4833													
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	323	323													
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	698	698													
44213200	SAW CUTS	FOOT	26502	26502													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12													
*78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	150	150													
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8742	8742													
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	200	200													
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	100	100													
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	110	110													
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	688	688													
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	308.4	308.4													
Z0017202	DOWEL BARS 1 1/2"	EACH	12,900	12,900													
Z0075330	TIE BARS 1 1/4"	EACH	8140	8140													
44213100	PAVEMENT FABRIC	SQ YD	1021	1021													
Z0075310	TIE BARS 3/4"	EACH	480	480													

* SPECIALTY ITEM

Rev. 7-21-09