

SECTION COUNTY SHEETS NO. 3578 15 VB-1-F COOK 62 30 STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 60H5




PARAPET SLIDING P ASSEMBLY

(Top View)

PARAPET SLIDING P ASSEMBLY AT SIDEWALK



SECTION A-A




SECTION B-B

- 1. New Modular Expansion Joints shall be installed to replace the expansion joints at Piers 6 and 11
- 2. See Special Provisions for a list of Approved Modular Expansion Joints Systems.
- 3. Joints shall provide a minimum total movement of 150 mm.
- 4. The Sliding Plate Assemblies shall be Hot-Dip Galvanized in accordance with ASTM A-123.
- 5. Sliding Plate Assemblies shall be provided for the sidewalk & barrier and the parapet at each Modular Joint location. Cost of furnishing and installing Sliding Plate Assemblies shall be included with Modular Expansion Joint 160 mm. Confractor shall submit shop drawlings showing the plate dimensions based on the actual joint system selected.
- The Contractor shall verify ALL dimensions in the field before fabrication of Modular Joints and Sliding Plate Assemblies.
- 7. Box Spacing and Stud Spacing shall be per Modular Joint Manufacturer.
- Modular expansion joints shall be assembled in their final relative position with the ends in place for shop inspection and acceptance.
- Support box should be rigidly attached to diaphragm by adjustable bracket, stools
 or shims. Cost is included in the Modular Expansion Joint 160 mm.


BILL OF MATERIAL

	ITEM	UNIT	aTY.
*	Modular Expansion Joint 160mm	m	31.2

* See Special Provision in Contract



MODULAR EXPANSION JOINT UPTURN DETAIL AT CURB



MODULAR EXPANSION JOINT UPTURN DETAIL AT PARAPET

DEVICTORS

	REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
	NAME DATE	TELEVISION DEL ARTIMENT OF TRANSFORMATION
-		MODULAR EXPANSION JOINT II
		SOUTHWEST HIGHWAY OVER
		B&O RAILROAD AND STONY CREEK
	:	FAU 3578 SECTION 15 VB-1-F
-		STRUCTURE NUMBER 016-2771
		COOK COUNTY STATION 4+716.497
		SCALE: NONE DRAWN BY: R. DIGIUNO
		DATE: MAY 22, 2009 CHECKED BY: A. Durbak

PATRICK ENGINEERING INC.

CHECKED BY: A. Durbak FOR INFORMATION ONLY

LISLE, ILLINOIS