SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN 100% STATE)	CONSTRUCTION TYPE CODE: SFTY-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	122	122					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
~~70300520~~	~~PAVEMENT MARKING TAPE, TYPE III 4"~~	~~FOOT~~	~~274132~~	~~274132~~					
~~70300550~~	~~PAVEMENT MARKING TAPE, TYPE III 8"~~	~~FOOT~~	~~12306~~	~~12306~~					
~~70300560~~	~~PAVEMENT MARKING TAPE, TYPE III 12"~~	~~FOOT~~	~~12789~~	~~12789~~					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	120,647	120,647					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	274132	274132					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	12306	12306					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	12789	12789					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	112371	112371					
X0326218	FIBER-MODIFIED ASPHALT CRACK SEALING	FOOT	6897	6897					
X0326219	BUMP REMOVAL	EACH	1380	1380					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	23	23					
XZ186500	ASPHALTIC EMULSION SLURRY SEAL	SQ YD	304579	304579					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24,826	24,826					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	274,132	274,132					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	12,306	12,306					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	12,789	12,789					

* SPECIALTY ITEMS

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

FILE NAME = c:\pw_work\pw1dot\steedpa\d0142782\D175309-sht-plan.dgn	USER NAME = steedpa	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/20/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-57--KANKAKEE COUNTY LINE TO COOK COUNTY LINE

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2009-065 I	WILL	36	3

CONTRACT NO. 60H55

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT