

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = abebawa	DESIGNED -	REVISED -	- R. MIRS 09-15-97		ARTERIAL ROAD		F.A.P.	SECTION	COUNTY	TOTAL SHEET	
c:\pw_work\PWIDOT\ABEBAWA\dØ147261\Dist	t\$td.dgn	DRAWN -	REVISED ~	R. MIRS 12-11-97	STATE OF ILLINOIS				352	113 RS-6 (09)	LAKE	17 16
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	-T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN				TC-22	CONTRACT	T NO. 60123
	PLOT DATE = 6/12/2009	DATE -	REVISED -	C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.			FED. ROAD		AID PROJECT	