



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| | | | | | | | | | | | |
|--|-------------------------|----------------------------|-----------------------------|---|--|-------------------------|--------------------------|-------------------------|-----------------|--------------------|--|
| FILE NAME = | USER NAME = gulllaumefp | DESIGNED - R. SHAH | REVISED - A. ABBAS 04-27-98 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT | F.A.P. RTE. 352 | SECTION (E.M.D) RS-4 | COUNTY LAKE | TOTAL SHEETS 41 | SHEET NO. 30 | |
| ci\pwr\work\pwr\dot\gulllaumefp\d0138202\037202-shr-plan.dgn | DRAWN - | REVISED - R. BORO 01-01-07 | SCALE: NONE | | | SHEET NO. 1 OF 1 SHEETS | STA. _____ TO STA. _____ | BD400-04 (BD-22) | | CONTRACT NO. 62545 | |
| PLOT SCALE = 50.0000' / IN. | CHECKED - | REVISED - R. BORO 09-04-07 | | | | | | | | | |
| PLOT DATE = 4/21/2009 | DATE - 10-25-94 | REVISED - K. ENG 10-27-08 | | | | | | | | | |