

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1503	08-00260-01-PV	KANE	176	9
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
						ROADWAY I000	LIGHTING Y030-IE	SIGNALS Y031	NON-PART
S		XX003536	CONNECTION TO EXISTING WATER MAINS (NON PRESSURE)	EACH	8	8			
S		XX003885	IRRIGATION SYSTEM	L SUM	1	1			
		XX004688	BRICK PAVER SIDEWALK	SQ FT	180				180
		XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1	1			
S		84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2	2			
S		XX005238	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	2,353	2,353			
		XX005348	AGGREGATE SHOULDERS (SPECIAL)	FOOT	3,184	3,184			
S		XX008055	ABANDON WATER MAIN	CU YD	128	128			
S		X0130250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C TWISTED SHIELDED	FOOT	500			500	
S		XX005845	MODULAR CONCRETE PAVERS (SPECIAL)	SQ FT	988	988			
S		XX006038	CONNECTION TO EXISTING WATER MAINS (PRESSURE) 16"	EACH	1	1			
		XX006277	TEMPORARY SEDIMENT TRAP	EACH	1	1			
S		XX006505	EXTERNAL LIGHT SHIELD, HOUSE SIDE	EACH	20		20		
		XX006574	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1			
S		X0620020	UNINTERRUPTABLE POWER SUPPLY	EACH	1			1	
S		XX006710	SEEDING, CLASS 5 (MODIFIED) WET TO MESIC PRAIRIE	ACRE	0.07	0.07			
S		XX024100	EXPOSED AGGREGATE SURFACE	SQ FT	400	400			
		XX104100	CONNECTION TO EXISTING MANHOLE	EACH	1	1			
		XZ161800	TRAILER MOUNTED ARROW BOARD, TYPE B	EACH	9	9			
		X0301834	STORM SEWER TO BE FILLED	FOOT	793	793			
		X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	1,000	1,000			
S		X0321720	WATER MAIN REMOVAL	FOOT	500	500			
S		X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	88	88			
S		X0322925	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C	FOOT	2,900			2,900	
		X0322938	TEMPORARY END SECTION	EACH	11	11			
S		X0323777	VIDEO VEHICLE DETECTION, 3 CAMERAS	EACH	1			1	
		X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	7,076	7,076			
		X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3,538	3,538			
S		X0325570	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	46	46			
		X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	5	5			
		X0712400	TEMPORARY PAVEMENT	SQ YD	3,942	3,942			
		X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	43	43			
		X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	16	16			
		X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4			
		X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2			
		X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	18	18			
		X7240500	RELOCATE EXISTING SIGNS	EACH	3	3			
S		X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	365	365			
S		X7800200	PAINT PAVEMENT MARKING CURB	FOOT	280	280			
S		X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2,900			2,900	
S		X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	600			600	
S		XX008056	POLYETHYLENE DUCT BORED AND PULLED, 1-1/4" DIA. WITH ELECTRIC CABLE 600 V (XLP-TYPE USE), 3-1/C NO.6 AND 1/C NO. 6 GROUND	FOOT	6,290		6,290		
		X008057	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
		35600714	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/2"	SQ YD	155	155			
		61100100	MOBILIZATION	L SUM	1	1			

PLOT DATE = 5/26/2009
 PLOT SCALE = N/A
 USER NAME = USER



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 6 OF 6

SCALE: VERT. N/A
 DATE: 1/7/09

DRAWN BY TC
 CHECKED BY TC/SBP