



\* EXISTING PAVEMENT

\* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

**NOTES:**

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

**SEQUENCE OF CONSTRUCTION**

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE FULL DEPTH PATCHES
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = W:\d:\state\22x34\bd22.dgn	USER NAME = gngkremobt	DESIGNED - R. SHAH	REVISED - A. ABBAS 01-20-98
		DRAWN -	REVISED - A. ABBAS 04-27-98
		CHECKED -	REVISED - R. BORO 01-01-07
		DATE - 10-25-94	REVISED - R. BORO 09-04-07

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT			
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	BD400-04 (BD-22)			
CONTRACT NO.				
FED. ROAD DIST. NO.   ILLINOIS FED. AID PROJECT				

Plotted: March 20, 2009 @ 11:01 AM By: Jim Galus - Tab: 16 BD-22 22x34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**CITY OF ELGIN**  
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS
2	03-20-09	PER IDOT COMMENTS
1	02-13-09	PER IDOT COMMENTS

**SUMMIT STREET**  
LAPP IMPROVEMENTS

**PAVEMENT PATCHING FOR**  
HMA SURFACED PAVEMENT

DATE:	DECEMBER 2008
PROJECT NO:	EG0810
FILE:	EG0810-CVR
SHEET	<b>16</b> OF <b>19</b>

Path: H:\S\SR\PROJ\EG0810\DWG\FINAL\_ENG\EG0810-CVR