


SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY CONSTRUCTION CODE: 1000	QUANTITY 'NON-PARTICIPATING'	
1	20101000	TEMPORARY FENCE	FOOT	4,330	4,330	0
2	20101100	TREE TRUNK PROTECTION	EACH	14	14	0
3	20101200	TREE ROOT PRUNING	EACH	4,330	4,330	0
4	20200100	EARTH EXCAVATION	CU YD	235	235	0
5	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	126	126	0
6	20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	100	100	0
7	20800150	TRENCH BACKFILL	CU YD	5,960	4,465	1,495
8	21101610	TOPSOIL FURNISH AND PLACE, 3"	SQ YD	6,780	6,780	0
9	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	50	30	20
10	25200110	SODDING, SALT TOLERANT	SQ YD	6,780	6,780	0
11	25200200	SUPPLEMENTAL WATERING	UNIT	150	150	0
12	28000510	INLET FILTERS	EACH	35	35	0
13	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	170	170	0
14	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	100	100	0
15	35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	6	6	0
16	40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	180	0	180
17	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	160	160	0
18	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,910	3,910	0
19	40600300	AGGREGATE (PRIME COAT)	TON	55	55	0
20	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30	0
21	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	75	75	0
22	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	490	490	0
23	40600982	HOT-MX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133	0
24	40601005	HOT-MX ASPHALT REPLACEMENT OVER PATCHES	TON	520	430	90
25	40603085	HOT-MX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,100	1,100	0
26	40603310	HOT-MX ASPHALT SURFACE COURSE, MX "C", N50	TON	145	145	0
27	40603340	HOT-MX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,035	1,035	0
28	40701861	HOT-MX ASPHALT PAVEMENT (FULL-DEPTH), 9" SQ YD	SQ YD	1,600	1,600	0
29	40701901	HOT-MX ASPHALT PAVEMENT (FULL-DEPTH), 11" SQ YD	SQ YD	1,060	1,060	0
30	40800050	INCIDENTAL HOT-MX ASPHALT SURFACING	TON	10	10	0
31	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	365	365	0
32	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	124	124	0
33	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	7,450	7,450	0
34	42400800	DETECTABLE WARNINGS	SQ FT	341	341	0
35	44000100	PAVEMENT REMOVAL	SQ YD	3,110	3,110	0
36	44000198	HOT-MX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	13,105	13,105	0
37	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	450	450	0
38	44000300	CURB REMOVAL	FOOT	4,100	4,100	0
39	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,710	1,710	0
40	44000600	SIDEWALK REMOVAL	SQ FT	7,405	7,405	0
41	550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	602	602	0
42	550A2760	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 24"	FOOT	968	968	0
43	550A2780	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 30"	FOOT	469	469	0
44	56102900	DUCTILE IRON WATER MAIN 4"	FOOT	165	0	165
45	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	170	0	170
46	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	480	0	480
47	56103300	DUCTILE IRON WATER MAIN 12"	FOOT	860	0	860
48	56104800	WATER VALVES 4"	EACH	6	0	6
49	56104900	WATER VALVES 6"	EACH	1	0	1
50	56105000	WATER VALVES 8"	EACH	4	0	4
51	56105200	WATER VALVES 12"	EACH	5	0	5
52	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2	0	2
53	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	4	0	4
54	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	8	0	8
55	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	0
56	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6	0
57	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	0
58	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	9	9	0
59	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	0	2
60	60249300	VALVE BOXES 4"	EACH	6	0	6
61	60249400	VALVE BOXES 6"	EACH	2	0	2
62	60249500	VALVE BOXES 8"	EACH	1	0	1
63	60249700	VALVE BOXES 12"	EACH	4	0	4

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY CONSTRUCTION CODE: 1000	QUANTITY 'NON-PARTICIPATING'	
64	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	14	14	0
65	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	8	8	0
66	60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1	1	0
67	60266910	VALVE BOXES TO BE REMOVED	EACH	6	0	6
68	60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	4	4	0
69	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12	12	0
70	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8	0
71	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22	0
72	60300410	VALVE BOX FRAMES TO BE ADJUSTED WITH NEW FRAMES	EACH	2	2	0
73	60405700	FRAMES AND GRATES, SPECIAL	EACH	15	15	0
74	60406500	FRAMES AND LIDS, SPECIAL	EACH	12	12	0
75	60500040	REMOVING MANHOLES	EACH	1	1	0
76	60500050	REMOVING CATCH BASINS	EACH	12	12	0
77	60500060	REMOVING INLETS	EACH	2	2	0
78	60500405	FILLING VALVE VAULTS	EACH	4	0	4
79	60600605	CONCRETE CURB, TYPE B	FOOT	120	120	0
80	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,875	5,875	0
81	63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	80	80	0
82	63600105	CABLE ROAD GUARD, SINGLE STRAND	FOOT	145	145	0
83	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	12	12	0
84	67100100	MOBILIZATION	L SUM	1	1	0
85	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	0
86	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	0
87	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	750	750	0
88	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,000	11,000	0
89	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	265	265	0
90	70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	250	250	0
91	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,500	5,500	0
92	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	155	155	0
93	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,640	2,640	0
94	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,910	2,910	0
95	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	485	485	0
96	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	135	135	0
97	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70	70	0
98	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40	40	0
99	88600600	DETECTOR LOOP REPLACEMENT	FOOT	105	105	0
100	Z0041700	PLUG EXISTING STORM SEWERS	EACH	90	90	0
101	Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	15	15	0
102	Z0078600	TRAINEES	FOOT	1,000	1,000	0
103	X0321317	GRANULAR BACKFILL	CU YD	15	15	0
104	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	0
105	X0325526	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TON	215	215	0
106	XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	455	455	0
107	XX002817	TEMPORARY LINE STOPPER, 6 INCH	EACH	1	0	1
108	XX003536	CONNECTION TO EXISTING WATER MAINS (NON PRESSURE)	EACH	6	0	6
109	XX004689	SANITARY SERVICE TO BE ADJUSTED	EACH	15	15	0
110	XX005213	WATER SERVICE LINE TO BE ADJUSTED	EACH	15	15	0
111	XX004812	VIDEO TAPING OF SEWERS	FOOT	6,750	6,750	0
112	XX005617	CONNECTING TO EXISTING MANHOLES BY CORE DRILLING	EACH	22	22	0
113	XX005758	TEMPORARY PAVEMENT	TON	60	0	60
114	XX006111	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, LONG SIDE 1"(MINIMUM)	EACH	6	0	6
115	XX006112	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, SHORT SIDE 1"(MINIMUM)	EACH	10	0	10
116	XX006281	STORM SEWERS, DUCTILE IRON, TYPE 1 10"	FOOT	189	189	0
117	XX006282	STORM SEWERS, DUCTILE IRON, TYPE 1 12"	FOOT	516	516	0
118	XX006284	STORM SEWERS, DUCTILE IRON, TYPE 2 18"	FOOT	569	569	0
119	XX006448	10" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	10	10	0
120	XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	38	38	0
121	XX005044	CLASS D PATCHES, 9 INCH	SQ YD	395	100	295
122	XX005063	CLASS B PATCHES	SQ YD	2,920	2,160	770
123	XX006786	CLASS D PATCHES, SPECIAL, 7 INCHES	SQ YD	485	485	0

△ DENOTES SPECIALTY ITEM
 △ INDICATES NON-STANDARD ITEM COVERED BY SPECIAL PROVISION OR PLAN NOTE

PLANS PREPARED BY:  CITY OF EVANSTON
 PUBLIC WORKS DEPARTMENT TRANSPORTATION
 AND ENGINEERING DIVISION
 PHONE: (847) 866-2924

DESIGNED -- DSM, AA REVISED -- 5/20/09 PER MWRD
 DRAWN -- DSM REVISED -- 5/20/09 PER IDOT
 CHECKED -- SN, PC REVISED --
 DATE -- 2 / 3 / 2009 REVISED --

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SHERIDAN ROAD

SCALE: N.T.S. SHEET NO. 3 OF 31 SHEETS STA. N.A. TO STA. N.A.

F. AU. RTEL. 2865	SECTION 08-00250-01-PV	COUNTY COOK	TOTAL SHEETS 31	SHEET NO. 3
				CONTRACT NO. 63189
ILLINOIS FED. AID PROJECT				