

SUMMARY OF QUANTITIES

ITEM NO.	PAY CODE	ITEM	UNIT	SFTY-1B QUANTITY
1	20101200	TREE ROOT PRUNING	EACH	51
2	20200100	EARTH EXCAVATION	CU YD	640
3	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1000
4	25000210	SEEDING, CLASS 2A	ACRE	0.2
5	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20
6	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20
7	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20
8	25100630	EROSION CONTROL BLANKET	SQ YD	1000
9	28000400	PERIMETER EROSION BARRIER	FOOT	751
10	28000510	INLET FILTERS	EACH	11
11	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1750
12	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	15690
13	42400800	DETECTABLE WARNINGS	SQ FT	64
14	44000600	SIDEWALK REMOVAL	SQ FT	960
15	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	202
16	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	240
17	60255500	MANHOLES TO BE ADJUSTED	EACH	2
18	67100100	MOBILIZATION	L SUM	1
19	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
20	X0321556	SANITARY MANHOLE TO BE ADJUSTED	EACH	2
21	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
22	XX007729	DETECTABLE WARNINGS (SPECIAL)	SQ FT	175

* SPECIAL PROVISION

CHRISTOPHER B. BURKE ENGINEERING LTD.
 318 ALANA DRIVE
 New Lenox, Illinois 60451 (815) 463-9050

FEDERAL AID DESIGN ENGINEER: MELCHOR MANGOBA
 201 W. CENTER COURT
 SCHAUMBURG, ILLINOIS 60196-1096
 (847) 705-4408

FILE NAME =	USER NAME = JDRALLE	DESIGNED CAA	REVISED 5/15/09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\Shorewood\070001\070001C\2008\C08-05-	C:\civil\SUM_C08-05.dgn	DRAWN CAA	REVISED -			08-00024-00-SW	WILL	37	3	
PLOT SCALE = N.T.S.	CHECKED KRC	REVISOR -	SCALE: N.T.S.			STA. NA TO STA. NA		CONTRACT NO. 63200		
PLOT DATE = 6/4/2009	DATE 5/15/09	REVISOR -	ILLINOIS FED. AID PROJECT							