

# SUMMARY OF QUANTITIES

CODE	PAY ITEM DESCRIPTION	UNIT	1000	1000	
			TOTAL QUANTITY	100% FEDERAL 0% LOCAL	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	275	275	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5	
25200100	SODDING	SQYD	275	275	
25200200	SUPPLEMENTAL WATERING	UNIT	10	10	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	40	40	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,750	1,750	
40600300	AGGREGATE (PRIME COAT)	TON	20	20	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	460	460	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	150	150	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	1,100	1,100	
42101300	PROTECTIVE COAT	SQYD	400	400	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	150	150	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	1,400	1,400	
~	42400800	DETECTABLE WARNINGS	SQFT	128	128
~	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	8,700	8,700
~	44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	125	125
~	44000600	SIDEWALK REMOVAL	SQFT	1,400	1,400
~	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600
~	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQYD	30	30
~	44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQYD	400	400
~	60213900	RESTRICTED DEPTH CATCH BASINS, 4' DIA, TY 1 FR, C.L.	EACH	1	1
~	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	10	10
~	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3
~	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	16	16
~	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1
~	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	23	23
~	67100100	MOBILIZATION	L SUM	1	1
~	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	40	40
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,200	2,200
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	250	250
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75
~*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	175	175
~	Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	20

\* DENOTES SPECIALTY ITEM  
~ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\05000009 - Brainard Ave LAPP\Summary.dwg Jun 03, 2009 10:23am



USER NAME	DESIGNED WOP	REVISED
PLOT SCALE	DRAWN LEV	REVISED
PLOT DATE	CHECKED WOP	REVISED
	DATE 6-3-09	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FAU. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2704	09-00131-00-RS	COOK	14	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63206	
ARA-9003(3Q3)			E.H.E. PROJECT NO. 520-09-06901	