

SUMMARY OF QUANTITIES

CODE	PAY ITEM DESCRIPTION	UNIT	1000 TOTAL QUANTITY	1000 100% FEDERAL 0% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	70	70
25200110	SODDING, SALT TOLERANT	SQYD	70	70
25200200	SUPPLEMENTAL WATERING	UNIT	50	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,200	1,200
40600300	AGGREGATE (PRIME COAT)	TON	25	25
40600895	CONSTRUCTING TEST STRIP	EACH	2	3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	85	85
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	1,400	1,400
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	50	50
⊛ 42400800	DETECTABLE WARNINGS	SQFT	15	15
⊛ 44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQYD	11,700	11,700
⊛ 44000600	SIDEWALK REMOVAL	SQFT	50	50
⊛ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200
⊛ 44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQYD	300	300
⊛ 44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQYD	300	300
⊛ 60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8
⊛ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	19	19
⊛ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
⊛ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67100100	MOBILIZATION	L SUM	1	1
⊛ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
⊛ 70300100	SHORT TERM PAVEMENT MARKING	FOOT	500	500
★ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	110	110
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,500	4,500
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	825	825
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80	80
⊛ ★ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	200	200
⊛ X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	700	700

- ★ DENOTES SPECIALTY ITEM
- ⊛ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\74009075 - Thatcher Ave\Summary.dwg Jun 02, 2009 - 11:15am



USER NAME	DESIGNED CH	REVISED
	DRAWN MK	REVISED
PLOT SCALE	CHECKED CH	REVISED
PLOT DATE	DATE 4-21-09	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2753	09-00089-00-RS	COOK	15	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63215	
			ARA-9003(349)	