

# EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
<b>STAGE I TRAFFIC</b>				
1112 + 49 - 1115 + 00	75	56	761	-705
1115 + 00 - 1116 + 12	34	25	131	-106
<b>UPSTREAM (LT)</b>				
1111 + 50 - 1115 + 00	1098	824	50	774
1115 + 00 - 1118 + 76	752	564	11	553
<b>STAGE II TRAFFIC</b>				
1112 + 49 - 1115 + 00	83	62	403	-341
1115 + 00 - 1116 + 12	34	25	25	0
<b>DOWNSTREAM (RT)</b>				
1111 + 50 - 1115 + 00	366	275	69	206
1115 + 00 - 1118 + 76	161	121	314	-193
<b>TOTALS</b>	2603	1952	1764	188