

SUMMARY OF QUANTITIES

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60 (IL Modified). See Special Provisions

Reinforcement bars designated (E) shall be epoxy coated.

The Contractor will submit to the Engineer a satisfactory progress schedule and critical path schedule which shall show the proposed sequence of work at the time of the pre-construction conference.

**100% STATE SFTY-2A
KNOX COUNTY**

CODE NO.	ITEM	UNIT	URBAN	TOTAL
50102400	CONCRETE REMOVAL	CUYD	4.3	4.3
50300255	CONCRETE SUPERSTRUCTURE	CUYD	4.3	4.3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	29,440	29,440
50501110	STRUCTURAL STEEL REMOVAL	POUND	27,740	27,740
67100100	MOBILIZATION	LSUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	LSUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	LSUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2600	2600
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	867	867
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0003600	BEAM STRAIGHTENING	LSUM	1	1
Z0073300	TEMPORARY SHORING AND CRIBBING	LSUM	1	1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	LSUM	1	1

SN.048-0065 FARNHAM
ST. OVER US34