

COMMITTMENTS

No commitments have been made for this project.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-155	[90-(107,107-2,108)HB]P	TAZEWELL	13	2

GENERAL NOTES

Cleaning & painting of the existing steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All beams, bearings, and all other structural steel shall be cleaned per Near White Blast Cleaning - SSPC SP 10 according to the following schedule.

Bridge 1 - 3 - Entire Structure

The designated paint system shall be Paint System 5 - MCU.
The final finish coat for the interior and exterior shall be according to the following schedule:

Bridge No. 1 - 3 - Paint system 5 shall be used and all exterior fascias including the bottom of the bottom flanges shall be blue (Munsell No. 10B 36). All of the underside shall be painted Light Gray (Munsell No. 5B 71).

QP1 IS REQUIRED FOR THIS CONTRACT.

AIR MONITORS - None for this project

**COMMITMENTS &
GENERAL NOTES**