

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY F.A.U. 8012 80% FEDERAL 20% STATE		STRUCTURE 80% FEDERAL 20% STATE	
				CONSTRUCTION TYPE CODE		CONSTRUCTION TYPE CODE	
				1000-2A		X028-2A	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	180	180			
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1			
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1			
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2800	2800			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	160	160			
73400100	CONCRETE FOUNDATIONS	CU YD	4.5	4.5			
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2	2			
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	180	180			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2			
XX004094	CONCRETE SLOPEWALL	SQ FT	1785	1785			
X0323665	RIPRAP SLURRY	SQ. YD	82	82			
X0323716	ACCESS GATE, DOUBLE, 30 FOOT	EACH	1	1			
X0324118	GRANULAR CULVERT BACKFILL	CU YD	716			716	
X0325129	TREE REMOVAL	L SUM	1	1			
X0325368	TRENCHLESS PIPE INSTALLATION, 60"	FOOT	224	224			
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1			
Z0005000	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (COLD MIX)	TON	20	20			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.8		0.2	
Z0022800	FENCE REMOVAL	FOOT	2452	2452			
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2			
Z0041500	PLUG EXISTING CULVERTS	EACH	1	1			
<del>Z0048665</del>	<del>RAILROAD PROTECTIVE LIABILITY INSURANCE</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>			
* Z0054517	ROCKFILL - FOUNDATION	TON	92			92	
Z0056100	SAND DRAINAGE BLANKET	CU YD	64			64	
X0326651	MANHOLES, TYPE A, SPECIAL, 9' DIAMETER, WITH MEDIAN INLET (604106)	EACH	2	2			
XX004829	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12", SPECIAL	EACH	1	1			
X0326652	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24", SPECIAL	EACH	1	1			
X0326653	PAVED DITCH (SPECIAL)	SQ YD	1145	1145			

\* SPECIALTY ITEMS

Rev. 7-15-09

FILE NAME =  
c:\pwork\PIW007\LAUGHLIN\081435870

USER NAME = laughlinr1  
722802-shr-500.dgn  
PLOT SCALE = 2.800' / IN.  
PLOT DATE = May-29-2009 07:50:45AM

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -



Allen Henderson & Associates, Inc.  
Civil and Structural Engineers Springfield, IL  
62703 Phone: (217)544-8083 IL Design Firm  
No. 184-001907

SCHEDULE OF QUANTITIES  
SCALE: SHEET NO. 4 OF 147 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	210-31	SANGAMON	147	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 72A02				