

**SCHEDULE
STONE DUMPED RIPRAP & FILTER FABRIC**

LOCATION	STONE DUMPED RIPRAP CLASS A3 (TON)	STONE DUMPED RIPRAP CLASS A4 (TON)	FILTER FABRIC (SQ. YD.)
WABASH AVE. - (STA. 398+25 (N. END ONLY)		33	49
WATERWAY NO. 1 (STA. 10+80 TO STA. 23+95)	1618	632	2229
I-72 (STA. 387+00 TO STA. 406+25)	3041	90	3106
RAMP A BOX CULVERTS		60	50
SLOPEWALL AREA		87	
WEIR (DOWNSTREAM SIDE) & S.E. ACCESS ROAD	441		91
TOTAL	5100	902	5525

**SCHEDULE
CONCRETE STRUCTURES, FOUNDATIONS & REINFORCEMENT BARS**

LOCATION	CONCRETE STRUCTURES (CU. YD.)	CONCRETE FOUNDATIONS (CU. YD.)	REINFORCEMENT BARS (POUND)	REINFORCEMENT BARS (EPOXY COATED) (POUND)
I-72 - CONCRETE DROP BOX	10.7		1550	
WEIR	65.1		7925	3195
SIGN CONCRETE FOUNDATIONS STA. 395+05 LT.		4.5	260	
TOTAL	75.8	4.5	9735	3195

**SCHEDULE
AGGREGATE SURFACE COURSE, TYPE B**

LOCATION	QUANTITY (TON)
STA. 500+00 TO STA. 506+45 (E. ACCESS ROAD)	325
STA. 101+47 TO STA. 107+80 (S. ACCESS ROAD)	358
STA. 398+05 TO STA. 398+45 (WABASH AVE.)	6
TOTAL	689

**SCHEDULE
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"**

LOCATION	QUANTITY (SQ. YD.)
STA. 17+83 LT. & RT. (ASH GROVE)	78
STA. 504+55 TO STA. 505+35 (E. ACCESS ROAD)	214
F.E. STA. 398+70 RT. (WABASH AVE.)	92
TOTAL	384

**SCHEDULE
PORTLAND CEMENT CONCRETE SIDEWALK, 4"**

LOCATION	QUANTITY (SQ. FT.)
STA. 397+95 TO STA. 403+93 RT. (WABASH AVE.)	3092
STA. 17+25 TO STA. 17+95 LT. & RT. (ASH GROVE ROAD)	560
TOTAL	3652

**SCHEDULE
PAVED DITCH REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 387+87 TO STA. 389+47 167' LT. (I-72)	160
TOTAL	160

**SCHEDULE
PAVEMENT REMOVAL**

LOCATION	QUANTITY (SQ. YD.)
STA. 397+30 TO STA. 398+44 (OLD BUNKER HILL RD.)	243
STA. 398+05 TO STA. 398+45 (WABASH AVE.)	160
STA. 17+25 TO STA. 17+63 (ASH GROVE DR.)	114
TOTAL	517

**SCHEDULE
SIDEWALK REMOVAL**

LOCATION	QUANTITY (SQ. FT.)
STA. 397+95 TO STA. 403+93.3 RT. (WABASH AVE.)	3112
STA. 17+25 TO STA. 17+95 LT. & RT. (ASH GROVE DR.)	560
TOTAL	3672

**SCHEDULE
*ESTIMATED QUANTITIES FOR FIELD TILES**

LOCATION	EXPLORATORY TRENCH 72" (FOOT)	MISC. CONCRETE (CU. YD.)	FIELD TILE JUNCTION VAULTS, 2' DIA. (EACH)	STORM SEWER PROTECTED CLASS A 8" (FOOT)	STORM SEWER PROTECTED CLASS A 10" (FOOT)	STORM SEWER PROTECTED CLASS A 12" (FOOT)	PIPE DRAINS 8" (FOOT)	PIPE DRAINS 10" (FOOT)	PIPE DRAINS 12" (FOOT)	TRENCH BACKFILL (CU. YD.)
ALL FIELD TILE LOCATIONS	500	10	4	100	100	100	100	100	100	10
TOTAL	500	10	4	100	100	100	100	100	100	10

* THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HANDLING FIELD TILES ADJACENT TO I-72 DITCHES AND ACROSS DETENTION AREA ACCESS ROAD. (SEE SPECIAL PROVISIONS)

**SCHEDULE
PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL EQUIVALENT ROUND SIZE 42" & FLARED END SECTIONS EQUIVALENT ROUND SIZE 42"**

LOCATION	EQ. ROUND SIZE 42" (FOOT)	END SECTION EQ. ROUND SIZE 42" (EACH)
STA. 388+08 TO STA. 388+58 LT. (I-72)	50	2
TOTAL	50	2

**SCHEDULE
REMOVE CONCRETE FOUNDATION - GROUND MOUNT**

LOCATION	QUANTITY (EACH)
STA. 395+05 101' LT.	1
STA. 395+05 111' LT.	1
TOTAL	2

**SCHEDULE
PRECAST REINFORCED CONCRETE FLARED END SECTIONS SPECIAL**

LOCATION	12" (EACH)	24" (EACH)
STA. 7+02 30' RT. RAMP A	1	
STA. 12+59 30' RT. RAMP A		1
TOTAL	1	1

**SCHEDULE
COMBINATION CURB & GUTTER REMOVAL AND REPLACEMENT**

LOCATION	QUANTITY (FOOT)
STA. 17+25 TO STA. 18+05 LT. & RT. (ASH GROVE)	160
TOTAL	160

**SCHEDULE
ACCESS GATE DOUBLE 30 FOOT**

LOCATION	QUANTITY (EACH)
STA. 502+50 (E. ACCESS ROAD)	1
TOTAL	1

**SCHEDULE
CONCRETE SLOPEWALL**

LOCATION	QUANTITY (SQ. FT.)
STA. 504+55 TO STA. 505+35 LT.	1785
TOTAL	1785

**SCHEDULE
WOVEN WIRE FENCE 4"**

LOCATION	QUANTITY (FOOT)
STA. 387+90.76 150.53' LT. TO STA. 406+00 125' LT. (I-72)	1837
STA. 500+18 13' LT. TO STA. 509+00 17' LT. (E. ACCESS ROAD)	888
STA. 502+50 17' LT. TO 15' LT.	2
STA. 502+50 15' RT. (E. ACCESS ROAD) TO STA. 199+60 60' RT. (S.E. ACCESS ROAD)	1187
STA. 200+25 23' RT. (S.E. ACCESS ROAD) TO STA. 421+76.96 95.1' RT. (I-72)	1336
TOTAL	5250

**SCHEDULE
REMOVE SIGN PANEL ASSEMBLY - TYPE B & RELOCATE SIGN PANEL ASSEMBLY - TYPE B**

LOCATION	QUANTITY (EACH)
STA. 395+00 102' LT. TO STA. 395+00 106' LT. (I-72)	1
TOTAL	1

**SCHEDULE
CLASS D PATCHES, TYPE IV, 14"**

LOCATION	QUANTITY (SQ. YD.)
STA. 398+05 TO STA. 398+45 (WABASH AVE.)	200
TOTAL	200

**SCHEDULE
CLASS D PATCHES, TYPE IV, 10"**

LOCATION	QUANTITY (SQ. YD.)
STA. 17+25 TO STA. 17+63 (ASH GROVE DR.)	114
TOTAL	114

**SCHEDULE
FENCE REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 387+25 TO STA. 402+87 LT. (I-72)	1562
STA. 500+18 13' LT. TO STA. 509+00 15' LT. (E. ACCESS ROAD)	890
TOTAL	2452

**SCHEDULE
FILLING EXISTING CULVERTS**

LOCATION	QUANTITY (EACH)
φ STA. 399+95, 24" x 82" R.C.C.P./PLASTIC (WABASH AVE.)	2
TOTAL	2

**SCHEDULE
PLUG EXISTING CULVERTS**

LOCATION	QUANTITY (EACH)
STA. 18+85 ELLIPTICAL 5' X 40' (ASH GROVE ROAD)	1
TOTAL	1

FILE NAME = c:\pwork\pwork\WIDOT\LAUGHLIN\08143507\72A02-sh1-schedule.dgn
USER NAME = laughtl1n1
DESIGNED -
DRAWN -
CHECKED -
DATE -

72A02-sh1-schedule.dgn
PLOT SCALE = 2.000 / 1 IN.
PLOT DATE = May-29-2009 07:50:47AM

REVISED -
REVISED -
REVISED -
REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907



SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 6 OF 147 SHEETS STA. TO STA.

F.A.U. RTE. 8012 SECTION 21(I-3) COUNTY SANGAMON TOTAL SHEETS 147 SHEET NO. 6 CONTRACT NO. 72A02
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT