



Note: Order bars full length. Lay out in field as shown. Cut along cut line. Use remainder of v_1 in opposite wing wall.



Note: Order bars full length. Lay out in field as shown. Cut along cut line. Use remainder of v2 in opposite wing wall.



Note: Order bars full length. Lay out in field as shown. Cut along cut line. Use remainder of v3 in opposite wing wall.

TWO END SECTIONS BILL OF MATERIAL

DILL OF WATERIAL										
Bar	No.	Size	Length	Shape						
ь	7	#4	24'-6"							
b ₁	12	#4	16'-0''							
d	<i>2</i> 7	#4	5'-4''							
d ₁	11	#4	4'-8''							
h	1	#5	29′-8′′							
h1	10	#5	9′-8′′							
h2	1	#5	18'-4"							
h3	12	#5	11′-5′′							
h4	6	#5	11'-5'' 4'-0"							
h 5	3	#5	16'-0''							
S	4	#5	36′-9′′							
v	44	#5	5′-10′′							
v 1	10	<i>#5</i>	10'-8''							
v 2	4	#5	12'-6"							
V3	8	#5	10'-8" 12'-6" 8'-2"							
₹4	22	#5	5′-1″							
Concrete	Box Culve	Cu. Yd.	22.0							
Reinforce	ement Bar	Pound	1511							

(Bill of Material for information only. Concrete and reinforcement included with Box Culvert End Sections.)

2'-0" BAR h3 BAR ha

CULVERT DETAILS
WABASH AVENUE OVER
WATERWAY NO. 1
STA. 398+25.00
SANGAMON COUNTY

Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL. Design Firm No. 184-001907

9-10''

BAR s

SHEET NO. 3 5 SHEETS

BARS V & V4

F.A.U. RTE.	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.		
8012	21(I-3)				SANGAMON	147	59	
						CONTRACT	NO. 72	A02
FED. RO	DAD DIST.	NO.	ILLINOIS	FED.	ΑI	D PROJECT		