

PAVING SCHEDULE							
LOCATION	PAVEMENT WIDTH (FOOT)	HMA SURF REM 1 1/2" (SQ YD)	HMA SURF REM BT JT (SQ YD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	SURFACE N50 (TON)	INCIDENTAL HMA SURF (TON)
BL-55 MAINLINE							
STA 87+13.29 TO STA 87+80.89	64	480.71		0.18	0.96	40.38	
STA 87+80.89 TO STA 91+24.36	53	2,022.66		0.77	4.05	169.90	
STA 91+24.36 TO STA 91+73.90	53 TO 46	272.47		0.10	0.54	22.89	
STA 91+73.90 TO STA 103+29.64	46	5,907.12		2.24	11.81	496.20	
STA 103+29.64 TO STA 104+59.39	46 TO 38	605.50		0.23	1.21	50.86	
STA 104+59.39 TO STA 132+83.08	38	11,922.25		4.53	23.84	1,001.47	
STA 132+83.08 TO STA 134+33.38	38 TO 68	885.10		0.34	1.77	74.35	
STA 134+33.38 TO STA 135+41.72	68	818.57		0.31	1.64	68.76	
SIDE STREETS							
BLACK (LT)			37.39	0.01	0.07		3.14
BLACK (RT)			35.26	0.01	0.07		2.96
PEORIA RD (LT)			52.85	0.02	0.11		4.44
RIDGELY (LT)			57.24	0.02	0.11		4.81
RIDGELY (RT)			64.39	0.02	0.13		5.41
WOOD / 10TH (LT)			108.23	0.04	0.22		9.09
GARFIELD / ELIZABETH (LT)			110.69	0.04	0.22		9.30
GRIFFITHS / 11TH (LT)			120.69	0.05	0.24		10.14
PERCY (LT)			35.88	0.01	0.07		3.01
JOLES (LT)			40.37	0.02	0.08		3.39
TOTALS		22,914	663	8.9	47	1,925	56

TEMPORARY RAMPS		
LOCATION	PAVEMENT WIDTH (FOOT)	(SQ YD)
BL-55 MAINLINE		
STA 87+13.29 TO STA 87+18.29	64	35.56
STA 135+36.72 TO STA 135+41.72	68	37.78
SIDE STREETS		
CONVERSE (LT)	52	28.89
CONVERSE (RT)	52	28.89
BLACK (LT)	32	17.78
BLACK (RT)	30	16.67
PEORIA RD (LT)	41	22.78
RIDGELY (LT)	48	26.67
RIDGELY (RT)	52	28.89
WOOD / 10TH (LT)	96	53.33
GARFIELD / ELIZABETH (LT)	98	54.44
GRIFFITHS / 11TH (LT)	93	51.67
PERCY (LT)	29	16.11
JOLES (LT)	31	17.22
TOTALS		437

CCC&G REMOVAL AND REPLACEMENT			
LOCATION			FOOT
BUSINESS 55			
CONVERSE AVE TO RR VIADUCT			
NB STA 87+37 TO STA 93+83			196
SB STA 87+37 TO STA 93+83			189
RR VIADUCT TO BLACK AVE			
NB STA 93+83 TO STA 99+56			108
SB STA 93+83 TO STA 99+56			108
BLACK AVE TO N PEORIA RD			
NB STA 99+56 TO STA 101+77			7
SB STA 99+56 TO STA 101+77			0
TOTAL			608

FRAMES AND LIDS TO BE ADJUSTED	
LOCATION	EACH
BUSINESS 55	
JOBSITE	14
TOTAL	14

SIDEWALK RAMPS	SIDEWALK REMOVAL SQ FT	DRIVEWAY PAVEMENT REMOVAL SQ YD	CCC&G REMOVAL & REPLACEMENT FOOT	PCC SIDEWALK 4 INCH SQ FT	DETECTABLE WARNINGS SQ FT
BUSINESS 55					
RT STA 102+48. TO STA 102+63.24	39.9	1.0		39.9	8.0
RT STA 102+78. TO STA 102+86.70	31.0	1.0		31.0	8.0
RT STA 103+20. TO STA 103+33.95	44.2	1.0		44.2	8.0
RT STA 103+70. TO STA 103+83.91	44.0	1.0		44.0	8.0
LT STA 104+24.5 TO STA 104+33.05	28.3		7.0	35.5	8.0
RT STA 105+27.7 TO STA 105+39.70	60.0		10.0	60.0	8.0
TOTAL	247	4	17	255	48

PAVEMENT PATCHING			
LOCATION	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD
BUSINESS 55			
BLACK AVE TO RIDGLEY AVE			
NB STA 99+56 TO STA 104+81	0.0	0.0	0.0
SB STA 99+56 TO STA 104+81	0.0	0.0	81.0
RIDGLEY AVE TO GARFIELD ST			
NB STA 104+81 TO STA 114+00	13.5	22.5	112.5
SB STA 104+81 TO STA 114+00	0.0	0.0	72.0
GARFIELD ST TO GRIFFITHS ST			
NB STA 114+00 TO STA 120+84	0.0	60.0	36.0
SB STA 114+00 TO STA 120+84	0.0	60.0	0.0
GRIFFITHS TO PERCY ST			
NB STA 120+84 TO STA 129+50	0.0	27.0	0.0
SB STA 120+84 TO STA 129+50	0.0	30.0	90.0
PERCY ST TO SANGAMON AVE			
NB STA 129+50 TO STA 135+41	15.0	22.5	0.0
SB STA 129+50 TO STA 135+41	15.0	0.0	135.0
TOTALS	44	222	527