

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LOCATION OF WORK			<i>URBAN</i>	I - 72 90% FED / 10% STATE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY-4A
20200100	EARTH EXCAVATION	CU YD	808.0	808.0
20400800	FURNISHED EXCAVATION	CU YD	4,386.0	4,386.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	675.0	675.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	675.0	675.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	675.0	675.0
25000200	SEEDING, CLASS 2	ACRE	7.6	7.6
25100125	MULCH, METHOD 3	ACRE	15.2	15.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	760.0	760.0
28000500	INLET AND PIPE PROTECTION	EACH	16.0	16.0
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	301.0	301.0
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	14,346.0	14,346.0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	8.0	8.0
54202965	PIPE CULVERTS, TYPE 4 RCCP 30"	FOOT	8.0	8.0
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1.0	1.0
54248515	CONCRETE COLLAR	EACH	1.0	1.0
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2,150.0	2,150.0
70100825	TRAFFIC CONTROL AND PROTECTION, STANARD 701456	L SUM	1	1

Rev.

FILE NAME =	USER NAME = laughlinr1	DESIGNED - BKL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\WIDOT\LAUGHLINRL\d0128581\72C77-shr-500.dgn		DRAWN - BKL	REVISED -			72	*	SANGAMON	100	3
PLOT SCALE = 100.0000 "/ IN.		CHECKED - JPM	REVISED -		SCALE: N.A.					
PLOT DATE = May-07-2009 09:11:31AM		DATE - 04/10/09	REVISED -		SHEET NO. OF SHEETS STA. TO STA.					
										CONTRACT NO. 72C77