

48101498	AGGREGATE SHOULDERS, TYPE B 4"						SQ YD
XX003301	GEOTEXTILE FILTER FABRIC						SQ YD
LOCATION	STATION	TO	STATION		LENGTH	WIDTH	QUANTITY
I-72	RT. STA. 601+15.	TO	RT. STA. 603+37.48		222.7	4.0	99.0
I-72	RT. STA. 665+00.	TO	RT. STA. 669+54.32		454.3	4.0	202
TOTAL							301

48203013	HOT-MIX ASPHALT SHOULDERS, 4"						SQ YD
LOCATION	STATION	TO	STATION				QUANTITY
I-72	RT. STA. 479+50.	TO	RT. STA. 545+63.92				4,522
I-72	RT. STA. 546+69.1	TO	RT. STA. 556+00.				702
I-72	RT. STA. 594+50.	TO	RT. STA. 601+15.				625
I-72	RT. STA. 609+55.	TO	RT. STA. 619+50.				691
I-72	RT. STA. 646+50.	TO	RT. STA. 665+00				1,565
I-72	LT. STA. 554+50.	TO	LT. STA. 598+00.				3,949
I-72	LT. STA. 618+50.	TO	LT. STA. 639+88.				1,954
I-72	LT. STA. 641+02.	TO	LT. STA. 649+50				338
TOTAL							14,346

54002020	EXPANSION BOLTS 3/4 INCH						EACH
54202965	PIPE CULVERTS, TYPE 4 RCCP 30"						FOOT
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"						EACH
54248515	CONCRETE COLLAR						EACH
LOCATION	STATION		EXPANSION BOLTS (EACH)	30" PIPE CULVERT (FEET)	30" FLARED END SECTION (EACH)	CONCRETE COLLAR (EACH)	
I-72	RT 662+00		8	8	1	1	
TOTAL			8	8	1	1	

63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS						FOOT
78200405	GUARDRAIL MARKERS						EACH
LOCATION	STATION	TO	STATION		QUANTITY (FOOT)	QUANTITY (EACH)	
I-72	RT. STA. 598+06.63	TO	RT. STA. 603+33.9		525.0	7	
I-72	LT. STA. 597+87.21	TO	LT. STA. 607+17.9		912.5	11	
6TH ST SE RAMP	LT. STA. 7+08.3	TO	LT. STA. 8+78.60		187.5	2	
6TH ST SW RAMP	LT. STA. 4+65.5		LT. STA. 11+46		525.0	7	
TOTAL					2,150.0	27	

63100085	TRAFFIC BARRIER TERMINAL, TYPE 6						EACH	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT						EACH	
X6330115	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) REMOVE AND RELOCATE						EACH	
78201000	TERMINAL MARKER - DIRECT APPLIED						EACH	
LOCATION	STATION	TO	STATION		TYPE 6 QUANTITY (EACH)	TYPE 1 TANGENT QUANTITY (EACH)	TYPE 1 REM/REPL QUANTITY (EACH)	TERMINAL MARKER QUANTITY (EACH)
I-72	RT. STA. 602+84.8	TO	RT. STA. 597+57.6				1.0	
I-72	LT. STA. 607+17.9	TO	LT. STA. 607+61.1		1.0			
6TH ST SE RAMP	LT. STA. 6+60.9	TO	LT. STA. 7+08.3			1.0		1.0
6TH ST SW RAMP	LT. STA. 4+15.5		LT. STA. 4+65.5			1.0		1.0
TOTAL					1.0	2.0	1.0	2.0

X0325231	CABLE GUARD MARKER						EACH
LOCATION	STATION	TO	STATION		LENGTH	QUANTITY	
I-72	RT. STA. 479+50.	TO	RT. STA. 545+63.92		6613.92	165	
I-72	RT. STA. 546+69.1	TO	RT. STA. 556+00.		930.90	23	
I-72	RT. STA. 594+50.	TO	RT. STA. 603+37.5		887.50	22	
I-72	RT. STA. 609+55.	TO	RT. STA. 619+50.		995.00	25	
I-72	RT. STA. 646+50.	TO	RT. STA. 669+54.32		2304.32	58	
I-72	LT. STA. 554+50.	TO	LT. STA. 571+05.03 BK		1605.03	40	
I-72	LT. STA. 569+30.74 AH	TO	LT. STA. 598+00.		2819.26	70	
I-72	LT. STA. 618+50.	TO	LT. STA. 635+79.29 BK		1679.29	42	
I-72	LT. STA. 634+03.49 AH	TO	LT. STA. 639+88.		534.50	13	
I-72	LT. STA. 641+02.	TO	LT. STA. 649+50.		848.00	21	
TOTAL					19217.72	480	

STA EQ. 571+05.03 BK = STA 569+30.74 AH  
 STA EQ. 635+79.29 BK = STA 634+03.49 AH

X0325589	HIGH TENSION CABLE MEDIAN BARRIER						FOOT
LOCATION	STATION	TO	STATION			QUANTITY	
I-72	RT. STA. 480+00.	TO	RT. STA. 545+13.92			6513.92	
I-72	RT. STA. 547+19.08	TO	RT. STA. 555+50.			830.92	
I-72	RT. STA. 595+00.	TO	RT. STA. 602+87.76			787.76	
I-72	RT. STA. 610+05.	TO	RT. STA. 619+00.			895.00	
I-72	RT. STA. 647+00.	TO	RT. STA. 669+04.32			2204.32	
I-72	LT. STA. 555+00.	TO	LT. STA. 571+05.03 BK			1605.03	
I-72	LT. STA. 569+30.74 AH	TO	LT. STA. 597+50			2819.26	
I-72	LT. STA. 619+00.	TO	LT. STA. 635+79.29 BK			1679.29	
I-72	LT. STA. 634+03.49 AH	TO	LT. STA. 639+38.			534.50	
I-72	LT. STA. 641+52.	TO	LT. STA. 649+00.			748.00	
TOTAL						18618.00	

STA EQ. 571+05.03 BK = STA 569+30.74 AH  
 STA EQ. 635+79.29 BK = STA 634+03.49 AH

FILE NAME =	USER NAME = laughlinr1	DESIGNED - BKL	REVISED -
es:\pwork\PIWIDOT\LAUGHLINRL\0128581\0672C77-ah-t-schedule.dgn		DRAWN - BKL	REVISED -
		CHECKED - JPM	REVISED -
		DATE - 04/10/09	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: N.A. SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	SANGAMON	100	8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72C77	