SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY I-70 100% STATE CONSTRUCTION TYPE CODE Y004
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,732	1,732
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	320	320
20100500	TREE REMOVAL, ACRES	ACRE	0.9	0.9
20101000	TEMPORARY FENCE	FOOT	495	495
20400800	FURNISHED EXCAVATION	CU YD	8,898	8,898
25000350	SEEDING, CLASS 7	ACRE	18.9	18.9
25100115	MULCH, METHOD 2	ACRE	18.9	18.9
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,890	1,890
28000400	PERIMETER EROSION BARRIER	FOOT	9,627	9,627
28000510	INLET FILTERS	EACH	34	34
44000100	PAVEMENT REMOVAL	SQ YD	4,822	4,822
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	3,318	3,318
55100300	STORM SEWER REMOVAL 8"	FOOT	13	13
55100500	STORM SEWER REMOVAL 12"	FOOT	140	140
55100700	STORM SEWER REMOVAL 15"	FOOT	189	189
63200310	GUARDRAIL REMOVAL	FOOT	21	21
66410300	CHAIN LINK FENCE REMOVAL	FOOT	234	234
• 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
67201000	SEALING ABANDONED WATER WELLS	EACH	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	4	4
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,000	1,000
X2010505	CLEARING, SPECIAL	L SUM	1	1
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,000	1,000
Z0007606	BUILDING REMOVAL NO. 6	L SUM	1	1
Z0007607	BUILDING REMOVAL NO. 7	L SUM	1	1
Z0007608	BUILDING REMOVAL NO. 8	L SUM	1	1
Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	15,282	15,282

• DENOTES SPECIALTY ITEMS

△ SAFTEY-3N

FILE NAME = $FILEL$
USER NAME = $USER$
PLOT SCALE = $SCALE$
PLOT DATE = $DATE$
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS
DESIGNED - JB REVISED -
DRAWN - JB REVISED -
CHECKED - ACL REVISED -
DATE - 05/15/09 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 1
SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-1DM	ST. CLAIR	41	3

CONTRACT NO. 76C39
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT