

PAVEMENT REPAIR SCHEDULE													
LOCATION			CLASS A PATCH, 15"			CLASS B PATCH, 15"			HMA SURFACE REMOVAL, 5" *	HMA BINDER IL 19, N90	HMA SURFACE, POLY, MIX E, N 90	POLYMERIZED BITUMINOUS MATERIALS, (PRIME COAT)	AGGREGATE (PRIME COAT)
			TYPE I	TYPE II	TYPE III	TYPE I	TYPE II	TYPE III					
MILE MARKER	DIRECTION	LANE	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	GALLON	TON	
19.0	NB	DL					13.3						
19.0	NB	PL				4		100	16.8	11.2	0.063	0.30	
19.0	SB	PL											
19.1	NB	DL					13.3						
19.2	NB	DL						100	16.8	11.2	0.063	0.30	
19.2	SB	DL				4		250	42.0	28.0	0.156	0.75	
19.4	NB	PL						50	8.4	5.6	0.031	0.15	
19.4	SB	DL				4	13.3						
19.5	NB	PL						55	9.2	6.2	0.034	0.17	
19.5	SB	DL											
19.5	SB	PL					13.3						
19.7	SB	PL				4		24					
19.8	NB	PL						75	12.6	8.4	0.047	0.23	
19.9	NB	DL					13.3						
19.9	NB	PL						200	33.6	22.4	0.125	0.60	
20.0	NB	DL						500	84.0	56.0	0.313	1.50	
20.1	NB	DL					13.3						
20.2	NB	DL						100	16.8	11.2	0.063	0.30	
20.2	NB	PL				4		100	16.8	11.2	0.063	0.30	
20.4	NB	DL						75	12.6	8.4	0.047	0.23	
20.5	SB	DL				4							
20.7	NB	PL						75	12.6	8.4	0.047	0.23	
20.7	SB	PL						100	16.8	11.2	0.063	0.30	
20.8	NB	DL						56	9.4	6.3	0.035	0.17	
20.9	NB	PL						50	8.4	5.6	0.031	0.15	
21.3	NB	PL						75	12.6	8.4	0.047	0.23	
21.5	NB	PL						61	10.2	6.8	0.038	0.18	
21.8	SB	DL						50	8.4	5.6	0.031	0.15	
21.8	SB	PL						300	50.4	33.6	0.188	0.90	
22.0	NB	PL						750	126.0	84.0	0.469	2.25	
22.3	NB	DL						75	12.6	8.4	0.047	0.23	
22.4	NB	PL						50	8.4	5.6	0.031	0.15	
22.6	SB	PL						200	33.6	22.4	0.125	0.60	

* ALL REMOVAL SHALL BE FULL LANE WIDTH

FILE NAME =	USER NAME = bergmd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PWIDOT\BERGMD\08120423\0876	94-sht-plan.dgn	DRAWN -	REVISED -			55	60-(1,2,3)I-1	MADISON	14	5	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		CONTRACT NO. 76C94	
	PLOT DATE = 6/25/2009	DATE -	REVISED -								