

PAVEMENT REPAIR SCHEDULE

Location			CLASS A PATCH, 15"			CLASS B PATCH, 15"			HMA SURFACE REMOVAL, 5"	HMA BINDER IL 19, N90	HMA SURFACE, POLY, MIX E, N 90	POLYMERIZED BITUMINOUS MATERIALS, (PRIME COAT)	AGGREGATE (PRIME COAT)
			TYPE I	TYPE II	TYPE III	TYPE I	TYPE II	TYPE III					
Mile Marker	Direction	Lane	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	GALLON	TON	
22.8	SB	DL						100	16.8	11.2	0.063	0.30	
22.8	SB	PL						1000	168.0	112.0	0.626	3.00	
23.0	NB	PL						60	10.1	6.7	0.038	0.18	
23.1	NB	PL						50	8.4	5.6	0.031	0.15	
23.9	NB	PL						50	8.4	5.6	0.031	0.15	
24.0	NB	DL						750	126.0	84.0	0.469	2.25	
24.0	SB	PL						60	10.1	6.7	0.038	0.18	
24.1	SB	DL						200	33.6	22.4	0.125	0.60	
24.6	SB	PL						50	8.4	5.6	0.031	0.15	
24.8	SB	DL						300	50.4	33.6	0.188	0.90	
24.9	SB	PL						55	9.2	6.2	0.034	0.17	
25.0	SB	PL						1000	168.0	112.0	0.626	3.00	
25.2	NB	DL						50	8.4	5.6	0.031	0.15	
25.5	SB	DL						50	8.4	5.6	0.031	0.15	
25.7	NB	DL						400	67.2	44.8	0.250	1.20	
25.8	NB	PL						50	8.4	5.6	0.031	0.15	
25.9	SB	PL						75	12.6	8.4	0.047	0.23	
26.4	SB	DL						300	50.4	33.6	0.188	0.90	
26.4	SB	PL						500	84.0	56.0	0.313	1.50	
26.6	NB	PL						50	8.4	5.6	0.031	0.15	
26.8	NB	DL						100	16.8	11.2	0.063	0.30	
27.0	NB	PL						50	8.4	5.6	0.031	0.15	
27.2	NB	DL						250	42.0	28.0	0.156	0.75	
27.3	SB	PL						200	33.6	22.4	0.125	0.60	
27.5	SB	DL						75	12.6	8.4	0.047	0.23	
27.7	SB	PL						85	14.3	9.5	0.053	0.26	
27.9	NB	PL						50	8.4	5.6	0.031	0.15	
28.0	SB	PL						750	126.0	84.0	0.469	2.25	

* ALL REMOVAL SHALL BE FULL LANE WIDTH

FILE NAME = e:\pwork\p\WIDOT\BERGMD\0120423\d876	USER NAME = bergmd 94-shr-plan.dgn	DESIGNED - ___ DRAWN - ___	REVISED - ___ REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE. 55	SECTION 60-(1,2,3)I-1	COUNTY MADISON	TOTAL SHEETS 14	SHEET NO. 6
PLOT SCALE = 50,000' / IN.		CHECKED - ___	REVISED - ___		SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT					
PLOT DATE = 6/25/2009		DATE - _____	REVISED - ___		CONTRACT NO. 76C94								