

SAWCUT AND REINFORCEMENT SCHEDULE							
LOCATION			SAWCUTS	TIE BARS	DOWEL BARS	PAVEMENT FABRIC	PATCHING REINFORCEMENT
MILE MARKER	DIRECTION	LANE	FT	EACH	EACH	SQ YD	SQ YD
19.0	NB	DL	66		20	13	
19.0	NB	PL	45		20	4	
19.0	SB	PL	90	20	20	24	
19.1	NB	DL	66		20	13	
19.2	NB	DL	90	20	20	24	
19.2	SB	DL	45		20	4	
19.4	NB	PL	90	20	20	24	
19.4	SB	DL	111		40	17	
19.5	SB	DL	90	20	20	24	
19.5	SB	PL	66		20	13	
19.7	SB	PL	135	20	40	28	
19.9	NB	DL	66		20	13	
20.0	NB	DL	90	20	20	24	
20.1	NB	DL	66		20	13	
20.2	NB	PL	45		20	4	
20.5	SB	DL	45		20	4	
33.1	SB	PL	57				4
33.3	NB	PL	78				13
33.6	NB	DL	102	20			24
34.0	SB	DL	57				4
34.1	NB	DL	102	20			24
34.7	SB	PL	78				13
35.3	SB	PL	135				17
35.4	SB	DL	102	20			24
35.9	SB	DL	102	20			24
36.7	NB	DL	135				17
37.5	SB	DL	57				4
37.6	NB	DL	102	20			24
37.8	NB	PL	78				13
38.3	SB	PL	78				13
38.7	SB	PL	102	20			24
39.0	NB	PL	57				4
TOTALS			2627	240	360	248	248