

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, GENERAL NOTES AND HIGHWAY STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4-5 TYPICAL SECTIONS
- 6 SCHEDULES
- 7-8 DETOUR SIGNING
- 9 STAGE CONSTRUCTION
- 10 PLAN SHEET
- 11 PAVEMENT MARKING
- 12 DETAIL SHEET

STANDARDS  
 442001-04  
 701101-02  
 701106-02  
 701400-03  
 701401-05  
 701406-05  
 701426-03  
 701451  
 701901-01  
 780001-02  
 781001-03  
*701454*

COMMITMENTS  
 NONE

GENERAL NOTES

1. THE PIPE UNDERDRAINS SHALL BE CONNECTED TO THE CROSSROAD CULVERTS AS SHOWN ON THE PLANS. PRIOR TO THE START OF THIS WORK, THE METHOD AND CONSTRUCTION OF THIS WORK SHALL BE APPROVED BY THE ENGINEER. ALL WORK TO MAKE THIS CONNECTION SHALL BE INCLUDED IN THE PAY ITEM PIPE UNDERDRAINS 4 INCH.
2. THE COST OF REMOVING THE EXISTING RAISED PAVEMENT MARKERS SHALL BE INCLUDED IN THE PAY ITEM CLASS A PATCHES TYPE IV, 14 INCH.
3. IF ANY SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR RESURFACED OVER. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
4. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - AMEREN IP (GAS & ELECTRIC)
  - AT&T ILLINOIS
  - AT&T CORPORATION
  - CHARTER COMMUNICATIONS (CABLE TV)
  - CITY OF COLLINSVILLE (WATER & SEWER)
  - CITY OF TROY (WATER)

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY \*. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
5. ALL TEMPORARY PAVEMENT MARKINGS WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
6. ONLY NON-CHLORIDE CONCRETE ACCELERATOR WILL BE ACCEPTED ON THIS PROJECT. IF USED, THE ACCELERATOR SHALL MEET THE APPROVAL OF THE ENGINEER PRIOR TO POURING THE CONCRETE.
7. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
8. ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND APPROPRIATE LIGHTS.
9. ALL TRAFFIC CONTROL DEVICES SHALL BE SKID MOUNTED.
10. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND END OF THE PROJECT AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
11. FLAGGERS SHALL BE PRESENT DURING ALL CLOSURE HOURS (INCLUDING LUNCH HOUR) WHEN WORKERS ARE PRESENT. NO ADDITIONAL COMPENSATION SHALL BE APPLIED.

*Rev.*

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, STANDARDS AND COMMITMENTS</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwwork\VPWIDOT\CHALLANDESKE\d0134076	d876d07-ahp-plan.dgn	DRAWN -	REVISED -		70	60-9-I	MADISON	12	2				
	PLOT SCALE = 1/2" = 100' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 76DOT				
	PLOT DATE = 5/14/2009	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								