

25000400 NITROGEN FERTILIZER NUTRIENT		
FERTILIZER CONSTANT:	90	lbs/Acre
SEEDING TYPE	ACRE	LB
CLASS 1	0.48	43
CLASS 2A	0.05	5
TOTAL		48

25000500 PHOSPHORUS FERTILIZER NUTRIENT		
FERTILIZER CONSTANT:	90	lbs/Acre
SEEDING TYPE	ACRE	LB
CLASS 1	0.48	43
CLASS 2A	0.05	5
TOTAL		48

25000600 POTASSIUM FERTILIZER NUTRIENT		
FERTILIZER CONSTANT:	90	lbs/Acre
SEEDING TYPE	ACRE	LB
CLASS 1	0.48	43
CLASS 2A	0.05	5
TOTAL		48

25100630 EROSION CONTROL BLANKET						
STREET	STATION	STATION	OFFSET	SQ FT	ADJUST. FACTOR	SQ. YD.
MANCHESTER ROAD	11+00.00	15+00.00	LT	2028.74	1.00	225.416
	15+00.00	22+80.57	LT	13204.06	1.12	1643.172
	16+00.00	22+22.98	RT	6599.95	1.03	755.328
MANCHESTER ROAD TO FRONT STREET	19+00.00		LT			
		55+25.00	RT	23034.90	1.12	2866.565
WESLEY STREET	40+89.96	42+87.77	LT	2813.37	1.03	321.975
	43+91.99	45+55.33	RT	3079.12	1.03	352.388
WESTERN AVENUE	61+15.77	62+28.31	LT	1181.03	1.00	131.226
	63+22.67	64+70.42	RT	2025.50	1.20	270.067
FRONT STREET	52+43.87	53+85.26	LT	3472.03	1.03	397.355
ILLINOIS PRAIRIE PATH	16+64.54	18+99.93	LT	3428.49	1.20	457.132
	16+64.54	19+18.59	RT	3890.10	1.20	518.680
	16+65.06	19+05.69	LT	1562.70	1.20	208.360
	16+99.97	18+49.93	RT	1127.88	1.20	150.384
			TOTAL			8298.05
			TOTAL (ROUNDED)			8298

25200110 SODDING, SALT TOLERANT							
STREET	STATION	STATION	OFFSET	SQ FT	ADJ. FACTOR	SQ YD	
MANCHESTER ROAD	15+25.00	19+73.00	LT	2588.00	1.00	287.56	
	11+00.00	11+22.64	RT	73.43	1.03	8.40	
	11+12.36	11+54.24	RT	123.94	1.03	14.18	
	11+79.33	12+49.06	RT	226.71	1.03	25.95	
	12+85.15	13+29.43	RT	138.05	1.03	15.80	
	15+20.79	15+99.99	RT	1008.63	1.04	116.55	
	21+91.48	23+02.34	RT	1079.94	1.12	134.39	
	23+07.12	23+29.30	LT	320.72	1.03	36.70	
	23+37.34	24+20.47	RT	479.36	1.03	54.86	
	23+44.30	23+96.50	LT	334.53	1.03	38.29	
	24+21.50	24+33.69	LT	61.88	1.00	6.88	
	24+29.01	24+75.00	LT	185.14	1.00	20.57	
	24+34.47	24+75.00	RT	143.55	1.00	15.95	
	24+58.78	24+75.00	RT	34.91	1.00	3.88	
GABLES BLVD	30+25.00	30+47.50	LT	146.53	1.03	16.77	
	30+25.00	30+39.48	LT	79.47	1.03	9.09	
	30+25.00	30+60.05	RT	281.71	1.01	31.61	
	30+30.14	30+82.59	RT	392.33	1.00	43.59	
	30+82.50	32+21.88	LT	1342.73	1.03	153.67	
	32+09.22	32+28.76	LT	268.21	1.03	30.70	
	31+09.75	32+70.58	RT	2032.40	1.03	232.60	
	WESLEY STREET	43+55.13	43+86.99	RT	1933.68	1.00	214.85
		43+91.99	44+87.62	RT	1242.32	1.03	142.18
		44+70.02	45+11.00	LT	1108.89	1.03	126.91
45+15.00		45+45.07	LT	568.15	1.03	65.02	
44+92.62		45+55.54	RT	819.13	1.03	93.74	
45+57.07		45+93.70	LT	383.00	1.01	42.98	
45+60.54		45+87.10	RT	339.18	1.03	38.82	
45+60.29		45+88.07	RT	151.88	1.03	17.38	
45+99.10		46+17.18	RT	229.21	1.03	26.23	
45+98.79		46+17.43	RT	90.90	1.03	10.40	
45+57.07		45+93.70	LT	253.00	1.03	28.95	
46+07.70		46+40.00	LT	514.00	1.03	58.82	
46+22.18		46+40.00	RT	231.68	1.03	26.51	
46+21.51		46+40.00	RT	87.35	1.03	10.00	
FRONT STREET	50+25.47	52+23.45	RT	1092.31	1.08	131.08	
	50+85.33	51+64.68	LT	1869.47	1.00	207.72	
	52+26.45	54+70.00	RT	1422.81	1.05	166.00	
	52+37.46	53+84.87	LT	783.82	1.03	89.70	
	54+09.19	54+70.00	LT	507.75	1.03	58.11	
	54+09.30	54+27.81	LT	66.56	1.03	7.62	
	54+31.73	54+68.01	LT	151.33	1.03	17.32	
	WESTERN AVENUE	62+28.07	62+71.42	LT	696.40	1.03	79.70
		63+09.48	65+00.00	LT	3045.03	1.03	348.49
		63+22.67	64+77.40	RT	1591.83	1.20	212.24
64+57.54		64+82.05	RT	397.85	1.20	53.05	
64+97.25		65+40.00	LT	151.11	1.00	16.79	
64+87.93		65+19.78	RT	452.17	1.03	51.75	
ILLINOIS PRAIRIE PATH	65+31.78	65+40.00	RT	80.02	1.00	8.89	
ILLINOIS PRAIRIE PATH	15+45.67	15+62.29	CENTER	216.28	1.01	24.27	
	15+65.65	16+63.18	CENTER	1261.93	1.01	141.62	
	15+45.67	16+64.54	RT	4817.00	1.01	540.57	
	15+47.14	16+64.54	LT	3894.96	1.01	437.10	
			TOTAL			4792.81	
			TOTAL (ROUNDED)			4793	

25200200 SUPPLEMENTAL WATERING				
TOTAL SOD AREA SQ YD	RATE GAL/SQ YD	ADDITIONAL WATERINGS	GALLONS	UNIT
4793	3	15	215685.00	215.69
			TOTAL	215.69
			TOTAL (ROUNDED)	215.7

28000250 TEMPORARY EROSION CONTROL SEEDING				
EROSION CONTROL BLANKET	AREA SQ YD	ACRE	POUND	
SODDING, SALT TOLERANT	8298.05	1.71	171.45	
			98.52	
			TOTAL	269.96
			TOTAL (ROUNDED)	270

28000300 TEMPORARY DITCH CHECKS					
STREET	STATION	ELEVATION	OFFSET (FT)	LT/RT	EACH
MANCHESTER ROAD	15+25.00	740.06	24.26'	LT	1
	15+50.00	741.11	28.15'	LT	1
	15+75.00	742.17	27.45'	LT	1
	16+00.00	743.22	33.67'	LT	1
	17+75.00	744.27	31.76'	LT	1
FRONT STREET	19+75.00	745.25	39.16'	LT	1
	22+00.00	745.98	42.96'	LT	1
	50+25.00	745.69'	50.37'	RT	1
Contingency					4
				TOTAL	12

REVISIONS	
NAME	DATE

CITY OF WHEATON
 MANCHESTER ROAD / WESLEY STREET
 OVER UNION PACIFIC RAILROAD
 SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
 DATE 6/4/2008

DRAWN BY DW
 CHECKED BY JLC