

44000300		CURB REMOVAL		
STATION	STATION	LOCATION	LENGTH	
			FT	
<b>MANCHESTER ROAD</b>				
22+26.42	23+79.19	LT	152.77	
22+28.27	24+75.00	RT	246.73	
24+37.59	24+56.30	LT	18.71	
<b>FRONT STREET</b>				
50+99.57	51+60.55	LT	60.98	
<b>WESLEY STREET</b>				
42+61.84	43+15.46	RT	75.00	
<b>WESTERN AVENUE</b>				
60+26.51	60+67.54	LT	41.03	
61+30.95	64+63.62	RT	332.67	
61+50.18	62+58.75	RT (MEDIAN)	114.16	
61+50.18	62+58.75	LT (MEDIAN)	114.74	
62+57.13	62+63.07	LT (DRIVE)	52.38	
62+65.58	62+76.68	LT (DRIVE)	41.48	
63+15.40	63+28.89	LT (DRIVE)	25.55	
63+18.28	64+16.84	RT (MEDIAN)	107.02	
63+18.28	64+16.84	LT (MEDIAN)	107.03	
63+39.94	64+55.97	LT	116.03	
64+92.15	65+40.00	RT	47.85	
65+24.85	65+40.00	LT	15.15	
	TOTAL		1669.28	
	TOTAL (ROUNDED)		1670	

44000500		COMBINATION CURB AND GUTTER REMOVAL		
STATION	STATION	LOCATION	LENGTH	
			FT	
<b>MANCHESTER ROAD</b>				
11+00.00	13+32.05	RT	232.05	
13+32.05	13+62.94	RT (RADIUS)	55.00	
11+00.00	16+50.00	LT	550.00	
16+50.00	20+42.93	LT	392.93	
20+42.93	20+73.15	LT (RADIUS)	45.00	
14+03.72	14+19.87	RT (RADIUS)	20.00	
14+19.87	16+50.00	RT	230.13	
14+21.00	14+75.35	RT (DRIVE)	74.00	
15+06.57	15+32.62	RT (PKLOT)	76.00	
15+11.69	15+16.80	RT (DRIVE)	42.00	
16+57.19	17+05.53	RT (DRIVE)	85.00	
17+28.37	17+59.96	RT (DRIVE)	90.00	
16+50.00	22+22.98	RT	572.98	
22+22.98	22+28.04	RT	5.06	
20+99.74	21+32.84	LT (RADIUS)	48.00	
21+32.84	22+22.98	LT	90.14	
22+22.98	22+26.43	LT	3.45	
23+76.30	23+96.51	LT (DRIVE)	36.00	
23+79.19	24+37.59	LT	58.40	
24+21.89	24+40.44	LT (DRIVE)	32.00	
24+56.30	24+75.00	LT	18.70	
<b>GABLES BOULEVARD</b>				
30+25.00	32+56.56	RT	231.56	
30+72.82	30+86.76	RT (DRIVE)	27.00	
31+09.14	31+20.39	RT (DRIVE)	27.00	
32+00.00	32+55.46	RT (PKLOT)	55.00	
<b>FRONT STREET</b>				
50+05.49	50+28.11	RT (RADIUS)	34.00	
50+28.11	54+70.00	RT	441.89	
52+03.31	52+36.20	LT (RADIUS)	39.00	
52+36.20	54+70.00	LT	233.80	

<b>WESLEY STREET</b>				
43+68.94	46+40.00	RT	271.06	
43+86.35	46+40.00	LT	253.65	
<b>WESTERN AVENUE</b>				
60+15.93	60+52.02	RT	36.09	
60+52.02	60+78.86	RT (RADIUS)	39.00	
60+99.59	61+30.90	RT (RADIUS)	49.00	
61+02.41	61+30.38	LT (RADIUS)	38.00	
61+30.38	63+40.02	LT	209.64	
64+55.97	65+24.85	LT (RADIUS)	54.00	
64+63.61	64+91.78	RT (RADIUS)	47.00	
	TOTAL		4843.53	
	TOTAL (ROUNDED)		4844	

44000600		SIDEWALK REMOVAL		
STATION	STATION	LOCATION	AREA	
			SQ FT	
<b>MANCHESTER ROAD</b>				
11+00.00	11+52.68	RT	349	
11+78.65	12+45.39	RT	323	
12+91.52	13+56.47	RT	316	
14+05.18	14+77.07	RT	385	
15+08.86	16+73.42	RT	781	
17+30.05	22+22.98	RT	2062	
21+00.87	21+23.79	LT	157	
22+22.98	22+99.62	RT	260	
22+80.58	23+93.42	LT	577	
23+35.20	24+75.00	RT	692	
22+79.73	22+98.55	LT	116	
<b>GABLES BOULEVARD</b>				
30+25.00	32+38.10	LT	985	
30+25.00	30+85.53	RT	299	
31+09.47	32+57.25	RT	712	
<b>FRONT STREET</b>				
50+06.00	50+69.04	RT	513	
50+98.92	51+61.31	LT	282	
52+12.79	54+70.00	LT	1124	
<b>WESLEY STREET</b>				
42+61.76	43+16.23	RT	242	
43+51.80	46+40.00	RT	1445	
43+61.30	46+40.00	LT	1310	
<b>WESTERN AVENUE</b>				
60+08.16	60+76.97	RT	356	
61+23.54	62+33.38	RT	666	
61+50.93	62+58.42	Center	507	
63+19.37	64+15.81	Center	476	
64+82.59	65+37.81	RT	321	
64+70.83	65+08.48	LT	85	
62+37.72	62+76.18	LT	189	
<b>IPP</b>				
11+48.42	11+98.04	RT	507	
	TOTAL		16037	

44000700		APPROACH SLAB REMOVAL	
STREET		SQ FT	SQ YD
<b>MANCHESTER/WESLEY (NORTH)</b>			
		952.39	105.82
<b>MANCHESTER/WESLEY (SOUTH)</b>			
		1131.75	125.75
	TOTAL	2084.14	231.57
	TOTAL (ROUNDED)		232

44201383		CLASS C PATCHES, TYPE IV, 12 INCH			
STATION	STATION	WIDTH	AREA		
		FT	SQ FT	SQ YD	
<b>BRIDGE STREET (MANCHESTER ROAD)</b>					
24+75.00	24+83.00	39.00	312.00	34.67	
	TOTAL			34.67	
	TOTAL (ROUNDED)			35	

44201757		CLASS D PATCHES, TYPE III, 9-INCH			
STATION	STATION	WIDTH	AREA		
		FT	SQ FT	SQ YD	
<b>MANCHESTER ROAD</b>					
10+92.00	11+00.00	28.00	224.00	24.89	
<b>FRONT STREET</b>					
54+70.00	54+78.00	22.00	176.00	19.56	
<b>WESLEY STREET</b>					
46+40.00	46+48.00	21.00	168.00	18.67	
<b>WESTERN AVENUE</b>					
65+40.00	65+48.00	23.00	184.00	20.44	
	TOTAL			83.56	
	TOTAL (ROUNDED)			84	

REVISIONS	
NAME	DATE

CITY OF WHEATON  
 MANCHESTER ROAD / WESLEY STREET  
 OVER UNION PACIFIC RAILROAD  
 SCHEDULE OF QUANTITIES

SCALE: VERT.  
 HORIZ.  
 DATE 6/4/2008

DRAWN BY DW  
 CHECKED BY JLC