

67000400	ENGINEER'S FIELD OFFICE, TYPE A		
TOTAL	18	CAL MO	

67000600	ENGINEER'S FIELD LABORATORY		
TOTAL	18	CAL MO	

67100100	MOBILIZATION		
TOTAL	1	LUMP SUM	

70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)		
TOTAL	1	LUMP SUM	

70400100	TEMPORARY CONCRETE BARRIER		
LOCATION	STATION	STATION	LENGTH
			FT
Contingency Item			50.00
		TOTAL	50

70400200	RELOCATE TEMPORARY CONCRETE BARRIER		
LOCATION	STATION	STATION	LENGTH
			FT
Contingency Item			50.00
		TOTAL	50

78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		
INTERSECTION	AREA	DESCRIPTION	
	SQ FT		
WESTERN/FRONT	36.4	1 (ONL Y+ARROW)	
WESLEY/WESTERN(EAST)	46.8	1 (ONL Y+ RIGHT+THROUGH ARROW)	
	36.4	1 (ONL Y+ARROW)	
WESLEY/WESTERN(WEST)	36.4	1 (ONL Y+ARROW)	
TOTAL	156		

78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"			
STATION	STATION	LENGTH	OFFSET	
		FT		
THERMOPLASTIC PAVEMENT MARKING LINE, 4" SOLID DOUBLE YELLOW				
MANCHESTER ROAD				
11+00.00	19+68.00	1736.00		
20+82.89	24+75.00	784.20		
GABLES BOULEVARD				
30+25.00	32+38.86	427.70		
WESLEY STREET				
41+74.20	42+17.57	85.32	RT	
42+17.57	42+78.00	120.90		
42+78.09	43+09.31	62.40	LT	
43+09.29	43+09.31	18.85	LT	
42+17.69	43+09.31	183.20	RT	
WESTERN AVENUE				
61+33.20	65+40.00	813.60		
	SUB TOTAL	4232.17		
THERMOPLASTIC PAVEMENT MARKING LINE, 4" WHITE SKIP 10' DASH, 30' SKIP				
WESLEY STREET				
44+15.24	46+40.00	60.00		
	SUB TOTAL	60.00		
THERMOPLASTIC PAVEMENT MARKING LINE, 4" SOLID SINGLE WHITE				
FRONT STREET				
53+35.13	54+55.15	77.00	RT	
	SUB TOTAL	77.00		
	TOTAL	4369.17		
	TOTAL (ROUNDED)	4369		

78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6 IN		
STATION	STATION	LENGTH	FT
THERMOPLASTIC PAVEMENT MARKING - LINE 6", SOLID WHITE TURN LANE LINES			
WESLEY STREET			
		59.57	
	SUB TOTAL	59.57	
THERMOPLASTIC PAVEMENT MARKING - LINE 6", WHITE CROSSWALK LINES			
GABLES BOULEVARD			
		137.90	
WESLEY STREET			
		45.40	
FRONT STREET			
		33.31	
	SUB TOTAL	216.61	
	TOTAL	276.18	
	TOTAL (ROUNDED)	276	

78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8 IN	
LOCATION	STATION	LENGTH
		FT
WESLEY STREET	43+60.21	73.59
	TOTAL	73.59
	TOTAL (ROUNDED)	74

78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12 IN		
WHITE MEDIAN DIAGONAL STRIPES			
LOCATION	STATION	STATION	LENGTH
			FT
WESLEY STREET	43+46.39	43+53.75	9.39
	43+50.55	43+53.75	5.15
	43+58.32	43+61.29	4.11
	43+59.13	43+61.29	3.13
	SUBTOTAL		22
YELLOW MEDIAN DIAGONAL STRIPES			
WESLEY STREET	42+37.89	42+39.48	2.12
	42+46.40	42+49.46	4.07
	42+55.14	42+59.44	5.71
	42+63.89	42+69.42	7.35
	42+72.63	42+79.39	8.99
	42+82.12	42+89.37	9.65
	42+92.84	42+99.35	8.65
	43+03.57	43+09.33	7.66
	SUBTOTAL		54.20
	TOTAL		75.98
	TOTAL (ROUNDED)		76

REVISIONS	
NAME	DATE

CITY OF WHEATON  
 MANCHESTER ROAD / WESLEY STREET  
 OVER UNION PACIFIC RAILROAD  
 SCHEDULE OF QUANTITIES

SCALE: VERT.      DRAWN BY DW  
 HORIZ.              CHECKED BY JLC  
 DATE 6/4/2008