

X0712400 TEMPORARY PAVEMENT					
STREET	STATION	STATION	SIDE	SQ FT	SQ YD
MANCHESTER ROAD	13+96.12	14+78.25	RT	1699.60	188.84
Contingency					94.42
				TOTAL	284

XX000541 EXPLORATORY EXCAVATION			
LOCATION	STATION	STATION	Volume CY
Estimated Quantity			10
		TOTAL	10

X2110100 TOPSOIL FURNISH AND PLACE, SPECIAL				
	AREA		VOLUME	
	SQ FT	SQ YD	CU YD	
SODDING, SALT TOLERANT		4792.80	532.53	
SEEDING, CLASS 1	19836.08	2204.01	244.89	
SEEDING, CLASS 2A	2028.74	225.42	25.05	
SEEDING, CLASS 3	45583.05	5064.78	562.75	
	TOTAL	12287.01	1365.22	
	TOTAL (ROUNDED)	12288	1366	

XX000714 FENCE TO BE REMOVED AND RE-ERECTED				
STATION	STATION	LOCATION	LENGTH FT	
FRONT STREET	50+69.06	54+70.00	RT	401
		TOTAL	401	

XX005434 WATER SERVICE LINE, SPECIAL				
ADDRESS	MEASUREMENT	FROM	LENGTH FEET	
WESLEY STREET	616 W.	44' N 9' NW corner of the house	50	
619 W.	29' S 16' W	SW corner of the house	20	
622 W.	42' N 7' E	NE corner of the porch	50	
623 W.	34' S 11' E	SE corner of the house	20	
626 W.	38' N	NW corner of the porch	50	
627 W.	32' S 12' W	SW corner of the house	20	
631 W.	43' S 14' E	SE corner of the house	20	
703 W.	87' N 73' E	NE corner of the buildin	20	
FRONT STREET	617 W.	14' S 7' E	SW corner of the house	20
621 W.	25' S 4' W	SW corner of the house	20	
BRIDGE STREET	100	34' E 62' S	NE corner of the buildin	20
101	32' W 12' N	SW corner of the house	45	
105	43' W 3' S	SW corner of the house	45	
	TOTAL		400	

XX002012 RELOCATE SIGN, SPECIAL		
LOCATION		EACH
Manchester Road/Gables BLVD		1
	Total	1

X5640175 FIRE HYDRANT COMPLETE				
STATION	OFFSET	LT/RT	EACH	
MANCHESTER ROAD/BRIDGE STREET	22+80.00	30'	RT	1
WESLEY STREET	44+85.00	25'	LT	1
WESTERN AVE	63+35.00	18'	LT	1
	TOTAL		3	

XXXXXXX DUCTILE IRON WATER MAIN, 12" CLASS 52, WITH POLYETHYLENE ENCASEMENT			
STATION	STATION	LENGTH FT	
Western Ave	60+00.00	61+10.00	120
Front Street	52+10.00	54+70.00	260
	TOTAL	380	

XX005463 ADJUST FIRE HYDRANT WITH AUXILIARY VALVE				
STATION	OFFSET	LT/RT	EACH	
FRONT STREET	54+53.00	19'	LT	1
	TOTAL		1	

XX000052 REMOVE EXISTING WATERMAIN				
STATION	STATION	LOCATION	LENGTH FT	
Manchester Road/Bridge Street	22+67.00	23+64.00	RT	105.00
Western Ave	61+05.00	64+80.00	LT	400.00
	60+00.00	61+05.63	RT	115.00
Wesley Street	43+54.25	46+40.00	LT	290.00
Front Street	52+10.00	54+70.00	LT	260.00
Connections to Hydrants				50.00
	TOTAL		1220	

XXXXXXX DUCTILE IRON WATER MAIN, 8" CLASS 52, WITH POLYETHYLENE ENCASEMENT			
STATION	STATION	LENGTH FT	
Manchester Road/Bridge Street	22+67.00	23+64.00	105
Western Ave	61+10.00	64+80.00	385
Wesley Street	43+31.00	46+40.00	310
	TOTAL	800	

REVISIONS	
NAME	DATE

CITY OF WHEATON
 MANCHESTER ROAD / WESLEY STREET
 OVER UNION PACIFIC RAILROAD
 SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE 6/4/2008

DRAWN BY DW
 CHECKED BY JLC