F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	97-00084-00-BR	DU PAGE	241	50
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83908

N

20 0 20 40 60 80 100
SCALE IN FEET

2 STORY FRAME RESIDENCE
INSTALL 8" WATER VALVE
CONNECTION TO EXISTING WATER MAINS (NON PRESSURE)
GAS PAINT MARKER
FRAME GARAGE
1 STORY FRAME BUILDING
PROP. UTILITY RISERS
8" PVC
CONCRETE WALK
PT STA 65+42.50
PC STA 65+72.50
PROP. ℄ WESTERN AVE.
WESTERN AVE.
EXIST. EOW
8FT
POT STA 65+94.14
6" VCP
2 STORY FRAME RESIDENCE
PROP. 2 - 6" POLY BY CUST
FIRE HYDRANTS TO BE REMOVED
DUCTILE IRON WATER MAIN, 8" CLASS 52, WITH POLYETHYLENE ENCASEMENT
FIRE HYDRANT COMPLETE
11FT
EXIST. 40W
PROP. UTILITY RISERS
MONITORING WELL
COMCAST HANDHOLE
TEMP EASEMENT
MONITORING WELL
PROP. ℄ WESTERN AVE.
CONCRETE WALK
9FT
PROP. 2 - 6" POLY BY CUST
PROP. 2 - 6" PLASTIC CONDUIT
MATCH LINE 61+45

LEGEND

- T—T— TELEPHONE
- CTV—CTV— CABLE TELEVISION
- E—E— ELECTRIC
- G— GAS PIPE
- WATER PIPE
- FO—FO— FIBER OPTIC
- SANITARY SEWER
- STORM SEWER
- EXISTING UTILITY REMOVAL
- UTILITY RISER
- MANHOLE
- LIGHT POLE
- FIRE HYDRANT

SHEET 5 OF 5

REVISIONS NAME	DATE

CITY OF WHEATON

MANCHESTER ROAD / WESLEY STREET
OVER UNION PACIFIC RAILROAD

EXISTING AND PROPOSED
UTILITIES PLAN

SCALE: VERT.
HORIZ. 1" = 20'
DATE 6/4/2008

DRAWN BY DWW
CHECKED BY VVS