

SCHEDULE OF QUANTITIES

20101000		TEMPORARY FENCE							
	EQUI	LOCATION		REMARKS					
122	LT. STA.	633 + 18	TO	634 + 40	Along Harrod property line				
217	LT. STA.	666 + 64	TO	667 + 84	Along wetland boundary & construction limits within Existing R.O.W.				
178	RT. STA.	37 + 37	TO	39 + 34	Cartwright Ln. - Along Harrod construction limits and temporary easement				
517	TOTAL								

20101100		TREE TRUNK PROTECTION							
	EACH	LOCATION		REMARKS					
1		608 + 93	at	40.1' LT					
1		611 + 0	at	52.2' LT					
1		611 + 11	at	52.4' LT					
1		618 + 43	at	60.4' LT					
1		618 + 53	at	72.6' LT					
1		637 + 97	at	68.2' RT					
1		637 + 94	at	65.6' RT					
1		662 + 20	at	79.2' LT					
1		662 + 23	at	100.7' LT					
1		662 + 30	at	101.5' LT					
1		662 + 31	at	77.0' LT					
1		662 + 35	at	84.7' LT					
1		Margaret Fuller Dr.							
1		17 + 54	at	38.7' LT					
1		Cartwright Ln.							
1		38 + 90	at	57.4' RT					
1		39 + 26	at	58.4' RT					
1		Access Rd. "A"							
1		47 + 40	at	18.49' RT					
1		47 + 55	at	29.8' RT					
1		48 + 56	at	44.7' LT					
1		Cultra Rd.							
1		60 + 65	at	44.3' LT					
1		60 + 65	at	40.3' LT					
1		60 + 67	at	47.8' LT					
1		60 + 67	at	58.1' LT					
1		60 + 76	at	34.3' LT					
77	TOTAL		Various Locations on Jobsite						
100	TOTAL		Determined by the IDOT Landscape Architect						

25000775		SELECTIVE MOWING STAKES							
	EACH	LOCATION		REMARKS					
30		654 + 50	TO	662 + 0					
48		663 + 50	TO	675 + 50					
24		678 + 0	TO	684 + 0					
102	TOTAL								

25100630		EROSION CONTROL BLANKET							
	SQ. YD	LOCATION		REMARKS					
2	RT. STA.	603 + 8			Concrete Headwall for Pipe Drains				
2	RT. STA.	604 + 50			Concrete Headwall for Pipe Drains				
2	RT. STA.	607 + 50			Concrete Headwall for Pipe Drains				
2	RT. STA.	610 + 50			Concrete Headwall for Pipe Drains				
2	LT. STA.	613 + 50			Concrete Headwall for Pipe Drains				
772	LT. STA.	615 + 22	TO	622 + 0	Ditch (12'x579')				
2	LT. STA.	616 + 0			Concrete Headwall for Pipe Drains				
2	LT. STA.	618 + 0			Concrete Headwall for Pipe Drains				
2	LT. STA.	620 + 50			Concrete Headwall for Pipe Drains				
2	LT. STA.	622 + 0			Concrete Headwall for Pipe Drains				
2	RT. STA.	620 + 50			Concrete Headwall for Pipe Drains				
420	LT. STA.	623 + 0	TO	626 + 61	Ditch (12'x315')				
373	LT. STA.	626 + 61	TO	630 + 50	Ditch (12'x280')				
2	RT. STA.	629 + 50			Concrete Headwall for Pipe Drains				
2	RT. STA.	631 + 75			Concrete Headwall for Pipe Drains				
2	RT. STA.	633 + 0			Concrete Headwall for Pipe Drains				
2	LT. STA.	628 + 0			Concrete Headwall for Pipe Drains				
2	LT. STA.	629 + 50			Concrete Headwall for Pipe Drains				
2	LT. STA.	632 + 0			Concrete Headwall for Pipe Drains				
365	LT. STA.	632 + 0	TO	635 + 64	Ditch (12'x274')				
2	LT. STA.	634 + 50			Concrete Headwall for Pipe Drains				
1341	LT. STA.	635 + 64	TO	647 + 0	Ditch (12'x1006')				
2	LT. STA.	636 + 89			Concrete Headwall for Pipe Drains				

2	LT. STA.	638 + 89			Concrete Headwall for Pipe Drains
2	RT. STA.	643 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	646 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	649 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	652 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	654 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	657 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	660 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	663 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	666 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	669 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	672 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	675 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	677 + 50			Concrete Headwall for Pipe Drains
496	LT. STA.	655 + 50	TO	659 + 22	Ditch (12'x372')
2	LT. STA.	656 + 50			Concrete Headwall for Pipe Drains
371	LT. STA.	659 + 22	TO	662 + 0	Ditch (12'x278')
2	LT. STA.	659 + 50			Concrete Headwall for Pipe Drains
2	LT. STA.	662 + 50			Concrete Headwall for Pipe Drains
280	LT. STA.	663 + 0	TO	667 + 20	Ditch (6'x420')
287	LT. STA.	667 + 20	TO	671 + 50	Ditch (6'x430')
49	LT. STA.	675 + 50	TO	676 + 23	Ditch (6'x73')
2	LT. STA.	677 + 50			Concrete Headwall for Pipe Drains
600	LT. STA.	679 + 0	TO	683 + 50	Ditch (12'x450')
2	LT. STA.	679 + 39			Concrete Headwall for Pipe Drains
256	RT. STA.	682 + 50	TO	683 + 50	Foreslope (23'x100')
101	RT. STA.	48 + 74	TO	49 + 50	Access Rd. "A" Ditch (12'x76')
109	LT. STA.	48 + 18	TO	49 + 0	Access Rd. "A" Ditch (12'x82')
600	WINTER SHUTDOWN				
6486	TOTAL				

25100900		TURF REINFORCEMENT MAT							
	SQ. YD	LOCATION		REMARKS					
28.0	RT. STA.	603 + 74	TO	603 + 97	Outlet of CC&G (12'x21')				
276.0	LT. STA.	613 + 15	TO	615 + 22	Outlet of CC&G to AR Culvert+ 615+22 (12'x207')				
52.9	LT. STA.	615 + 22			Drop Box No.1 (17'x28')				
64.0	LT. STA.	626 + 61			Drop Box No.2 (24'x24')				
60.0	LT. STA.	654 + 30			Drop Box No.4 (18'x30')				
50.7	LT. STA.	667 + 20			Drop Box No.5 (24'x19')				
249.3	RT. STA.	17 + 63	TO	19 + 50	Margaret Fuller Rd. Ditch (12'x187')				
249.3	LT. STA.	17 + 63	TO	19 + 50	Margaret Fuller Rd. Ditch (12'x187')				
266.7	RT. STA.	27 + 50	TO	29 + 50	Blackhawk Vista Ditch (12'x200')				
200.0	LT. STA.	27 + 50	TO	29 + 50	Blackhawk Vista Ditch (12'x150')				
208.0	RT. STA.	37 + 42	TO	39 + 50	Cartwright Ln. (12'x156')				
1704.9	TOTAL								

28000300		TEMPORARY DITCH CHECKS							
	EACH	LOCATION		REMARKS					
4	LT. STA.	613 + 0	TO	615 + 22	at 50' ctrs.				
1	LT. STA.	616 + 23	TO	615 + 22					
2	LT. STA.	618 + 35	TO	616 + 75	at 100' ctrs.				
4	LT. STA.	622 + 0	TO	618 + 81	at 100' ctrs.				
3	LT. STA.	623 + 0	TO	625 + 0	at 100' ctrs.				
2	LT. STA.	625 + 52	TO	626 + 61	at 50' ctrs.				
3	LT. STA.	630 + 50	TO	628 + 19	at 100' ctrs.				
3	LT. STA.	632 + 0	TO	634 + 50	at 100' ctrs.				
6	LT. STA.	641 + 37	TO	635 + 63	at 100' ctrs.				
3	LT. STA.	649 + 0	TO	643 + 32	at 100' ctrs.				
4	LT. STA.	655 + 25	TO	659 + 22	at 100' ctrs.				
3	LT. STA.	662 + 50	TO	659 + 22	at 100' ctrs.				
4	LT. STA.	663 + 0	TO	667 + 20	at 100' ctrs.				
4	LT. STA.	667 + 20	TO	671 + 50	at 100' ctrs.				
4	RT. STA.	679 + 0	TO	683 + 50	at 100' ctrs.				
5	RT. STA.	18 + 28	TO	19 + 48	Margaret Fuller Rd. - at 25' ctrs.				
5	LT. STA.	17 + 63	TO	19 + 0	Margaret Fuller Rd. - at 25' ctrs.				
3	RT. STA.	27 + 50	TO	28 + 25	Blackhawk Vista - at 25' ctrs.				
2	LT. STA.	27 + 50	TO	28 + 38	Blackhawk Vista - at 50' ctrs.				
2	RT. STA.	28 + 25	TO	29 + 50	Blackhawk Vista - at 50' ctrs.				
4	RT. STA.	37 + 42	TO	38 + 34	Cartwright Ln. - at 25' ctrs.				
3	RT. STA.	38 + 85	TO	39 + 50	Cartwright Ln. - at 25' ctrs.				
3	LT. STA.	38 + 0	TO	39 + 0	Cartwright Ln. - at 25' ctrs.				
1	LT. STA.	48 + 18	TO	49 + 0	Access Rd. "A"				
2	RT. STA.	48 + 74	TO	49 + 47	Access Rd. "A" - at 25' ctrs.				
8	WINTER SHUTDOWN								
88	TOTAL								

REVISED SHEET 7-15-09