

SCHEDULE OF QUANTITIES

20101000 TEMPORARY FENCE					
EQOI		LOCATION		REMARKS	
122	LT. STA.	633 + 18	TO	634 + 40	Along Harrod property line
217	LT. STA.	666 + 64	TO	667 + 84	Along wetland boundary & construction limits within Existing R.O.W.
178	RT. STA.	37 + 37	TO	39 + 34	Cartwright Ln. - Along Harrod construction limits and temporary easement
517		TOTAL			

20101100 TREE TRUNK PROTECTION					
EACH		LOCATION		REMARKS	
1		608 + 93	at	40.1' LT	
1		611 + 0	at	52.2' LT	
1		611 + 11	at	52.4' LT	
1		618 + 43	at	60.4' LT	
1		618 + 53	at	72.6' LT	
1		637 + 97	at	68.2' RT	
1		637 + 94	at	65.6' RT	
1		662 + 20	at	79.2' LT	
1		662 + 23	at	100.7' LT	
1		662 + 30	at	101.5' LT	
1		662 + 31	at	77.0' LT	
1		662 + 35	at	84.7' LT	
Margaret Fuller Dr.					
1		17 + 54	at	38.7' LT	
Cartwright Ln.					
1		38 + 90	at	57.4' RT	
1		39 + 26	at	58.4' RT	
Access Rd. "A"					
1		47 + 40	at	18.49' RT	
1		47 + 55	at	29.8' RT	
1		48 + 56	at	44.7' LT	
Cultra Rd.					
1		60 + 65	at	44.3' LT	
1		60 + 65	at	40.3' LT	
1		60 + 67	at	47.8' LT	
1		60 + 67	at	58.1' LT	
1		60 + 76	at	34.3' LT	
77		Various Locatbns on Jobsite		Determined by the IDOT Landscape Architect	
100		TOTAL			

25000775 SELECTIVE MOWING STAKES					
EACH		LOCATION		REMARKS	
30		654 + 50	TO	662 + 0	
48		663 + 50	TO	675 + 50	
24		678 + 0	TO	684 + 0	
102		TOTAL			

25100630 EROSION CONTROL BLANKET					
SQ_YD		LOCATION		REMARKS	
2	RT. STA.	603 + 8			Concrete Headwall for Pipe Drains
2	RT. STA.	604 + 50			Concrete Headwall for Pipe Drains
2	RT. STA.	607 + 50			Concrete Headwall for Pipe Drains
2	RT. STA.	610 + 50			Concrete Headwall for Pipe Drains
2	LT. STA.	613 + 50			Concrete Headwall for Pipe Drains
772	LT. STA.	615 + 22	TO	622 + 0	Ditch (12'x579')
2	LT. STA.	616 + 0			Concrete Headwall for Pipe Drains
2	LT. STA.	618 + 0			Concrete Headwall for Pipe Drains
2	LT. STA.	620 + 50			Concrete Headwall for Pipe Drains
2	LT. STA.	622 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	620 + 50			Concrete Headwall for Pipe Drains
420	LT. STA.	623 + 0	TO	626 + 61	Ditch (12'x315')
373	LT. STA.	626 + 61	TO	630 + 50	Ditch (12'x280')
2	RT. STA.	629 + 50			Concrete Headwall for Pipe Drains
2	RT. STA.	631 + 75			Concrete Headwall for Pipe Drains
2	RT. STA.	633 + 0			Concrete Headwall for Pipe Drains
2	LT. STA.	628 + 0			Concrete Headwall for Pipe Drains
2	LT. STA.	629 + 50			Concrete Headwall for Pipe Drains
2	LT. STA.	632 + 0			Concrete Headwall for Pipe Drains
365	LT. STA.	632 + 0	TO	635 + 64	Ditch (12'x274')
2	LT. STA.	634 + 50			Concrete Headwall for Pipe Drains
1341	LT. STA.	635 + 64	TO	647 + 0	Ditch (12'x1006')
2	LT. STA.	636 + 89			Concrete Headwall for Pipe Drains

2	LT. STA.	638 + 89			Concrete Headwall for Pipe Drains
2	RT. STA.	643 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	646 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	649 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	652 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	654 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	657 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	660 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	663 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	666 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	669 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	672 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	675 + 0			Concrete Headwall for Pipe Drains
2	RT. STA.	677 + 50			Concrete Headwall for Pipe Drains
496	LT. STA.	655 + 50	TO	659 + 22	Ditch (12'x372')
2	LT. STA.	656 + 50			Concrete Headwall for Pipe Drains
371	LT. STA.	659 + 22	TO	662 + 0	Ditch (12'x278')
2	LT. STA.	659 + 50			Concrete Headwall for Pipe Drains
2	LT. STA.	662 + 50			Concrete Headwall for Pipe Drains
280	LT. STA.	663 + 0	TO	667 + 20	Ditch (6'x420')
287	LT. STA.	667 + 20	TO	671 + 50	Ditch (6'x430')
49	LT. STA.	675 + 50	TO	676 + 23	Ditch (6'x73')
2	LT. STA.	677 + 50			Concrete Headwall for Pipe Drains
600	LT. STA.	679 + 0	TO	683 + 50	Ditch (12'x450')
2	LT. STA.	679 + 39			Concrete Headwall for Pipe Drains
256	RT. STA.	682 + 50	TO	683 + 50	Foreslope (23'x100')
101	RT. STA.	48 + 74	TO	49 + 50	Access Rd. "A" Ditch (12'x76')
109	LT. STA.	48 + 18	TO	49 + 0	Access Rd. "A" Ditch (12'x82')
600	WINTER SHUTDOWN				
6486		TOTAL			

25100900 TURF REINFORCEMENT MAT					
SQ_YD		LOCATION		REMARKS	
28.0	RT. STA.	603 + 74	TO	603 + 97	Outlet of CC&G (12'x21')
276.0	LT. STA.	613 + 15	TO	615 + 22	Outlet of CC&G to AR Culvert+ 615+22 (12'x207')
52.9	LT. STA.	615 + 22			Drop Box No.1 (17'x28')
64.0	LT. STA.	626 + 61			Drop Box No.2 (24'x24')
60.0	LT. STA.	654 + 30			Drop Box No.4 (18'x30')
50.7	LT. STA.	667 + 20			Drop Box No.5 (24'x19')
249.3	RT. STA.	17 + 63	TO	19 + 50	Margaret Fuller Rd. Ditch (12'x187')
249.3	LT. STA.	17 + 63	TO	19 + 50	Margaret Fuller Rd. Ditch (12'x187')
266.7	RT. STA.	27 + 50	TO	29 + 50	Blackhawk Vista Ditch (12'x200')
200.0	LT. STA.	27 + 50	TO	29 + 50	Blackhawk Vista Ditch (12'x150')
208.0	RT. STA.	37 + 42	TO	39 + 50	Cartwright Ln. (12'x156')
1704.9		TOTAL			

28000300 TEMPORARY DITCH CHECKS					
EACH		LOCATION		REMARKS	
4	LT. STA.	613 + 0	TO	615 + 22	at 50' ctrs.
1	LT. STA.	616 + 23	TO	615 + 22	
2	LT. STA.	618 + 35	TO	616 + 75	at 100' ctrs.
4	LT. STA.	622 + 0	TO	618 + 81	at 100' ctrs.
3	LT. STA.	623 + 0	TO	625 + 0	at 100' ctrs.
2	LT. STA.	625 + 52	TO	626 + 61	at 50' ctrs.
3	LT. STA.	630 + 50	TO	628 + 19	at 100' ctrs.
3	LT. STA.	632 + 0	TO	634 + 50	at 100' ctrs.
6	LT. STA.	641 + 37	TO	635 + 63	at 100' ctrs.
3	LT. STA.	649 + 0	TO	643 + 32	at 100' ctrs.
4	LT. STA.	655 + 25	TO	659 + 22	at 100' ctrs.
3	LT. STA.	662 + 50	TO	659 + 22	at 100' ctrs.
4	LT. STA.	663 + 0	TO	667 + 20	at 100' ctrs.
4	LT. STA.	667 + 20	TO	671 + 50	at 100' ctrs.
4	RT. STA.	679 + 0	TO	683 + 50	at 100' ctrs.
5	RT. STA.	18 + 28	TO	19 + 48	Margaret Fuller Rd. - at 25' ctrs.
5	LT. STA.	17 + 63	TO	19 + 0	Margaret Fuller Rd. - at 25' ctrs.
3	RT. STA.	27 + 50	TO	28 + 25	Blackhawk Vista - at 25' ctrs.
2	LT. STA.	27 + 50	TO	28 + 38	Blackhawk Vista - at 50' ctrs.
2	RT. STA.	28 + 25	TO	29 + 50	Blackhawk Vista - at 50' ctrs.
4	RT. STA.	37 + 42	TO	38 + 34	Cartwright Ln. - at 25' ctrs.
3	RT. STA.	38 + 85	TO	39 + 50	Cartwright Ln. - at 25' ctrs.
3	LT. STA.	38 + 0	TO	39 + 0	Cartwright Ln. - at 25' ctrs.
1	LT. STA.	48 + 18	TO	49 + 0	Access Rd. "A"
2	RT. STA.	48 + 74	TO	49 + 47	Access Rd. "A" - at 25' ctrs.
WINTER SHUTDOWN					
88		TOTAL			

▲ REVISIED SHEET 7-15-09

FILE NAME =	USER NAME = perkinsdr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. R/E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\KPMIDOT\PERKINSR\ms34123\d8486c.dgn	DRAWN -	REVISED -	742			3TR-3	OGLE	345	30	
PLOT SCALE = 58.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 84788							
PLOT DATE = Mon Jun 08 11:19:11 2009	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.

SCHEDULE OF QUANTITIES

SQ YD	LOCATION	REMARKS
23602	LT/RT 603 + 8 TO 680 + 0	Entire Job - Including existing bituminous shoulder Shoulder Lt. Sta. 604+09 to 613+91 Shoulder Rt. Sta. 603+80 to 613+99
23602	TOTAL	

FOOT	LOCATION	REMARKS
67	LT. STA. 603 + 44 TO 249 + 0	Around SW Radius Fair St.
67	TOTAL	

FOOT	LOCATION	REMARKS
831	LT. STA. 604 + 10 TO 612 + 41	Near Fair St.
831	TOTAL	

FOOT	LOCATION	REMARKS
49	LT. STA. 603 + 8 TO 603 + 44	Around SW Radius Fair St.
73	RT. STA. 603 + 8 TO 603 + 80	
122	TOTAL	

SQ YD	LOCATION	REMARKS
94	CL 626 + 61	AR Culvert at Sta. 626+61 (done under flaggers) AR Culvert at Sta. 635+63 (done under flaggers) AR Culvert at Sta. 654+30 (done under flaggers) AR Culvert at Sta. 659+22 (done under flaggers) AR Culvert at Sta. 667+20 (done under flaggers)
91	CL 635 + 63	
81	CL 654 + 30	
97	CL 659 + 22	
62	CL 667 + 20	
426	TOTAL	

TON	LOCATION	REMARKS
207	LT/RT 664 + 0 TO 712 + 36	SMART Resurfacing
99	LT/RT 729 + 37 TO 752 + 50	
305	TOTAL	

SQ YD	LOCATION	REMARKS
905	LT/RT 618 + 0 TO 628 + 29	STAGE 9 - SHOULDERS
905	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 615 + 22	4x4 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 626 + 61	10x6 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 635 + 63	5x4 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 654 + 30	7x2.5 Concrete Box Culvert
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 659 + 22	4x2 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 667 + 20	30" Round Concrete Pipe Culvert
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 677 + 98	12x3 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
1	TOTAL	

EACH	LOCATION	REMARKS
1	LT/RT 618 + 62	24" CMP w/ Drop Structure
1	TOTAL	

SQ. FT.	LOCATION	REMARKS
578.4	615 + 22	AR Culvert AR Culvert - Removal of Existing AR Culvert • Quantities duplicated on Culvert Detail Sheets
268.2	677 + 98	
1321.8	678 + 70	
2168.4	TOTAL	

EACH	LOCATION	REMARKS
1	615 + 22	• Quantity duplicated on Culvert Detail Sheet
1	626 + 61	
1	635 + 63	
1	654 + 30	
1	659 + 22	
1	667 + 20	
1	678 + 70	
7	TOTAL	

FOOT	LOCATION	REMARKS
146	LT/RT 19 + 44	Margaret Fuller Rd. Cartwright Ln. Access Road A (AR Culvert)
101	LT/RT 39 + 44	
184	LT/RT 49 + 25	
431	TOTAL	

▲ REVISED SHEET 7-15-09