

SUMMARY OF QUANTITIES

CODE NO. DESCRIPTION

- *40600100 BITUMINOUS MATERIALS (PRIME COAT) RC-70
- *40600300 AGGREGATE (PRIME COAT)
- *40600625 LEVELING BINDER (MACHINE METHOD) N50
- *40603350 HOT MIX ASPHALT SURFACE COURSE, MIXTURE "D" N50
- *44000154 HOT MIX ASPHALT SURFACE REMOVAL, 1 1/4" S.Y.
- *60255500 MANHOLES TO BE ADJUSTED
- *60266600 VALVE BOXES TO BE ADJUSTED
- 67100100 MOBILIZATION
- △ *70300220 TEMPORARY PAVEMENT MARKING LINE, 4"

UNIT	TOTAL QUANTITY
GAL.	3211
TON	54
TON	2268
TON	2698
S.Y.	32113
EACH	38
EACH	7
L.SUM	1
FOOT	900

* DENOTES SPECIAL PROVISIONS
CONSTRUCTION CODE 1000

△ SPECIALTY ITEMS

RESURFACING SCHEDULE

STREET	FROM	TO	LENGTH (FT)	WIDTH (E-E)	PAVT. (SY)	HMA SURF REM 1 1/4" (SY)	BIT. MATLS. (PR CT) RC-70 (GAL)	AGG. (PR CT) (TON)	LEVEL BINDER (MACH METH) (TON)	HMA SURF. CSE., MIX "D" N50 (TON)	MH ADJ (EACH)	WV ADJ (EACH)
LISBON ROAD (FAU 5966)	US ROUTE 6 (BEDFORD ROAD)	BOULDER STREET	2,922	36	11,688	11,688	1,159	19	818	982	10	1
		BOULDER STREET	1,087	25	2,959	2,959	296	5	208	249		
		I-80 OVERPASS	877	25	2,387	2,387	239	4	168	201		
		877' NORTH/OVERPASS	184	30	613	613	61	1	43	51		
		1081' NORTH/OVERPASS	215	36	860	860	86	1	60	72		
		EAST RADIUS GORE ROAD	23	29	74	74	7		5	6		
		MAINLINE TOTALS	5,308		18,581	18,581	1,858	30	1,302	1,561	10	1
		INTERSECTIONS										
		DALEY	5	30	17	17	2		1	1		
		WEST BRENTWOOD	22	30	72	72	7		5	6		
		EAST BRENTWOOD	39	30	130	130	13		9	12		
		THOMAS	23	30	77	77	8		5	6		
		EAST BOULDER	21	34	79	79	8		5	6		
		WEST BOULDER (SOUTH LANE)	36	17	68	68	7		5	6		
		WEST BOULDER (NORTH LANE)	18	17	34	34	3		2	3		
		INTERSECTION TOTALS			477	477	48	1	32	40		
		LISBON ROAD TOTALS	5,308		19,058	19,058	1,906	31	1,334	1,601	10	1
LISBON STREET (FAU 5967)	QUARRY STREET	US ROUTE 6 (BEDFORD ROAD)	765	36	3,060	3,060	306	4	234	257	8	1
		INTERSECTIONS										
		WEST WAVERLY STREET	12	36	48	48	5	1	3	4		
		EAST WAVERLY STREET	23	36	92	92	9		7	8		
		LISBON STREET TOATLS	765		3,200	3,200	320	5	244	269	8	1
HIGH STREET (FAU 5953)	LIBERTY STREET	ILL. ROUTE 47 (DIVISION STREET) RADII	552	35	2,147	2,147	215	4	151	181	4	3
					63	63	6		4	5		
		HIGH STREET TOTAL	552		2,210	2,210	221	4	155	186	4	3
JOHNSON AVENUE (FAU 5954)	UNION STREET	250' WEST OF LISBON STREET RADII	952	33	3,490	3,490	349	7	244	293	5	2
					33	33	3		2	3		
		JOHNSON STREET TOTALS	952		3,523	3,523	352	7	246	296	5	2
WASHINGTON STREET (FAU 5962)	SPRUCE STREET	NORTH/MAIN STREET	925	37	3,803	3,803	380	7	267	319	11	0
		INTERSECTIONS										
		EAST STREET	83	31	286	286	29		20	24		
		MAIN STREET	10	30	33	33	3		2	3		
		WASHINGTON STREET TOTALS	925		4,122	4,122	412	7	289	346	11	0
		LISBON ROAD (FAU 5966) TOTALS			19,058	19,058	1,906	31	1,334	1,601	10	1
		LISBON STREET (FAU 5967) TOTALS			3,200	3,200	320	5	244	269	8	1
		HIGH STREET (FAU 5953) TOTALS			2,210	2,210	221	4	155	186	4	3
		JOHNSON AVENUE (FAU 5954) TOTALS			3,523	3,523	352	7	246	296	5	2
		WASHINGTON STREET (FAU 5962) TOTALS			4,122	4,122	412	7	289	346	11	0
		GRAND TOTALS	8,502		32,113	32,113	3,211	54	2,268	2,698	38	7

DRAWN BY: MAB
CHECKED BY: RJS
DATE: 4/1/09

REVISIONS	
DATE	BY
5/12/09	MAB
5/21/09	MEF

CHAMLIN ASSOCIATES
PERU MORRIS
ILLINOIS

MORRIS ARRA PROJECT 2009
CITY OF MORRIS, GRUNDY COUNTY, ILLINOIS

SUMMARY OF QUANTITIES AND SCHEDULE

SCALE: 1 = 20
FILE NO.: 12883
SHEET 2
OF 12