

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6141	09-00092-00-PV	LASALLE	36	5
STA. 1+85		TO STA. 39+80		
FED. ROAD DIST. NO. 3		ILLINOIS ARRA PROJECT		

BITUMINOUS PAVEMENT AND AGGREGATE SCHEDULE

LOCATION (STA. TO STA.)	LENGTH FEET	WIDTH FEET	HMA BINDER COURSE, MIX C. N60, 7" TON	HMA BINDER COURSE, MIX C. N60, 2" TON	HMA SURFACE COURSE, MIX C. N60, 1-1/2" TON	AREA REFLECTIVE CRACK CONTROL SQ. YD.	BITUMINOUS MATERIALS (PRIME COAT) SQ. YD.	AGGREGATE BASE COURSE, TYPE A TON
1+85 - 18+90	1705	30			500		1486	
18+90 - 39+00 (6' PATCH)	2010	6	525				670	615
18+90 - 39+80	2090	21.5		566			2496	
18+90 - 39+80	2090	28			540	6390		
SIDERoads & DRIVEWAYS	VAR.	VAR.			17		76	
TOTALS			1091		1057	6390	4766	615

SIDEWALK REMOVAL & REPLACEMENT SCHEDULE

LOCATION	SIDEWALK REMOVAL SQ. YD.	P.C.C. SIDEWALK 4" SQ. YD.
5+50 RT	75	75
8+10 RT	25	25
9+50 RT	50	50
12+00 RT	25	25
12+85 RT	50	50
13+40 RT	75	75
13+75 RT	75	75
15+70 RT	38	38
17+50 RT	100	100
21+44 LT	-	55
21+44 RT	-	55
24+50 - 25+50 LT	-	515
30+55 LT	37	37
31+10 LT	37	37
39+00 LT	57	57
39+65 LT	58	58
TOTALS		1292

PAVEMENT REMOVAL SCHEDULE

LOCATION	HMA PAVEMENT REMOVAL SQ. YD.	P.C.C. PAVEMENT REMOVAL SQ. YD.	HMA SURFACE REMOVAL (1-1/2") SQ. YD.	HMA SURFACE REMOVAL (3") SQ. YD.	HMA SURF. REMOVAL (BUTT JOINT) SQ. YD.	PCC SURF. REMOVAL (BUTT JOINT) SQ. YD.
2+42 - 5+36		882				
5+89 - 10+13		1273				
10+80 - 13+14		700				
13+51 - 15+15 RT		247				
18+90 - 40+80				5050		
18+90 - 39+00 RT	1340					
21+95.46			15			
22+12.37			16			
25+48.82			12			
26+10.22			10			
27+18.82			14			
29+72.22			15			
30+84.11			12			
32+41.31			14			
33+70.39			15			
35+50.06			13			
39+32.17			15			
BUTT JOINTS						
1+85 - 2+05						75
PINE CREST DR.						58
PONDEROSA DR.						78
WILLOW DR.						58
HERITAGE CIR.					51	
TOTALS		1340	3102	151	5050	269

CL B HOT PATCH 7" P.C.C. SCHEDULE

LOCATION	CL B PATCH TYPE 2, 7" SQ. YD.	CL B PATCH TYPE 3, 7" SQ. YD.	CL B PATCH TYPE 4, 7" SQ. YD.	REINF. FABRIC SQ. YD.	DOWEL BARS EACH	TIE BARS EACH	SAW CUTS FOOT
WB 2+22 - 2+26	5.8				24		34
EB 2+22 - 2+26	6.7				28		38
EB 5+68 - 5+74	8.7				24		38
WB 10+29 - 10+33	5.8				24		34
EB 14+07 - 14+15	11.6				24		42
WB 15+69 - 15+78	13				24		44
WB 16+23 - 16+35		18		18	24		50
WB 16+52 - 16+56	6.6				28		38
WB 16+71 - 16+75	5.8				24		34
WB 18+54 - 18+91			53	53	24	18	100
EB 18+72 - 18+91			28	28	24	10	64
TOTALS		64	18	81	99	272	516

CURB & GUTTER REMOVAL & REPLACEMENT SCHEDULE

LOCATION	C.C.&G. B8:18 REM. & REPLACE FOOT	
3+08-3+18 LT	10	
3+60-3+87 RT	27	
4+00-4+63 RT	63	
4+80-4+98 LT	18	
5+24-5+80 RT	56	
5+46-5+52 LT	6	
6+40-6+95 LT	55	
7+44-7+75 LT	31	
7+50-7+56 RT	6	
8+60-8+86 LT	8	
9+49-9+53 RT	4	
10+47-10+53 RT	6	
12+10-12+20 RT	10	
14+08-14+53 LT	45	
14+92-15+03 RT	11	
15+79-15+95 RT	16	
17+74-17+82 LT	8	
18+72-18+98 LT	26	
21+41 - 21+49 LT&RT (FOR SW RAMP)	16	
ROSEMONT (FOR SW RAMP)	16	
EASTWOOD (FOR SW RAMP)	16	
TOTALS		454

P.C.C. 7" JOINTED PAVEMENT SCHEDULE

LOCATION	7" PCC JOINTED PAVEMENT SQ. YD.	
2+42 - 5+36	882	
5+89 - 10+13	1273	
10+80 - 13+14	700	
13+51 - 15+15 RT	247	
TOTALS		3102

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION	4" YELLOW FOOT	6" WHITE FOOT	24" WHITE FOOT	LETTERS & SYMBOLS (WHITE) SQ. FT.
CENTERLINE				
1+85 - 39+80 C.L.	1000			
CROSSWALKS				
PINE CREST		81		
PONDEROSA		111		
WILLOW		81		
LEXTIN		81		
21+44 X-WALK		56		9
MEMORY		85		
ROSEMONT		86		
EASTWOOD		228		
STOP BARS				
EASTWOOD (E. & W.)			28	
TOTALS		1000	869	28

EXISTING STRUCTURE SCHEDULE

LOCATION	MANHOLE ADJUST EACH	VALVE VAULTS TO BE ADJUSTED EACH	INLETS TO BE ADJUSTED EACH
10+04 LT	1		
10+06 RT	1		
10+17 RT	1		
15+01 LT			1
20+33 RT		1	
39+60 LT	1		
TOTALS		4	1

FINAL

SCALE: N.T.S.

DESIGNED - JEP
DRAWN - JCL
CHECKED - JEP
DATE - 4/10/09

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES