

RTE NO.	SECTION	COUNTY	TOTAL	SHEET #
F.A.P. 646	125W-1,RS-2	PEORIA	256	5A

CONTRACT NUMBER 88679

TRAFFIC SIGNALS (Y030-1F)						
CODE NUMBER	PAY ITEM	UNIT	TOTAL	FED ST CITY 80/10/10	FED ST CNTY 80/10/10	FED ST TOWNSHIP 80/10/10
				CITY	COUNTY	TOWNSHIP
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	3	1	1	1
* M8100260	CONDUIT IN TRENCH, 50mm DIA., P V C	METER	2452	935.5	285	1231.5
* M8100280	CONDUIT IN TRENCH, 75mm DIA., P V C	METER	115.5	39.5	46	30
* M8100290	CONDUIT IN TRENCH, 90mm DIA., P V C	METER	44.5	22	11	11.5
* M8101470	CONDUIT PUSHED, 75mm DIA., P V C	METER	119	44.5	37.5	37
* M8101480	CONDUIT PUSHED, 90mm DIA., P V C	METER	70	19	24.5	26.5
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	27	10	5	12
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3	1	1	1
* M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	2612	997	342	1273
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3	1	1	1
* M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 3C	METER	55 126	55 126		
* M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 5C	METER	396	163		233
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO.14 7C	METER	1286	506	465	315
* M8731510	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	METER	1380	474	429	477
* M8770750	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.36 METER	EACH	1			1
* M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1			1
* M8770770	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.80 METER	EACH	1	1		
* M8770780	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 15.24 METER	EACH	6	3	1	2
* M8780200	CONCRETE FOUNDATION, TYPE D	METER	3.3	1.1	1.1	1.1
* M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	16.4		8.2	8.2
* MX878030	CONCRETE FOUNDATION TYPE E 900MM DIAMETER	METER	36.2	17.8	9.2	9.2
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	19	6	7	6
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	10	4	4	2
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	10	4	4	2
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2	2		
* 88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	1	1		
* 88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	29	10	11	8
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	32	11	11	10
* M8860100	DETECTOR LOOP, TYPE I	METER	1,245	403	448	394
* MX871055	FIBEROPTIC CABLE IN CONDUIT, NO 62.5/125, MM12F SM12F	METER	2831	1811		1020
* M8770055	STEEL MAST ARM ASSEMBLY AND POLE, 10.36 METER	EACH	1			1
* M8770060	STEEL MAST ARM ASSEMBLY AND POLE, 10.97 METER	EACH	1			1
* M8770095	STEEL MAST ARM ASSEMBLY AND POLE, 15.24 METER	EACH	1			1

*SPECIALTY ITEM

TRAFFIC SIGNALS (Y030-1F)						
CODE NUMBER	PAY ITEM	UNIT	TOTAL	FED ST CITY 80/10/10	FED ST CNTY 80/10/10	FED ST TOWNSHIP 80/10/10
				CITY	COUNTY	TOWNSHIP
* MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	458	158	141	159
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	4		
X0325977	TEMPORARY TRAFFIC SIGNAL INSTALLATION (LOCATION 1)	EACH	1			
X0325978	TEMPORARY TRAFFIC SIGNAL INSTALLATION (LOCATION 2)	EACH	1		1	
89502380	REMOVE EXISTING HAND HOLE	EACH	9	4	4	1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	3	5	1

HIGHWAY LIGHTING (URBAN Y030-1E)						
CODE NUMBER	PAY ITEM	UNIT	TOTAL	100% CITY	100% COUNTY	100% TOWNSHIP
				CITY	COUNTY	TOWNSHIP
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	8	4		4
* 82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1			1
* X8250208	LIGHTING CONTROLLER PHOTOCCELL RELAY, INSTALL ONLY	EACH	1	1		
* M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	METER	690	350	50	290
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	2		2	

△ SHEET ADDED
5/26/09

△ REVISED 7-15-09