



**CONCRETE GUTTER**  
 DEPRESS GUTTER 4" @ RAMP  
 w/ 2' TRANSITION TO EXISTING,  
 8' TOTAL LENGTH EACH.

NOTE:  
 PR PCC SIDEWALKS AND RAMP  
 TO BE 4' WIDE AND 4" THICK.  
 RAMP SLOPES 8.33% (1:12) TYP.  
 COSTS FOR INCIDENTAL EARTHWORK  
 AND SEEDING TO BE INCLUDED IN THE  
 COST FOR PCC SIDEWALK 4".  
 ALL MEASUREMENTS ON CURVES  
 ARE CHORD DISTANCES.

**BILL OF MATERIALS**

TOTAL PCC SIDEWALK 4"	= 87 SQ FT
TOTAL SIDEWALK REMOVAL	= 34 SQ FT
TOTAL CONCRETE GUTTER	= 16 FT
TOTAL GUTTER REMOVAL	= 16 FT
DETECTABLE WARNING	= 16 SQ FT

FILE NAME = G:\587009-01\cad\7009-01_Ext_Detail101.dwg	USER NAME = IE Consultants	DESIGNED -	REVISED -	<b>VILLAGE OF SHERMAN</b>	<b>RAMP SIDEWALK DETAILS</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 5.0000' / IN.	DRAWN -	REVISED -			08-00014-00-SW	SANGAMON	47	43	
	PLOT DATE = 2/12/2009	CHECKED -	REVISED -			CONTRACT NO. <b>93486</b>				
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	