

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
35800100	PREPARATION OF BASE	SQ YD	400
35800200	AGGREGATE BASE REPAIR	TON	25
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	75
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,098
40600300	AGGREGATE (PRIME COAT)	TON	1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,487
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	74
40600990	TEMPORARY RAMP	SQ YD	25
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,146
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,500
42400800	DETECTABLE WARNINGS	SQ FT	50
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	12,762
* 44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	300
44000600	SIDEWALK REMOVAL	SQ FT	1,500
48101200	AGGREGATE SHOULDERS, TYPE B	TON	292
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	6
60255500	MANHOLES TO BE ADJUSTED	EACH	9
60260100	INLETS TO BE ADJUSTED	EACH	13
* 60266600	VALVE BOXES TO BE ADJUSTED	EACH	14
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	300
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,939
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	254
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,231
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,219
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	575
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,465
72000100	SIGN PANEL - TYPE 1	SQ FT	85
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	214
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,616
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	610
△ 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	127
△ 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	288
* Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

\* SEE SPECIAL PROVISIONS  
NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE I000  
△ SPECIALTY ITEMS

FILE NAME =	USER NAME = Prussell	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CITY OF BEARDSTOWN - 4th STREET (FAU 7768)</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
V:\2693\09-00075-00-rs (4th)\2693q001.dwg		DRAWN - JCW	REVISED -		<b>SUMMARY OF QUANTITIES</b>			7768	09-00075-00-RS	CASS	3	12
	PLOT SCALE = 10.0000' / IN.	CHECKED - JRB	REVISED -		SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. N/A TO STA. N/A	CONTRACT NO. 93489				
	PLOT DATE = 3/25/2009	DATE - 02-26-09	REVISED -		ILLINOIS FED. AID PROJECT							