

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-0009H-00-RS	COLES	8	7

# SCHEDULE OF QUANTITIES

Location	44201737	Class D Patch Type 1 8"	Width	Sq. Yds.
W. Polk	Station	Length		
	Rt 13+90	4	9.5	4.22
	Lt 13+90	4	9.5	4.22
	Rt 23+60	4	9.5	4.22
	Rt 27+21	4	9.5	4.22
				<u>16.89</u>

Location	44201741	Class D Patch Type 2 8"	Width	Sq. Yds.
W. Polk	Station	Length		
	Rt 6+49	11.5	9.5	12.14
	Rt 12+63	6	9.5	6.33
	Lt 24+85	14	7	10.89
14th	1+15 LT & RT	20	6	13.3
	5+30 LT & RT	20	6	13.3
				<u>56.03</u>

Location	44201745	Class D Patch Type 3 8"	Width	Sq. Yds.
W. Polk	Station	Length		
	Lt 29+00	17.5	9.5	18.47
14th	0+25 LT	50	6	33.3
				<u>51.81</u>

Location	44201747	Class D Patch Type 4 8"	Width	Sq. Yds.
W. Polk	Station	Length		
	Rt 28+24	60	6.5	43.33
	Rt 29+00	58	9.5	61.22
				<u>104.56</u>

Location	Station	Description	Length	Width	Area	Tons Incid. HMA
W. Polk	1+23 LT	PCC P.E.	8	15	13.3	2.24
	2+68 LT	Davis Dr.	20	25	55.6	9.33
	3+66 LT	PCC P.E.	8	12	10.7	1.79
	4+13 LT	PCC P.E.	8	12	10.7	1.79
	4+37 LT	PCC P.E.	8	20	17.8	2.99
	5+66 LT	PCC P.E.	8	20	17.8	2.99
	6+76 LT	PCC P.E.	8	20	17.8	2.99
	7+60 LT	PCC P.E.	8	20	17.8	2.99
	8+21 LT	PCC P.E.	8	18	16.0	2.69
	9+44 LT	Douglas Dr.	35	20	77.8	13.07
	10+97 LT	PCC P.E.	8	28	24.9	4.18
	11+41 RT	PCC P.E.	8	28	24.9	4.18
	12+55 RT	HMA C.E.	10	35	38.9	6.53
	13+66 LT	HMA C.E.	10	35	38.9	6.53
	14+44 RT	HMA C.E.	10	20	22.2	3.73
	15+69 RT	Oakcrest Dr.	20	55	122.2	20.53
	16+42 RT	HMA C.E.	8	38	33.8	5.67
	17+04 LT	Timber Lane	25	70	194.4	32.67
	17+20 RT	HMA C.E.	8	35	31.1	5.23
	18+06 RT	HMA P.E.	12	18	24.0	4.03
	19+13 RT	Foxcrest Dr.	10	70	77.8	13.07
	19+76 LT	PCC P.E.	10	28	31.1	5.23
	20+26 RT	PCC P.E.	10	20	22.2	3.73
	20+30 LT	PCC P.E.	10	18	20.0	3.36
	20+89 RT	PCC P.E.	10	15	16.7	2.80
	21+46 RT	PCC P.E.	7	15	11.7	1.96
21+65 LT	PCC P.E.	3	40	13.3	2.24	
22+01 RT	PCC P.E.	5	15	8.3	1.40	
25+01 LT	HMA C.E.	10	25	27.8	4.67	
26+88 RT	Lynnwood Dr.	13	64	92.4	15.53	
14th	2+58 RT	Jefferson Ave.	12	15	20.0	3.4
	2+58 LT	Jefferson Ave.	35	20	77.8	13.1
	5+20 RT	Adams Ave.	30	15	50.0	8.4
	5+45 LT	Adams Ave.	30	20	66.7	11.2
IL 16 Intersections						<u>0.00</u>
						226.17

Location	60255500	Manholes to be Adjusted	Quantity	Total
W. Polk	Station	Quantity		
	2+68	1		
	6+04	1		
	9+40	1		
	11+29	1		
	13+36	1		
	14+43	1		
17+27	1			
				7
14th	1+03 LT	1		
	1+34 LT	1		
	1+59 LT	1		
	1+59 RT	1		
	5+45 CL	1		
				5
	Total			<u>12</u>

Location	56109210	Water Valves to be Adjusted	Quantity
W. Polk	Station	Quantity	
	9+21	1	
	9+55	1	
	12+49	1	
	15+48	1	
16+49	1		
			<u>5</u>