July 20, 2009

SUBJECT: FAU 9124 (Spring Street)

Project M-5011(204)

Section 05-00085-01-FP & 05-00085-02-FP (Collinsville)

Madison County Contract No. 97353

Item 124

July 31, 2009 Letting

Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal - Schedule of Prices - page 1, special provisions - page 7.

Plans – Sheets 3, 7, 22, 23, 31, 34-61.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll

Engineer of Design and Environment

By: Ted B. Walschleger

Engineer of Project Development

Tet Develyon A.E.

and Implementation

STATE JOB #- C-98-337-06 SCH PPS NBR - 8-10231-0000 CONTR

ILLINOIS DEPARTMENT OF TRANSPORTATION ECW SCHEDULE OF PRICES CONTRACT NUMBER - 97353 RUN

ECMS002 DTGECM03 ECMR003 PAGE RUN DATE - 07/17/09 RUN TIME - 183325

ROUTE FAU 9124	TOTAL PRICE DOLLARS CTS			! ! ! !	i i				i i	i I			i	i		
PROJECT NUMBER 1/204/000	UNIT PRICE DOLLARS CENTS		— II — I									i	i	i	i	- 11
) M-501	QUANTITY	266.000 X	97.00	128.00	0	16.00	86.000	58,000	0.100	9.000	,403.00	,260.00	20	Ō	5.000	000
ION NUMBER (COLLINSVILLE)	UNIT OF MEASURE	SQ YD	SQ FT			no		INN	ACRI	no		SQ Y		NO !	NUOA	POUND
AME CODE DIST SECT SECT 119 08 05-00085-01-FP	PAY ITEM DESCRIPTION	CONCRETE	BLOCK RETAIN WALL	SS 1 WAT MN 12	SS 1 WAT MN 15	CONCRETE STEPS	TREE REMOV 6-15	TREE REMOV OVER 15	TREE REMOV ACRES	EARTH EXCAVATION	TRENCH BACKFILL	TOPSOIL F & P 4	SEEDING CL 1A	ITROGEN FERT NUTR	PHOSPHORUS FERT NUTR	TASSIUM FERT NUTR
COUNTY NAME CODE	ITEM	X004102	X008086	21905	0321906	0012450	0110	0100210	0100500	0200100	0800150	1101615	5000110	5000400		5000600

CONTRACTOR ACCESS

At road closure locations, where Type III barricades are installed in a manner that will not allow Contractor access to the project without relocation of one or more of the barricades, the arrangement of the barricades at the beginning of each work day may be relocated, when approved by the Engineer, in the manner shown on Highway Standard 701901. At the end of each work day, the barricades shall be returned to the proper overnight position.

The cost incurred by the Contractor in complying with this requirement shall be considered included in the contract unit price bid for traffic control work and no additional compensation will be allowed.

EARTH EXCAVATION

This work shall be constructed according to Section 202 of the "Standard Specifications for Road and Bridge Construction," except as modified herein:

At locations where existing bituminous treated surface lies at or below the elevation of the proposed subgrade, the Contractor shall scarify the existing surface, reducing all particles to a size not larger than four inches in the largest dimension and recompact the existing surface prior to placing earth embankment or other subbase material.



All excavated material shall be used on site. No material shall be hauled away unless approved by the Engineer.

This work will be paid for at the contract unit price per cubic yard for EARTH EXCAVATION, measured as specified in Article 202.07 of the "Standard Specifications for Road and Bridge Construction", as specified herein and no additional compensation will be allowed.

TRENCH BACKFILL

This work shall be constructed according to Section 208 of the "Standard Specifications for Road and Bridge Construction", except as modified herein:

Fine aggregate according to Article 1003.04 may be used for bedding only, except as follows: Fine aggregate will be required for trench backfill within 2-feet of all gas mains and gas service lines that are exposed during trenching operations.