# CONSTRUCTION PLANS FOR QUAD CITY INTERNATIONAL AIRPORT METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND

METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLANI MOLINE, ILLINOIS

> IL. PROJ. NO. MLI-4482 AIP PROJ. NO. 3-17-0068-XX

# **CONSTRUCT TAXIWAY K CONNECTOR (K12)**



JUNE 26, 2015



SITE PLAN



# TOTAL SHEETS: 27 QU020

MAXIMUM EQUIPMENT HEIGHT - 25 UNICOM FREQUENCY - 122.95

METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS

APPROVED Bruce Conter

DATE April 13, 2015

CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS

Se Sl
SEAN M. SMITH, P.E.
17 ATRIL 2015



CMT JOB NUMBER: 14014-07-00

SUBMITTED BY

DATE

INDEX TO SHEETS					
Sheet Number	Sheet Title				
01	COVER				
02	INDEX TO SHEETS AND SUMMARY OF QUANTITIES				
03	SITE PLAN				
04	PROJECT CONTROL PLAN				
05	SEQUENCE OF CONSTRUCTION				
06	SEQUENCE OF CONSTRUCTION GENERAL NOTES				
07	SEQUENCE OF CONSTRUCTION DETAILS				
08	STORM WATER POLLUTION PREVENTION PLAN				
09	STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS SHEET 1				
10	STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS SHEET 2				
11	TYPICAL SECTIONS				
12	EXISTING CONDITIONS AND PROPOSED REMOVALS				
13	PLAN AND PROFILE				
14	GRADING AND DRAINAGE PLAN				
15	DRAINAGE DETAILS				
16	PAVEMENT JOINTING PLAN				
17	PAVEMENT JOINT ELEVATION PLAN				
18	PAVEMENT JOINTING DETAILS				
19	ELECTRICAL AND PAVEMENT MARKING PLAN				
20	ELECTRICAL DETAILS SHEET 1				
21	ELECTRICAL DETAILS SHEET 2				
22	ELECTRICAL DETAILS SHEET 3				
23	PAVEMENT MARKING DETAILS				
24	INDEX TO CROSS SECTIONS AND EARTHWORK SUMMARY				
25	CROSS SECTIONS SHEET 1				
26	CROSS SECTIONS SHEET 2				
27	SOIL BORING LOCATIONS				

SUMMARY OF QUANTITIES						
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY		
AR108158	1/C #8 5KV UG CABLE IN UD	LF	3,500			
AR109210	VAULT MODIFICATIONS	LS	1			
AR110312	2" STEEL DUCT, JACKED	LF	175			
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	75			
AR125415	MITL-BASE MOUNTED	EACH	24			
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2			
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	4			
AR125470	MODIFY EXISTING SIGN PANEL	EACH	1			
AR125565	SPLICE CAN	EACH	1			
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	8			
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	2			
AR125915	RELOCATE RGL	PAIR	1			
AR150520	MOBILIZATION	LS	1			
AR152410	UNCLASSIFIED EXCAVATION	CY	3,093			
AR1524540	SOIL STABILIZATION FABRIC	SY	2,750			
AR156520	INLET PROTECTION	EACH	4			
AR208515	POROUS GRANULAR EMBANKMENT	CY	150			
AR209610	CRUSHED AGG. BASE COURSE - 10"	SY	2,750			
AR501509	9" PCC PAVEMENT	SY	2,575			
AR501900	REMOVE PCC PAVEMENT	SY	37			
AR605510	JOINT SEALING FILLER	LF	3,920			
AR620520	PAVEMENT MARKING - WATERBORNE	SF	7,195			
AR620900	PAVEMENT MARKING REMOVAL	SF	3,560			
AR701006	6" PVC STORM SEWER	LF	75			
AR701512	12" RCP, CLASS IV	LF	415			
AR705506	6" PERFORATED UNDERDRAIN	LF	815			
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	2			
AR705900	REMOVE UNDERDRAIN	LF	380			
AR751540	MANHOLE 4'	EACH	2			
AR800022	2-1/C #4 XLP-USE, 600V AND 1/C #8 GND IN 1-1/4" UD	LF	1,000			
AR800038	REMOVE BASE MOUNTED LIGHT (FIXTURE ONLY)	EACH	25			
AR800116	PAVEMENT MARKING - PREFORMED THERMOPLASTIC	SF	2,660			
AR901510	SEEDING	ACRE	1.00			
AR904510	SODDING	SY	535			
AR908510	MULCHING	ACRE	1.00			

	BY DATE				
	BY DATE				
0 THIS BA					
O THIS BA AT FUI					
	1 2 R IS EQUAL TO 2" L SCALE (34X22).				
METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS	CONSTRUCT TAXIWAY K CONNECTOR (K12) INDEX TO SHEETS AND SUMMARY OF QUANTITIES				
CAPITOR CAT. INC. CRAMFORD, MURPHY & TILLY, INC. CONSULTING, FIRINFERS					
DESIGN BY:	CMT				
CHECKED BI	r: SMS				
APPROVED BY: MND					
DATE: JUNE 26, 2015					
JUB No: 14014-07-00 IL. PROJ. NO. MLI-4482 AIP PROJ. NO. 3-17-0068-XX					





HORIZONTAL CONTROL POINTS						
POINT	€ STATION 1	€ STATION 2	NORTHING	EASTING		
1	TAXIWAY K12 STA. 10+00.00	TAXIWAY K STA. 380+68.24	1,739,702.71	2,206,062.68		
2	TAXIWAY K12 STA. 14+00.26	RUNWAY 13/31 STA. 80+70.56	1,740,019.85	2,206,306.87		
3	RUNWAY 13/31 STA. 86+05.50	TAXIWAY B STA. 189+19.66	1,739,693.40	2,206,730.66		
4	RUNWAY 13/31 STA. 86+13.00	TAXIWAY K STA. 389+46.45	1,739,688.82	2,206,736.60		
5	TAXIWAY K STA. 384+60.60	TAXIWAY K STA. 386+96.21	1,739,582.12	2,206,465.06		
6	TAXIWAY K STA. 375+45.57	TAXIWAY K STA. 376+08.60	1,739,903.96	2,205,637.52		

VERTICAL CONTROL POINTS						
POINT STATION 1 STATION 2 NORTHING EASTING ELEVATION						
A - IRON PIN	TAXIWAY K STA. 381+42.98, 55.77' RT.	TAXIWAY K12 STA. 9+44.23, 72.57' RT.	1,739,614.24	2,206,086.15	574.85	
B - IRON PIN	TAXIWAY K STA. 375+89.79, 66.05' RT.	TAXIWAY K12 STA. 9+33.35, 465.99' LT.	1,739,934.26	2,205,652.84	572.29	

# **CRITICAL POINTS**

POINT NO.	LATITUDE	LONGITUDE	ELEV.*
A	41° 26' 27.60"	90° 30' 01.16"	604.00
В	41° 26' 30.20"	90° 30' 01.08"	604.00
С	41° 26' 37.51	90° 30' 01.22"	601.00
D	41° 26' 43.35"	90° 29' 55.49"	600.00
Е	41° 26' 46.47"	90° 29' 52.28"	594.00
F	41° 26' 35.60"	90° 29' 47.42"	601.20
G	41° 26' 32.35"	90° 29' 41.77"	603.30

EQUIPMENT HEIGHT

- ALL CLOSED TAXIWAY SECTIONS SHALL HAVE THE TAXIWAY EDGE LIGHTS AND TAXIWAY GUIDANCE SIGNS REMOVED FROM SERVICE. IF DEACTIVATING THE CIRCUIT IMPACTS AN OPEN TAXIWAY SECTION, THE EDGE LIGHTS AND GUIDANCE SIGNS MAY BE COVERED IN A MANNER THAT PREVENTS VISIBLE LIGHT. ADDITIONALLY, A TEMPORARY JUMPER MAY BE INSTALLED TO BEMOVE THE LIGHTS FROM THE ACTIVE CIRCUIT. METHOD OF DEACTIVATION SHALL BE APPROVED BY THE RESIDENT ENGINEER. THIS WORK SHALL BE
- CONTRACTOR SHALL INSTALL TAXIWAY CLOSURE MARKERS AND REMOVE TAXIWAY LEAD-IN LINES AS SHOWN OR AS DIRECTED BY THE RESIDENT ENGINEER TO MINIMIZE IMPACT TO THE AIRPORT THIS WORK SHALL BE EXPEDITED AND COORDINATED TO BE COMPLETED WITHIN THE SAME CALENDAR DAY. SEE SEQUENCE OF CONSTRUCTION DETAILS SHEET FOR TAXIWAY CLOSURE MARKER DETAILS
- CONTRACTOR SHALL INSTALL AND MAINTAIN BUNWAY

- OF VARIOUS AIRFIELD PAVEMENTS THROUGHOUT THE ENGINEER A MINIMUM OF 72 HOURS PRIOR TO CLOSURE SEE PHASING SUMMARY TABLE LOCATED ON SEQUENCE
- THE LOCATION OF THE BARRICADES SHALL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE RESIDENT ENGINEER. SHOULD THE PHASING REQUIRE THE BARRICADES TO BE REPOSITIONED THE WORK SHALL BE

- PLACE RUNWAY CLOSED MARKERS ON BOTH ENDS OF RUNWAY 13/31 AND PLACE BARRICADES AS SHOWN OR AS DIRECTED BY THE ENGINEER.

- EXCAVATE TO SUBGRADE AND PLACE PGE AND AGGREGATE BASE COURSE
- CONSTRUCT PCC PAVEMENT AND DRAINAGE

- CLOSUBE MARKERS
- SAFETY AREA OF RUNWAY AND REOPEN RUNWAY 13/31.

- AND PLACE BARRICADES AS SHOWN OR DIRECTED BY THE **FNGINFFR**
- BASE COURSE

BARRICADES, REMOVE HAUL ROAD AND REOPEN ALL TAXIWAYS



### GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE BEOLIBEMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2F, AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL 2. SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2F. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER З. PERSONNEL AND MEETING SAFETY REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING 4. THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE 5. CONTRACTOR SHALL SUBMIT THE SPCD FOR APPROVAL.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL 6. SIGN THE SWPPP CERTIFICATION STATEMENT.
- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE RESIDENT ENGINEER. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT
- 8. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS. FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER AND AIRPORT FOR ALL PHASES ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK 9. SHALL BE REQUIRED TO BE ONSITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE AIRPORT PAYMENT FOR DUST CONTROL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 10. PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A) LATH AND RIBBON, ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE 11. CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.

#### 1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE, THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT
- THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A COORDINATION PLAN WITH THE AIRPORT DIRECTOR OF AVIATION OR HIS/HER DESIGNATED REPRESENTATIVE, REGARDING DE-ENERGIZING AND ENERGIZING OF THE AIRFIELD CIRCUITS IMPACTED BY CONSTRUCTION ACTIVITY
- CONTRACTOR SHALL PLAN HIS/HER WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS WORK OR HALL BOAD ACCESS OF OTHER CONTRACTORS (SEE STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORT AND SPECIAL PROVISIONS SECTION 50-05) THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT:
  - INSTALL RWY 9 PAPI AND AIRFIELD SIGNAGE UPGRADES **REHABILITATE TAXIWAY H2**

### 2. PHASING

- TOTAL CONTRACT TIME SHALL BE 55 CALENDAR DAYS.
- PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET.

- 3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY
- ALL BUNWAYS, TAXIWAYS AND APBONS SHALL BE KEPT OPEN TO 1. AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET.
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND 2. AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT
- AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO З. ONCOMING AIRCRAFT AT ALL TIMES.
- SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO

#### 4. PROTECTION OF NAVIGATION AIDS (NAVAIDS)

THE CONTRACTOR SHALL REMAIN CLEAR OF THE ILS CRITICAL AREAS AND OTHER NAVAIDS FACILITIES AT ALL TIMES.

### 5. CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION SAFETY AND PHASING PLAN SHFFTS
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE EXISTING GATE SHOWN. THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY CONSTRUCTION VEHICLES ACCESS AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL CONFORM TO CITY OF MOLINE AND IDOT CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE.
- CERTAIN CONTRACTOR EMPLOYEES SHALL OBTAIN AN AIRPORT IDENTIFICATION BADGE. THIS CONSISTS OF FILLING OUT ALL З. NECESSARY PAPERWORK, FINGERPRINTING, ATTENDING AND PASSING A TRAINING CLASS CONCERNING SAFETY AND SECURITY AT THE AIRPORT. CONTRACTOR EMPLOYEES MUST MEET CERTAIN BACKGROUND CHECK CRITERIA AND THE CONTRACTOR MUST MAKE CERTAIN CERTIFICATION ABOUT FACH EMPLOYEE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FINGERPRINTING COSTS. ALL COSTS ASSOCIATED WITH OBTAINING THE IDENTIFICATION BADGE SHALL BE BORNE BY THE CONTRACTOR.
- ALL CONTRACTOR EMPLOYEES WHO ARE DESIGNATED AS DRIVERS FOR 4. THE CONTRACTOR WITHIN THE AIRFIELD OPERATION AREA (AOA) SHALL ALSO ATTEND AND PASS THE AIRPORT DRIVERS TRAINING PROGRAM. PERMITTED TO OPERATE VEHICLES OR EQUIPMENT ON THE AIRPORT WITHOUT AN ESCORT. ALL COST ASSOCIATED WITH THE DRIVERS TRAINING PROGRAM SHALL BE BORNE BY THE CONTRACTOR.
- DRIVERS OF TRUCKS CONTAINING MATERIAL DELIVERIES (AGGREGATE, CONCRETE, ETC.) NEED NOT OBTAIN AN AIRPORT ID BADGE BUT SHALL 5. BE REQUIRED TO SUBMIT THEIR NAME, DRIVER'S LICENSE NUMBER TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE.
- THE CONTRACTOR'S STORAGE AND STAGING AREA WILL BE AS SHOWN 6 IN THE SITE PLAN AND CONSTRUCTION PHASING PLAN.
- THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL 7. EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR.
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE STORED AT THE STAGING AREA.
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE
- ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS 10. TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT IN RADIO CONTACT WITH THE ATCT. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE 11. CONTRACTOR FOR HAUL ROADS, STORAGE AREAS AND/OR STAGING AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION. NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK.
- 12. ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL NOTIFY THE AIRCRAFT RESCUE AND FIRE 13 FIGHTING (ARFF) FACILITY IF CONSTRUCTION ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT

#### 6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE 2. CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD 3. SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.

### 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

### 8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

#### 9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT.
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER 3. THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911
- CONTACTS FOR THIS PROJECT ARE AS LISTED BELOW 5.

AIRPORT OPERATOR BRUCE CARTER - DIRECTOR OF AVIATION BRYAN JOHNSON - ASSISTANT DIRECTOR OF AVIATION	(309) 757-1732 (309) 757-1754	
ENGINEER CMT - RESIDENT ENGINEER	(217) 787-8050	

- 1. COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2F MAY BE USED TO AID IN THE INSPECTIONS.

#### 11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD 1 INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROURD UTILITIES AT CRITICAL POINTS. SEE SECTION 70-17 OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE 2. AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES. SEE SECTION 70-17 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION.
- SHOULD A UTILITY COMPANY OR GOVEMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT З. FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

#### 12. PENALTIES

- NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW.
- THE GATE SHALL BE MAINTAINED, CLOSED AND LOCKED AS DIRECTED BY 2. THE AIRPORT DIRECTOR OF AVIATION. SHOULD THE CONTRACTOR'S OPERATIONS REQUIRE THE GATE TO REMAIN OPEN TO PROVIDE ACCESS TO HAULING OPERATIONS, A COMPETENT GATE GUARD SHALL BE REQUIRED TO CONTROL ACCESS TO THE AIRFIELD. A \$1,000 FINE SHALL BE ASSESSED FOR ANY OCCURRENCE OF AN UNSECURE GATE THAT IS THE CONTRACTOR'S RESPONSIBILITY. AN UNSECURED GATE SHALL BE DEFINED AS ANY GATE THAT IS NOT WITHIN THE SIGHT AND PHYSICAL CONTROL OF THE CONTRACTOR'S GUARD. IN THE EVENT THAT THE GATE MAY NOT BE SECURED, THE CONTRACTOR WILL BE CHARGED FOR AIRPORT PERSONNEL TO REMAIN AT THE GATE UNTIL SECURED.

### 12. PENALTIES (CONT.)

1.

# 14. RUNWAY AND TAXIWAY VISUAL AIDS

### **15. HAZARD MARKING AND LIGHTING**

#### **10. INSPECTION REQUIREMENTS**

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE
  - THE CONTRACTOR SHALL ATTEND AN INSPECTION OF EACH PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS.

- З.
  - 2.
- CONTRACT
- 4.

5.

THE CONTRACTOR SHALL RESTRICT ALL CONSTRUCTION ACTIVITIES TO THE CONSTRUCTION AREA DETAILED IN THE CONSTRUCTION SAFETY AND PHASING PLAN. ANY UNAUTHORIZED MOVEMENTS PEDESTRIAN OR VEHICULAR. BEYOND THE CONSTRUCTION LIMITS SHOWN SHALL BE CONSIDERED AN AIRFIELD INCURSION. AIRFIELD INCURSIONS, AT THE DISCRETION OF THE AIRPORT DIRECTOR OF AVIATION, MAY BE FINED \$10,000.00 PER INCIDENT. INCURSION FINES WILL BE ASSESSED IMMEDIATELY AND TAKEN FROM MONIES DUE THE CONTRACTOR ON THE NEXT CONSTRUCTION PAYMENT

### 13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION.

BUNWAY OR TAXIWAY CLOSURES ARE AS DETAILED IN THE CONSTRUCTION SAFETY AND PHASING PLAN FOR THIS PROJECT. IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC 150/5370-2F.

THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS. AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT

ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISOBY CIRCUILAB 150/5370-2E AND 150/5210-5C AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'

BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY THE RESIDENT ENGINEER. THE CONTRACTOR SHALL PLACE ALL BARRICADES AND CONSTRUCTION SETBACK LINES ITEMS AS SHOWN PRIOR TO INITIATING WORK IN EACH PHASE ALL COSTS TO FURNISH INSTALL, REPOSITION, AND MAINTAIN THESE ITEMS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.

THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT

ACCESS TO ACTIVE BUNWAY AND TAXIWAY PAVEMENTS (TOWER CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON TYPE II BABBICADES (2 EACH, BIGHT AND | FET). IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED. WARNING SIGNS SHALL STATE "TOWER CONTROL AREA / UNAUTHORIZED ACCESS SUBJECT TO FINE".

### 16. PROTECTION

CONTRACTOR PERSONNEL, VEHICLES, EQUIPMENT AND BARRICADES SHALL NOT BE ALLOWED WITHIN THE TAXIWAY OBJECT FREE AREA (TOFA) OF ACTIVE TAXIWAYS AND THE RUNWAY SAFETY AREA (RSA) OF ACTIVE BUNWAYS

### 17. OTHER LIMITATIONS ON CONSTRUCTION

IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.

THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A REVISED PROGRESS SCHEDULE TO ACCOMMODATE AIRPORT EVENTS (I.E. AIRSHOW). SHOULD A REVISED SCHEDULE BE REQUIRED, THE REVISION SHALL BE COMPLETED AT NO ADDITIONAL COST TO THE

THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING RUNWAYS AND TAXIWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS. THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS.

THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.

WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICAL AREA IGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS, LIGHT SHALL CONSIST OF MOVEABLE POLE MOUNTED. FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY.

BROKEN CONCRETE, BROKEN ASPHALT, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.



### LIGHTED RUNWAY CLOSURE MARKERS NOTES

- 1. THE AIRPORT SHALL FURNISH TWO PORTABLE, LIGHTED RUNWAY CLOSURE MARKERS FOR THE DURATION OF THE PROJECT. IF LIGHTED RUNWAY CLOSURE MARKERS ARE NOT AVAILABLE, THE CONTRACTOR SHALL REFER TO THE "CLOSED RUNWAY MARKER DETAIL" ON THIS SHEET.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TRANSPORTING, INSTALLING, MAINTAINING, REFUELING, REPOSITIONING AND REMOVING THE LIGHTED RUNWAY CLOSURE MARKERS AS SHOWN IN THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION
- 3. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS. WHEN CONSTRUCTION OPERATIONS CONFLICT, THE CLOSURE MARKERS SHALL BE MOVED TO AN ALTERNATE LOCATION AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER
- 4. IT WILL BE NECESSARY TO CLOSE RUNWAY 13/31 TO AIR TRAFFIC FOR THE DURATION OF PHASE A CONSTRUCTION. THE CONTRACTOR SHALL MARK RUNWAY 13/31 CLOSED BY PLACING LIGHTED RUNWAY CLOSURE MARKER AT THE LOCATION DETAILED IN THE PLANS OR AS DIRECTED BY THE ENGINEER AND AIRPORT. THE LIGHTED RUNWAY CLOSURE MARKERS ARE REQUIRED TO BE IN OPERATION ANYTIME THE RUNWAY IS CLOSED
- 5. UPON COMPLETION OF THE PROJECT, THE MARKERS SHALL BE RETURNED TO THE AIRPORT IN GOOD CONDITION.
- 6. ALL COST ASSOCIATED WITH THE LIGHTED RUNWAY CLOSURE MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.



### RUNWAY CLOSURE MARKERS NOTES

- 1. THE CONTRACTOR SHALL USE THE LIGHTED RUNWAY CLOSURE MARKERS PROVIDED BY THE AIRPORT. IF THE LIGHTED RUNWAY CLOSURE MARKERS ARE NOT AVAILABLE, THE CONTRACTOR WILL BE REQUIRED TO INSTALL RUNWAY CLOSURE MARKERS AS DETAILED ABOVE.
- 2. CLOSED RUNWAY MARKERS SHALL BE YELLOW.
- 3. MARKERS SHALL BE A MATERIAL APPROVED BY THE ENGINEER AND THE AIRPORT.
- 4. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION.
- 5. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN.
- 6. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 7. IT WILL BE NECESSARY TO CLOSE RUNWAY 13/31 TO AIR TRAFFIC FOR THE DURATION OF PHASE A CONSTRUCTION. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET OR AS DIRECTED BY THE ENGINEER AND AIRPORT, THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION





PHASE / CALENDAR DAYS	WORK AREA
PHASE A / 21 CALENDAR DAYS	WORK INSIDE RUNWAY 13/31 SAFETY AREA AND TAXIWAY K SAFETY AREA.
PHASE B / 34 CALENDAR DAYS	WORK OUTSIDE RUNWAY 13/31 SAFETY AREA AND WORK WITHIN TAXIWAY K SAFETY AREA.
55 CALENDAR DAYS	AT THE CONTRACTOR'S OPTION, PHASE A, PROVIDED RUNWAY 13/31





### STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

#### SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF CONSTRUCTION OF TAXIWAY K CONNECTOR AT THE QUAD CITY INTERNATIONAL AIRPORT. THE PROJECT INCLUDES GRADING, EXCAVATION, FILL, TOPSOIL PLACEMENT, PAVEMENT CONSTRUCTION, ELECTRICAL, LANDSCAPING AND OTHER MISCELLANEOUS CONSTRUCTION WORK

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

- . PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION
- CONTROL, SUCH AS PERIMETER SILT FENCE AND INLET PROTECTION.
- 2. EXCAVATION AND EMBANKMENT WILL BE COMPLETED WITHIN THE PROJECT LIMITS.
- 3. PAVEMENT CONSTRUCTION.
- 4. FINAL GRADING AND OTHER MISCELLANEOUS ITEMS.
- 5. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS SEEDING AND MULCHING.

### 6. REMOVAL OF TEMPORARY EROSION CONTROL / PROTECTION FACILITIES.

#### AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.56 ACRES OF WHICH 1.56 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

#### OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS

1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.

2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE

THE CONSTRUCTION SITE DRAINS INTO THE ROCK RIVER VIA OVERLAND FLOW AND THROUGH A STORM SEWER SYSTEM.

#### CONTROLS - EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION

- 1. THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- 2. AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTION AND PERIMETER SILT FENCE SHALL BE INSTALLED AS CALLED OUT IN THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 3 THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES

- 1 WITHIN THE CONSTRUCTION LIMITS. AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION
- 2 FARTH STOCKPILES SHALL BE TEMPORARILY SEEDED AT THE CONTRACTORS EXPENSE IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS

B. CONSTRUCT DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.

C. BUILD NECESSARY EMBANKMENT AT CULVERT/STORM SEWER LOCATIONS AND THEN EXCAVATE AND PLACE PIPE.

D. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS

4. CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLITIANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS I FAKING FOUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.

5. THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD.

6. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION CONTROL ITEMS

7. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

#### ALLOWABLE NON-STORM WATER DISCHARGES:

- 1. DISCHARGES FROM FIRE-FIGHTING ACTIVITIES
- 2. FIRE HYDRANT FLUSHINGS;
- 3. WATER USED TO CONTROL DUST
- 4. POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHINGS;
- 5. UNCONTAMINATED GROUND WATER OR SPRING WATER;
- 6. UNCONTAMINATED EXCAVATION DEWATERING;
- 7. LANDSCAPE IRRIGATION

### RUNOFF COEFFICIENT AFTER CONSTRUCTION = 0.90

WHEN REQUESTED BY THE CONTRACTOR, THE RESIDENT ENGINEER WILL PROVIDE GENERAL MAINTENANCE GUIDES TO THE CONTRACTOR FOR THE PRACTICES ASSOCIATED WITH THIS PROJECT. THE FOLLOWING ADDITIONAL PROCEDURES WILL BE USED TO MAINTAIN, IN GOOD AND EFFECTIVE OPERATING CONDITIONS, THE VEGETATION, EROSION AND SEDIMENT CONTROL MEASURES AND OTHER PROTECTIVE MEASURES IDENTIFIED IN THIS PLAN. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN MAINTENANCE GUIDELINES FOR ANY MANUFACTURED BMPS WHICH ARE TO BE INSTALLED AND MAINTAINED PER MANUFACTURE'S SPECIFICATIONS.

1. SEEDING - WHERE TEMPORARY CESSATION OF THE FARTH DISTURBING ACTIVITIES OCCURS STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN 1 WORKING DAY IF WORK WILL NOT RESUME FOR A PERIOD EXCEEDING 14 DAYS.

2. PERIMETER EROSION BARRIER - SEDIMENT WILL BE REMOVED IF THE INTEGRITY OF THE FENCING IS IN JEOPARDY AND ANY FENCE KNOCKED DOWN WILL BE REPAIRED IMMEDIATELY

3. DITCH CHECK - SEDIMENT WILL BE REMOVED IF THE INTEGRITY OF THE DITCH CHECK IS IN JEOPARDY, ANY DITCH CHECKS WHICH FAILS WILL BE REPAIRED OR REPLACED IMMEDIATELY

4. INLET PROTECTION/FILTERS - SEDIMENT WILL BE REMOVED IF THE INTEGRITY OF THE INLET PROTECTION IS IN JEOPARDY. ANY INLET PROTECTION FILTERS WHICH FAILS WILL BE REPLACED IMMEDIATELY



FROM NRCS STANDARD DRAWING NO. IL-63

FILE: 09 SWPPP NOTES 1.dwg UPDATE BY: Sean Smith PLOT DATE: 6/26/2015 3:49 PM QU020 REVISIONS BY DATE NUMBER INCIDENCE OF NON-COMPLIANCE (ION) REPORT FOR THE IDENTIFIED VIOLATION WITHIN FIVE (5) THIS BAR IS EQUAL TO 2 AT FULL SCALE (34X22) ISLAND PLAN I PREVENTION F ILS SHEET 1 **CONNECTOR (K12)** Y OF ROCK | AIRPORT F AUTHORITY ( RNATIONAL A IE, ILLINOIS ETAIL: POLLUTION ¥ **CONSTRUCT TAXIWAY** ETROPOLITAN AIRPORT A QUAD CITY INTERN MOLINE, AND S **STORMWATER** Ш NOT Σ STABILIZED CONSTRUCTION ENTRANCE NOTES FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFIED UNDER SECTION 1080.03, OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007 ROCK OR RECLAIMED CONCRETE SHALL MEET ONE OF THE FOLLOWING IDOT COARSE AGGREGATE GRADATION, CA-1, CA-2, CA-3 OR CA-4. COMPACTION SHALL BE TO THE BS & SATISFACTION OF THE ENGINEER. ANY DRAINAGE FACILITIES REQUIRED BECAUSE OF WASHING SHALL BE CONSTRUCTED ACCORDING TO Συ QUAD MANUFACTURERS SPECIFICATIONS AND SHALL BE INCIDENTAL TO THE CONTRACT. 4. MINIMUM WIDTH IS 14' FOR ONE-WAY TRAFFIC AND 20' FOR 1 TWO WAY TRAFFIC. TWO-WAY TRAFFIC WIDTHS SHALL BE INCREASED A MINIMUM OF 4' FOR TRAILER TRAFFIC. DEPENDING ON THE TYPE OF VEHICLE OR EQUIPMENT, SPEED, LOADS, CLIMATIC AND OTHER CONDITIONS UNDER DESIGN BY: CMT WHICH VEHICLES AND EQUIPMENT OPERATE AN INCREASE DRAWN BY CMT IN THE MINIMUM WIDTHS MAY BE REQUIRED. CHECKED BY SMS 5. ROADWAY SHALL FOLLOW THE CONTOUR OF THE NATURAL APPROVED BY MND TERRAIN TO THE EXTENT POSSIBLE. DATE: JUNE 26. 2015 6. IF WASH RACK ARE USED THEY SHALL BE INSTALLED JOB Not 14014-07-00 ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS IL. PROJ. NO. MLI-4482 AIP PROJ. NO. 3-17-0068-XX 7. THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE INCIDENTAL TO THE CONTRACT. SHEET 09 OF 27 SHEETS

INSPECTIONS: QUALIFIED PERSONNEL SHALL INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE WHICH HAVE NOT YET BEEN FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES AND EQUIPMENT ENTER AND EXIT THE SITE USING IDOT STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (BC 2259). SUCH INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND INSPECTIONS MAY BE REDUCED TO ONCE PER MONTH WHEN CONSTRUCTION ACTIVITIES HAVE DISCHARGE DUE TO SNOWMELT OCCURS. IF ANY VIOLATION OF THE PROVISIONS OF THIS PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION WORK COVERED BY THIS PLAN, THE BY EMAIL AT: EPA.SWNONCOMP@ILLINOIS.GOV, TELEPHONE OR FAX WITHIN TWENTY-FOUR (24) HOURS OF THE INCIDENT. THE RESIDENT ENGINEER SHALL THEN COMPLETE AND SUBMIT AN SHALL INCLUDE SPECIFIC INFORMATION ON THE CAUSE OF NONCOMPLIANCE, ACTIONS WHICH WERE TAKEN TO PREVENT ANY FURTHER CAUSES OF NONCOMPLIANCE, AND A STATEMENT NONCOMPLIANCE. ALL REPORTS OF NON-COMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G OF THE PERMIT ILR10.THE INCIDENCE OF NON-COMPLIANCE SHALL BE MAILED TO THE FOLLOWING ADDRESS: ILLINOIS ENVIRONMENTAL PROTECTION AGENCY ATTN: COMPLIANCE ASSURANCE SECTION 1021 NORTH GRAND EAST SPRINGFIELD, ILLINOIS 62794-9276ADDITIONAL INSPECTIONS REQUIRED:

WITHIN TWENTY-FOUR (24) HOURS OF THE END OF A STORM OR BY THE END OF THE FOLLOWING BUSINESS OR WORK DAY THAT IS 0.5 INCH OR GREATER OR EQUIVALENT SNOWFALL. CEASED DUE TO FROZEN CONDITIONS. WEEKLY INSPECTIONS WILL RECOMMENCE WHEN CONSTRUCTION ACTIVITIES ARE CONDUCTED, OR IF THERE IS 0.5 OR GREATER RAIN EVENT, OR A RESIDENT ENGINEER SHALL NOTIFY THE APPROPRIATE IEPA FIELD OPERATIONS SECTION OFFICE DAYS OF THE INCIDENT. THE RESIDENT ENGINEER SHALL USE FORMS PROVIDED BY IEPA AND DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE DIVISION OF WATER POLLUTION CONTROL POST OFFICE BOX 19276 DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING: TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED. ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED MAINTENANCE AFTER CONSTRUCTION CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR



 UPON COMPLETION OF CONCRETE OPERATIONS, THE CONCRETE WASHOUT AND ALL MATERIALS CONTAINED WITHIN SHALL BE DISPOSED OF AT A LEGAL OFF-SITE LOCATION.

					FILE: 10 SWPPP N UPDATE BY: Sean PLOT DATE: 6/26,	NOTES 2.dwg Smith /2015 3:49 PM
IPP FLeXs	torm Inlet Filte	er Specificatio	ons			
ial Property	Test Method	Value (m	in ave)			
ilter Bag Specs	(2 ft <sup>3</sup> min vol)	Non-Woven	Woven Mono		QU020	
nsile	ASTM D 4632	100 lbs	200 l bs		REVI	SIONS
Strength	ASTM D 4833	65 lbs	90 l bs			
dal Tear	ASTM D 4533	45 lbs	75 lbs		NOMBER	DATE
stance	ASTM D 4355	70% at 500 hrs	90%			
n Size (AOS)	ASTM D 4751	70 sieve	40 sieve			
4		(.212 mm)	(.425 mm)			
vity	ASTM D 4491	2.0 /sec	2.1/sec			
ow Rate	ASTM D 4491	145 gpm/sqft	145 gpm/s qft		0	1 2
ter Outer Reinfo	orcement Bag Spe	ecifications			THIS BAR IS	EQUAL TO 2"
	ASTM D 3776	4.55 oz/sqy	/d +/- 15%		AT FULL SC.	ALE (34X22).
S	ASTM D 1777	.040 +/	005			1
Construction						
ctural Steel; e; Zinc Plated	ASTM A 576	Tensile Strengtl Yield Strength	n > 58,000 psi; > 36,000 psi		LAND	LAN
		LACK LETTERS	G G REWS /2") DD POST 5"x3.5"x8")	RAP .et filters	METROPOLITAN AIRPORT AUTHORITY OF ROCK IS QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS	CONSTRUCT TAXIWAY K CONNECTOR (K12) STORMWATER POLLUTION PREVENTION NOTES AND DETAILS SHEET 2
	CRETE WA SIGN DETA R EQUI∨AL	LJ SHOUT IL ENTX			CHECKED BY: CONSULTING ENGREERS DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE: DATE	CMT CMT SMS MND JUNE 26, 2015
					300 NO.	. =0, = = 0, = 00
	CONCR	ETE WASH	HOUT		IL. PROJ. N	0. MLI-4482
	N	DT TO SCALE	<u> </u>		AIP PROJ. NO.	ა-1/-0068-XX
					SHEET 10 C	F 27 SHEETS





TAXIWAY K CONNECTOR AND RUNWAY 13/31 INTERSECTION SECTION C-C

NOT TO SCALE

- (A) NEW 9" PCC PAVEMENT (501) NEW 10" CRUSHED AGGREGATE BASE COURSE (209)
- B EXISTING 9" PCC EXISTING 10" AGGREGATE BASE COURSE
- EXISTING 15" PCC EXISTING 16" CRUSHED AGGREGATE BASE COURSE (c)
- (D) EXISTING GROUNDLINE
- (E) NEW 6' WIDE SODDING (904) (F)NEW GROUNDLINE
- G NEW SEEDING AND MULCHING (908)
- (H)NEW SOIL STABILIZATION FABRIC
- $(\mathbf{I})$ NEW ISOLATION JOINT W/THICKENED EDGE PCC PAVEMENT
- (J)NEW DOWEL BAR
- (K) NEW DOWEL BAR IN EXISTING PAVEMENT



# LEGEND

FILE: 11 TYP SECTS 1.dwg UPDATE BY: Seon Smith PLOT DATE: 6/26/2015 3:49 PM Taxiway K Base PROP-GEOMETRY MLI Alignments QU020 REVISIONS NUMBER BY DATE 0 1 2					
METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS	CONSTRUCT TAXIWAY K CONNECTOR (K12) TYPICAL SECTIONS				
Cappright CWT. Inc. CAMFORD, MURPHY & TILLY, INC. CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-000613	CUAD CITY A				
DESIGN BY: DRAWN BY: CHECKED BY: APPROVED BY: DATE:	CMT CMT SMS MND JUNE 26, 2015				









1.

6" PERFORATED

- FLOW

-

DIRECT CONNECTION DETAIL

NOT TO SCALE

UNDERDRAIN PIPE

CORE OPENING

IN EXISTING PIPE

- OTHERWISE NOTED.
  - 4 OF UNDERDRAIN, COSTS INCLUDED.
  - 5.
  - 6.
  - CASTINGS

DRAINAGE STRUCTURE DATA TABLE						
STRUCTURE NUMBER	LOCATION	RIM	INVERT	NOTES		
CS-1	TXY K12 STA. 11+34, 35' LT.	575.50	INV. (IN) 572.60 INV. (OUT) 572.50	6" UNDERDRAIN		
CS-2	TXY K12 STA. 11+34, 30' RT.	575.62	INV. (IN) 572.75 INV. (OUT) 572.65	6" UNDERDRAIN		
MH-1	TXY K12 STA. 10+78, 80' RT	574.30	NW INV. (12") 572.00 N INV. (6") 572.25	4' DIA. MANHOLE		
MH-2	TXY K12 STA. 11+28, 320' LT.	573.60	SE INV. (12") 570.00 NE INV. (12") 566.57	4' DIA. MANHOLE		
DC-1	TXY K12 STA. 11+32, 335' LT.		566.50	FIELD VERIFY LOCATION		
E-1	TXY K12 STA. 10+92, 347' LT.	571.20±	UNKNOWN	EXISTING STRUCTURE		
E-2	TXY K12 STA. 11+13, 346' LT.	573.20±	563.05±	EXISTING STRUCTURE		



NOT TO SCALE





# 1. THE 6" UNDERDRAIN SHALL BE INSTALLED AFTER THE SUBGRADE IS COMPACTED.

NEW PAVEMENT

NEW TRENCH FABRIC

NEW CA-7 BACKFILL (705) -

NOTES

ENVELOPE

NEW 6" PERFORATED

UNDERDRAIN PIPE

4" (TYP)

NEW CRUSHED

AGGREGATE BASE

18"

1-1/2"

NEW GROUND LINE

INSIDE DIAMETER OF STORM SEWER (INCHES)

6

12

21

42

48

60

78

MAXIMUM RENCH WIDT

3'-7"

4'-2"

5'-0"

7'-1"

10'-7"

7'-8"

24 5'-4"

27 5'-7"

12" FARRIC

VARIABI F

DFPTH

SEE PLAN

SHEET

OVERLAP (MIN.)

(TYP)

2. THE SPOILS FROM THE 6" UNDERDRAIN CONSTRUCTION SHALL BE REMOVED DAILY FROM THE SURFACE OF THE CRUSHED AGGREGATE BASE

12"

MAX UNDERDRAIN DETAIL - EDGE OF

P.C.C. PAVEMENT AREAS

NOT TO SCALE

3. TRENCH FABRIC ENVELOPE AND CA-7 BACKFILL SHALL BE CONSIDERED INCIDENTAL TO THE UNDERDRAIN.



- TYPE 1 FRAME AND LID

(CLOSED LID)

6" TEE CONNECTION -

NEW INV. GRADE

NEW ITEM P-610

CONC. COLLAR,

6" (MIN.)

VARIABLE

DIA. R.C.P

FLOW -

PLAN VIEW UNDERDRAIN COLLECTION STRUCTURE DETAIL

NOT TO SCALE

### STORM SEWER/UNDERDRAIN NOTES

CONTRACTOR SHALL FIELD VERIFY EXISTING STORM SEWER OR UNDERDRAIN INVERTS BEFORE INSTALLING PROPOSED PIPE, CONNECTIONS AND ORDERING MATERIALS.

2. ALL UNDERDRAIN CONNECTIONS, CORING INTO STRUCTURES, CAPS, TEES, BENDS, STORM SEWER ETC. SHALL BE CONSIDERED INCLUDED IN THE COST OF THE UNDERDRAIN.

3. UNDERDRAIN SLOPES FOLLOW EDGE OF PAVEMENT SLOPE UNLESS

INSTALL PROPOSED ELECTRICAL DUCTS AND CONDUITS TO BE CLEAR

UNDERDRAIN CONFLICTS WITH EXISTING CONDITIONS SHALL BE RESOLVED AND COST SHALL BE INCIDENTAL TO UNDERDRAIN.

CORING OF DRAINAGE STRUCTURE AND REMOVAL OF EXISTING STORM SEWER MANHOLE/INLET CONCRETE BENCHES TO FACILITATE CONNECTIONS OF PROPOSED STORM SEWER AND UNDERDRAIN PIPE SHALL BE CONSIDERED INCLUDED IN THE COST OF THE PIPE.

7. ALL FRAMES, LIDS AND GRATES SHALL BE AIRPORT CONSTRUCTION













## NOTES

- 1. INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.
- 2. WRAP WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE-HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF JOINT.
- 3. THE COST OF FURNISHING AND INSTALLING ALL SPLICE MATERIALS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 4. THE CONTRACTOR SHALL HAVE A MINIMUM OF TWO (2) TYPE A SPLICE KITS ON THE JOB SITE AT ALL TIMES FOR EMERGENCY REPAIRS.
- 5. THE CONTRACTOR MAY ELECT TO USE AN FAA APPROVED PRIMARY CONNECTOR KIT OR COMPLETE KIT IN LIEU OF HEAT SHRINK KIT AT NO ADDITIONAL COST.

5/8"ø

CIRCUIT DESIGNATION

LIGHT DESIGNATION

Ő

6-23

2" DIA.

### NOTES:

- 1. INSTALL A NONCORROSIVE DISC OF 2" MINIMUM DIAMETER WITH THE NUMBER PERMANENTLY STAMPED, CUT OUT, OR ENGRAVED UNDER THE HEAD OF THE BASE PLATE BOLT OR ATTACHED TO LIGHT FLANGE WITH A SET SCREW.
- 2. NUMERALS SHOWN ARE FOR ILLUSTRATIVE NUMERALS SHOWN ARE FUR ILLUSTRATIVE PURPOSES ONLY. ALL EXISTING AND PROPOSED TAXIWAY AND RUNWAY LIGHTS SHALL BE TAGGED AS DIRECTED BY THE RESIDENT ENGINEER. ALL LIGHTS ON EXISTING CIRCUITS THAT HAVE LIGHTING IMPROVEMENTS (NEW OR RELOCATED LIGHTS) SHALL BE RETAGGED.
- 3. COST OF TAGGING LIGHTS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.





### RUNWAY/TAXIWAY LIGHTING CIRCUIT CONNECTION DETAIL

NOT TO SCALE

### GERERAL NOTES:

- THE CONCRETE BASE FOR BASE MTD. LIGHTS AND SIGNS SHALL BE TROWEL FINISHED WITH A 45' BEVELED EDGE. SLOPE TO DRAIN (610).
- TRANSFORMER HOLDER SHALL BE ANY COMMERCIALLY AVAILABLE BRICK. 2.
- 3. BREAKING GROOVE COUPLINGS SHALL NOT BE OVER 1" ABOVE GROUND LINE.
- ISOLATION TRANSFORMERS COME WITH A FACTORY INSTALLED PLUG (TYPE 1. 4. ISOURION TRANSFORMERS COME WITH A FACTORY INSTALLED FLOG (THE CLASS A, STYLE 2) AND RECEPTACLE (TYPE 1, CLASS A, STYLE 9). A TYPE 1, CLASS B, STYLE 3 PLUG AND TYPE 1, CLASS B, STYLE 10 RECEPTACLE SHALL BE INSTALLED ON THE 1/C, No. 8, 5000 V., L-824 TYPE C CABLES FOR CONNECTION TO EACH TRANSFORMER.
- TO FURTHER REDUCE THE POSSIBILITY OF WATER/MOISTURE ENTRANCE INTO THE CONNECTOR BETWEEN THE CABLE AND THE FIELD ATTACHED CONNECTOR, IT IS REQUIRED THAT A HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE BE 5. APPLIED OVER THE ENTIRE CABLE CONNECTOR.
- ALL SIGNS, LIGHTS, CABLES AND TRANSFORMERS TO BE REMOVED SHALL REMAIN THE PROPERTY OF THE AIRPORT. AT THE DISCRETION OF THE AIRPORT DIRECTOR. 6. THE CONTRACTOR MAY BE REQUIRED TO DISPOSE OF THESE MATERIALS OFFSITE.
- CONTRACTOR SHALL HAVE THE OPTION TO TRENCH OR PLOW UNIT DUCT. NO 7. ADDITIONAL PAYMENT SHALL BE MADE FOR TRENCHING.
- ALL RUNWAY/TAXIWAY EDGE LIGHTS SHALL HAVE 2" DIA. COLUMN AND FRANGIBLE 8. COUPLINGS, UNLESS NOTED OTHERWISE.
- INSTALL SAFETY GROUND TO EXISTING SIGNS AND L-867 CANS. ATTACH GROUND LUG TO EXISTING CAN AND INSTALL GROUND ROD 9. AS SHOWN ON PLANS.



#### TURF CABLE MARKER DETAIL TO SCALE

NOTES:

1.

2.

- CABLE MARKERS SHALL BE INSTALLED AT ALL BENDS AND EVERY 200' ALONG THE CABLE RUN
- ITEM 610 CONCRETE SHALL BE USED.
- ALL EXPOSED EDGES SHALL BE EDGED WITH A 1/4" RADIUS TOOL. .3.
- THE COST OF FURNISHING AND INSTALLING NEW MARKERS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 5. 0.049 CU. YD. CONCRETE PER MARKER

BACKFILL RESTORATION PER SPEC. 108-3.5 (TYP.) SAND OR EARTH BACKFILL (TYP.) (SEE SPECIFICATIONS)



SHEET 20 OF 27 SHEETS









NOT TO SCALE

100' MAX



## TAXIWAY CENTERLINE DETAIL

NOT TO SCALE



# SURFACE PAINTE

- 1. ALL SURFACE PAINTED HOLDING POSITION SIGNS SHALL HAVE A RED REFLECTIVE BACKGROUND WITH A WHITE REFLECTIVE INSCRIPTION.

- 4. LEGENDS SHALL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE AIRPORT MANAGER.



ENHANCED TAXIWAY CENTERLINE MARKING NOT TO SCALE

OCATION	3' TO TAXIWAY CENTERLINE
VARIES PER LEGEND 15"	
< <b>-</b> <	
RED BACKGROUND	ł
	201
NOT TO SCALE	

- 2. ALL SURFACE PAINTED LOCATION SIGNS SHALL HAVE A BLACK BACKGROUND WITH A YELLOW REFLECTIVE INSCRIPTION.
- 3. ALL SURFACE PAINTED SIGNS SHALL BE OUTLINED WITH A 6" BLACK BORDER.
- ALL LETTERS, NUMBERS AND SYMBOLS SHALL CONFORM TO FAA ADVISORY CIRCULAR 150/5340-1(LATEST EDITION).

# BLACK BORDER SHALL NOT REQUIRE REFLECTIVE MEDIA

FILE: 23 MARK DETS.dwg UPDATE BY: Sean Smith PLOT DATE: 6/26/2015 3:54 PM					
	REVIS	IONS			
NUMBER	В	Y	DATE		
0	1		2		
THIS B. AT FU	AR IS LL SCA	EQUAL LE (34	TO 2" X22).		
METROPOLITAN AIRPORT AUTHORITY OF ROCK ISLAND QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS		CONSTRUCT TAXIWAY K CONNECTOR (K12)	PAVEMENT MARKING DETAILS		
1			1		
COMPACT Copyright CMT. Inc. CRAWFORD, MURPHY & TLLY, NC.	CONSULTING ENGINEERS License No. 184-000613		QUAD CITY MTERMITOWLARPOTT		
CCAPATION CONTINUES CARAWEORD, MUGHHY & TILLY, NC.	License No. 184-000613	CMT	QUAD CITY SAME AND A LAPORT		
CHECKED BEAM CART. Inc. BARANT CHECKED MERHY & TILLY, NC.	License No. 184-000613	CMT CMT SMS	QUAD CITY S		
CHECKED E CHECKED E CHECKED MARHHY & TILLY, NC.	日 13 13 13 14 14 14 14 14 14 14 14 14 14 14 14 14	CMT CMT SMS MND			
Ceppingit cur, Inc. Gooppingit cur, Inc. DESIGN BA DESIGN BA CHECKED E APPROVED DATE: JOB No:	D X CONSULTING ENGINEERS	CMT CMT SMS MND JUNE 14014	26, 2015 -07-00		
CHECKED E APPROVED DATE: JOB No: LL. PF	I CONSULTING ENGINEERS	CMT CMT SMS MND JUNE 14014 2. MLI-	26, 2015 07-00		

			377		11	
	LEGEND					
	NEW PCC PAVEMENT					
	NOTES		STA. 1 STA. 1 826	STA.1	82 STA 1	
	<ol> <li>ALL EARTHWORK QUANTITIES ARE CALCULATED BASED ON THE INITIAL OR FINAL POSITION AS SHOWN IN THE PLANS AND QUA METHOD OF AVERAGE END AREAS.</li> </ol>	MATERIAL IN ITS NTIFIED BY THE	0+54	(3+00 (2+50 (1+50)		
	<ol> <li>AREAS OF UNSUITABLE MATERIAL/UNDERCUT AREAS (PAID AS A BE AS DESIGNATED BY THE ENGINEER. THE QUANTITY O MATERIAL/UNDERCUT AREAS SHALL NOT BE USED AS EME MATERIAL UNLESS AUTHORIZED BY THE ENGINEER.</li> </ol>	R152410) SHALL )F UNSUITABLE 3ANKMENT FILL				
	<ol> <li>PAYMENT FOR UNCLASSIFIED EXCAVATION IS THE SUM OF TOPS UNCLASSIFIED EXCAVATION AND UNDERCUT AREAS AND SHAL UNDER ITEM NO. AR152410.</li> </ol>	SOIL STRIPPING, L BE PAID FOR				
	<ol> <li>ALL HAUL ROADS TO BE CONSTRUCTED FOR THE PROJECT MEASURED FOR PAYMENT BUT SHALL BE CONSIDERED INCID PROJECT.</li> </ol>	WILL NOT BE ENTAL TO THE				
	<ol> <li>ANY CONTRACTOR HAUL ROADS TO THE SITE SHALL BE RES MINIMUM OF TOPSOIL PLACED. ALL HAUL ROAD RESTORAT INCIDENTAL TO THE CONTRACT AND NO SEPARATE PAYMENT SHA</li> </ol>	TORED WITH 4" 'ION SHALL BE ALL BE MADE.	380			
A AND SHORE VATENCE HILL CARE DEMONSTORE IT ALL WITER ALL ONE TOTALE BIAL BE HANDED OF AND DEVOLUTION OF AND DEVOLUTION AND A AND SHORE AND TO AND THE ADDRESS THE RELIVER IT ALL AND THE PROPOSED TAXINA' K12      PROPOSED TAXINA' K12      PROPOS	<ol> <li>TOPSOIL PLACEMENT AND SHOULDER FILL SHALL BE CONSIDER THE CONTRACT UNIT PRICE FOR TOPSOIL STRIPPING (ITEM SEPARATE PAYMENT WILL BE MADE FOR TOPSOIL PLACEMENT FILL.</li> </ol>	ED INCLUDED IN AR152410). NO AND SHOULDER			20 	21 22 23 TAXIWAY B2
A A VESS SUBJECT SUBJ	<ol> <li>ANY EXCESS MATERIAL INCLUDING EMBANKMENT FILL MATERIA SHALL BE HAULED OFF AND DISPOSED OF BY THE CONTF ADDITIONAL COST TO THE CONTRACT.</li> </ol>	L AND TOPSOIL ACTOR AT NO		OSED TAXIWAY K12		(PCC PAVEMENT)
	8. A 15% SHRINKAGE FACTOR WAS USED TO DETERMINE THE REQU INITIAL POSITION. THE DIFFERENCE BETWEEN THE REQU REQUIRED CUT QUANTITY WAS USED TO DETERMINE THE NUN YARDS OF MATERIAL TO BE DISPOSED OF OFF AIRPORT ADJUSTMENTS IN EARTHWORK QUANTITIES WILL BE ALLOWED F IN ACTUAL SHRINKAGE AND OR EXPANSION FACTORS ENCOUN CONSTRUCTION.	IRED FILL IN ITS RED FILL AND /BER OF CUBIC PROPERTY. NO OR VARIATIONS ITERED DURING	Φ			
19. TOPOLI SHALL NOT BUSINESS     UNITED THE USED CORE ENAMAGENET UNDER HER SAVENEENT OR WITH WHE USED CORE ENAMAGENET TABLE.       11. DORTROTOR SHULL ENSURE THUT A 1 THERE LIVER OF TORSULE LAW BE INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SHULL ENSURE THUT A 1 THERE LIVER OF TORSULE LAW BE INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SHULL ENSURE THUT A 1 THERE LIVER OF TORSULE LAW BE INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SHULL ENSURE THUT A 1 THERE LIVER OF TORSULE LAW BE INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SHULL ENSURE THUT A 1 THE ENSURE THE EQUATITY OF OVEREXAMITENT INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SUMMARY TABLE     TOTAL INVERTIGATE.     INVERTIGATE.       11. DORTROTOR SUMMARY TABLE     TOTAL INVERSION OF TOTAL INVERTIGATION OF OVEREXAMITENT     INVERTIGATE.       11. DORTROTOR SUMMARY TABLE     TOTAL INVERTIGATE.     TOTAL INVERTIGATE.       11. DORTROTOR SUMMARY TABLE     TOTAL INVERTIGATE.     TOTAL INVERTIGATE.       11. DORTROTOR SUMMARY TABLE     TOTAL INVERTIGATE.     TOTAL INVERTIGATE.       11. DORTROTOR     244 Or     INVERTIGATE.     INVERTIGATE.	9. ANY TESTING AND HANDLING REQUIRED BY THE CONTRACTOR'S DISPOSAL FACILITY FOR COMPLIANCE REGULATIONS SHALL BE COMPLETED AT THE CONTRACTOR'S E CONTRACTOR ENCOUNTERS ANY SOIL FROM THIS SITE/PRO POTENTIALLY CONTAMINATED, THE ENGINEER AND OWNER SHA PRIOR TO HAULING THE POTENTIALLY CONTAMINATED SOIL OFF	ACTOR AND/OR WITH CCDD XPENSE. IF THE DJECT THAT IS LL BE NOTIFIED SITE.			WAY 13/31 C PAVEMENT)	
11. CONTRACTOR SHALL ENSURE TWY A 7 HICK LAFER OF OFFICIU CAN BE MARED OWNER HE OWNER UP THE DETURBANCE UNITS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASES IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASE IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASE IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASE IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASE IT MAY BE RECESSARY TO OVEREXCAVATE BURS. IN SOME CASE IT MAY BE RECESSARY TO OVER BURSNEW AND	10. TOPSOIL SHALL NOT BE USED FOR EMBANKMENT UNDER NEW WITHIN THE LIMITS OF THE TAXIWAY SAFETY AREA (TSA).	PAVEMENT OR				
EARTHWORK SUMMARY TABLE (BEE NOTE)         TOTAL (FUE AND ANTSAU)         UNIT           387         388         389         38           387         388         389         38           1000000000000000000000000000000000000	11. CONTRACTOR SHALL ENSURE THAT A 4" THICK LAYER OF TO PLACED OVER THE ENTIRETY OF THE DISTURBANCE LIMITS. IN 3 MAY BE NECESSARY TO OVEREXCAVATE IN AREAS IN ORDER T REQUIRED THICKNESS OF TOPSOILING. THE QUANTITY UNCLASSIFIED EXCAVATION, INCLUDES THE QUANTITY OF OV NEEDED.	DPSOIL CAN BE SOME CASES. IT O PROVIDE THE FOR AR152410, 'EREXCAVATION				
EARTHWORK SUMMARY TABLE         TOTAL         UNIT           967         398         389         38           188         189         188         187           UNCLASSIFIED EXCAVATION (NON-TOPSOL SUBGRADE(INITIAL POSITION)         640         CV           10250L STRIPPING - 127 (INITIAL POSITION)         2.444         CV           10250L STRIPPING - 127 (INITIAL POSITION)         1.288         CV           10250L STRIPPING - 127 (INITIAL POSITION)         1.288         CV           10250L STRIPPING - 127 (INITIAL POSITION)         1.288         CV           10350L STRIPPING - 112, INITIAL         1.288         CV           10350L STRIPPING - 112, INITIAL INIT			384		8	
EARTHWORK SUMMARY TABLE (SEE WOTE)         TOTAL OUANTITY         UNIT OUANTITY         UNIT OUANTITY <th></th> <th></th> <th></th> <th></th> <th></th> <th></th>						
EARTHWORK SUMMARY TABLE         TOTAL         UNIT           (SEE NOTE)         (GUANTITY         UNIT           UNCLASSIFIED EXCAVATION (NON-TOPSOIL SUBGRADE)(INITIAL POSITION)         649         CY           TOPSOIL STRIPPING- 12' (INITIAL POSITION)         649         CY           TOPSOIL STRIPPING- 12' (UNITAL POSITION)         2.444         CY           TOTAL CUT (UNCLASSIFIED EXCAVATION ARIS2110)         3.093         CY           EMBANGMENT FILL (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION)         628         CY           TOTAL FILL (OUTSIDE TSA AND POSOIL SUBGRADE)(INTIAL POSITION)         1.328         CY           TOTAL EXCESS MATERIAL (TO BE HAULED OFF)         1.954         CY					/  ±	
EARTHWORK SUMMARY TABLE (see note)         TOTAL QUANTITY         UNIT QUANTITY         UNIT           UNCLASSIFIED EXCAVATION (NON-TOPSOIL SUBGRADE/(INITIAL POSITION)         649         CY           TOPSOIL STRIPPING-12* (INITIAL POSITION)         649         CY           INFORMATION (NON-TOPSOIL SUBGRADE/(INITIAL POSITION)         649         CY           INFORMATION (INITIAL POSITION)         2,444         CY           INFORMATION (INITIAL POSITION)         2,444         CY           INFORMATION ARISANION ARISANIO         3,093         CY           INFORMATION (INITIAL POSITION)         628         CY           INFORMATION (INITIAL POSITION)         628         CY           INFORMATION INTICULAR FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION)         1,326         CY           INFORMATION TOTAL EXCESS MATERIAL (TO BE HAULED OFF)         1,954         CY						
Barthwork summary table (see note)         Total QUANTITY         UNIT QUANTITY         UNIT QUANTITY         UNIT           unclassified excavation (NON-TOPSoil subgrade)(INITIAL POSITION)         649         CY           TOPSoil Stripping - 12° (INITIAL POSITION)         649         CY           TOPSoil Stripping - 12° (INITIAL POSITION)         2,444         CY           Total cut (unclassified excavation anisotition)         628         CY           Non-structural fill (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION)         628         CY           Non-structural fill (OUTSIDE TSA AND TOPSoilling)(FINAL POSITION)         1.326         CY           Total excess material (to be hauled off)         1.954         CY			386			186
LART HWORK SUBMINARY TABLE (SEE NOTE)       IOTAL QUANTITY       IOTAL QUANTITY       IOTAL QUANTITY         UNCLASSIFIED EXCAVATION (NON-TOPSOIL SUBGRADE)(INITIAL POSITION)       649       CY         TOPSOIL STRIPPING - 12" (INITIAL POSITION)       2,444       CY         TOTAL CUT (UNCLASSIFIED EXCAVATION AR152410)       3,093       CY         EMBANKMENT FILL (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION)       628       CY         NON-STRUCTURAL FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION)       1,326       CY         TOTAL LYCESS MATERIAL (TO BE HAULED OFF)       1,954       CY				387 388	389	199 197
UNCLASSIFIED EXCAVATION (NON-TOPSOIL SUBGRADE)(INITIAL POSITION)       649       CY         TOPSOIL STRIPPING - 12" (INITIAL POSITION)       2,444       CY         TOTAL CUT (UNCLASSIFIED EXCAVATION AR152410)       3,093       CY         BMBANKMENT FILL (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION)       628       CY         NON-STRUCTURAL FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION)       1,326       CY         TOTAL EXCESS MATERIAL (TO BE HAULED OFF)       1,954       CY	EANINWORK SUMMARY TABLE (SEE NOTE)			TAXIWAY K12	389	
IOPSOIL STRIPPING-12" (INITIAL POSITION)       2,444       CY         IDDAME       ADDAME       ADDAME       ADDAME         IDDAME       ADDAME       ADDAME       ADDAME       ADDAME         IDDAME       IDDAME       ADDAME       CY       IDDAME       ADDAME       IDDAME       ADDAME       <	UNCLASSIFIED EXCAVATION (NON-TOPSOIL SUBGRADE)(INITIAL POSITION)	649 CY		(PCC PAVEMENT)		(POU PAVEMENT)
EMBANKMENT FILL (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION) 628 CY NON-STRUCTURAL FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION) 1,326 CY TOTAL FILL 1,954 CY TOTAL EXCESS MATERIAL (TO BE HAULED OFF) 1,954 CY	TOPSOIL STRIPPING - 12" (INITIAL POSITION)	2,444 CY 3.093 CY				<u>م</u>
NON-STRUCTURAL FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION)     1,326     CY       TOTAL FILL     1,954     CY       TOTAL EXCESS MATERIAL (TO BE HAULED OFF)     1,954     CY	EMBANKMENT FILL (UNDER PAVEMENT AND WITHIN TSA)(FINAL POSITION)	628 CY				
TOTAL FILL     1,954     CY       TOTAL EXCESS MATERIAL (TO BE HAULED OFF)     1,954     CY	NON-STRUCTURAL FILL (OUTSIDE TSA AND TOPSOILING)(FINAL POSITION)	1,326 CY			84	l D
TOTAL EXCESS MATERIAL (TO BE HAULED OFF) 1,954 CY	TOTAL FILL	1,954 CY				
	TOTAL EXCESS MATERIAL (TO BE HAULED OFF)	1,954 CY				





SC = STRUCTURAL CUT

SF = STRUCTURAL (EMBANKMENT) FILL

TF = TOPSOIL FILL









SC = STRUCTURAL CUT

SF = STRUCTURAL (EMBANKMENT) FILL

TF = TOPSOIL FILL







