| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 55 | * | WILL | 608 | 8 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

# SUMMARY OF QUANTITIES

90% FED./10% STATE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY (URBAN) | WILL COUNTY: ROADWAY IL-59 90% FED 10% STATE | ROADWAY I-55 90% FED 10% STATE | ROADWAY NB RAMP 90% FED 10% STATE | ROADWAY SB RAMP 90% FED 10% STATE | ROADWAY SEIL RD 90% FED 10% STATE | ROADWAY FRONTG RD 90% FED 10% STATE | BRIDGE IL59 NB EXIT RAMP OVER I-55 | BRIDGE IL59 OVER DUPAGE RIVER | SIGNING | EXPRESSWAY LIGHTING 100% STATE | VILLAGE LIGHTING 100% VOS | TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS | CITY OF JOLIET 100% JOLIET | 90% FED./10% STATE: RETAINING WALLS CULVERTS | VILLAGE OF SHOREWOOD 100% VOS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | CONSTRUCTION TYPE CODE | | | | | | | | | | | | | | |
| | | | | J000-2A | I000-2A | J000-2A | J000-2A | I000-2A | I000-2A | X271-2A | X081-2A | Y002-2A | Y030-1E | Y030-1E | Y031-1F | J000-2A | Y007 | J000-2A |
| 5421A012 | PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY) | FOOT | 80 | 80 | | | | | | | | | | | | | | |
| 5421A015 | PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY) | FOOT | 40 | | | | | 40 | | | | | | | | | | |
| 5421A018 | PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY) | FOOT | 20 | 20 | | | | | | | | | | | | | | |
| 5421A036 | PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY) | FOOT | 177 | | | | | 177 | | | | | | | | | | |
| 542A0215 | PIPE CULVERTS, CLASS A, TYPE 1 10" | FOOT | 52 | | | | | 52 | | | | | | | | | | |
| 542A0217 | PIPE CULVERTS, CLASS A, TYPE 1 12" | FOOT | 183 | 57 | | | | 45 | 81 | | | | | | | | | |
| 542A0220 | PIPE CULVERTS, CLASS A, TYPE 1 15" | FOOT | 53 | | | | | 53 | | | | | | | | | | |
| 542A0235 | PIPE CULVERTS, CLASS A, TYPE 1 30" | FOOT | 50 | | | 50 | | | | | | | | | | | | |
| 542A1057 | PIPE CULVERTS, CLASS A, TYPE 2 12" | FOOT | 260 | 260 | | | | | | | | | | | | | | |
| 542A1060 | PIPE CULVERTS, CLASS A, TYPE 2 15" | FOOT | 60 | 60 | | | | | | | | | | | | | | |
| 542A1066 | PIPE CULVERTS, CLASS A, TYPE 2 21" | FOOT | 42 | | | | 42 | | | | | | | | | | | |
| 542A1069 | PIPE CULVERTS, CLASS A, TYPE 2 24" | FOOT | 124 | 51 | | | 73 | | | | | | | | | | | |
| 542A5473 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18" | FOOT | 106 | | | | 69 | 37 | | | | | | | | | | |
| 542A5479 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24" | FOOT | 444 | | | | | 444 | | | | | | | | | | |
| 542A5491 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | FOOT | 38 | | | | | | 38 | | | | | | | | | |
| 55034300 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19 | FOOT | 113 | | | | | 113 | | | | | | | | | | |
| 55034400 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE SPAN 34, RISE 22 | FOOT | 331 | 331 | | | | | | | | | | | | | | |
| 55034600 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 45, RISE 29 | FOOT | 724 | | | | | 724 | | | | | | | | | | |
| 55035400 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19 | FOOT | 47 | | | | 47 | | | | | | | | | | | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 939 | 349 | | | 14 | 576 | | | | | | | | | | |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1 15" | FOOT | 271 | 9 | | | | 262 | | | | | | | | | | |
| 550A0200 | STORM SEWERS, CLASS A, TYPE 1 54" | FOOT | 208 | 208 | | | | | | | | | | | | | | |
| 550A0210 | STORM SEWERS, CLASS A, TYPE 1 60" | FOOT | 427 | 427 | | | | | | | | | | | | | | |
| 550A0230 | STORM SEWERS, CLASS A, TYPE 1 72" | FOOT | 620 | 620 | | | | | | | | | | | | | | |
| 550A0260 | STORM SEWERS, CLASS A, TYPE 1 90" | FOOT | 146 | 146 | | | | | | | | | | | | | | |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 3257 | 3084 | | 96 | | 77 | | | | | | | | | | |
| 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 1729 | 1278 | | 416 | 35 | | | | | | | | | | | |
| 550A0380 | STORM SEWERS, CLASS A, TYPE 2 18" | FOOT | 368 | 268 | | 100 | | | | | | | | | | | | |
| 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | FOOT | 5 | 5 | | | | | | | | | | | | | | |
| 550A0420 | STORM SEWERS, CLASS A, TYPE 2 27" | FOOT | 326 | 326 | | | | | | | | | | | | | | |
| 550A0520 | STORM SEWERS, CLASS A, TYPE 2 72" | FOOT | 209 | 209 | | | | | | | | | | | | | | |

* DENOTES SPECIALTY ITEMS

Rev. 7-17-08

REV.

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

## SUMMARY OF QUANTITIES 5

SCALE:
DRAWN BY: JB
DATE: 03/14/08
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0600

..\SU000RS5.DGN..\SU000RR3.DGN..\TTB00RNA.DGN
3-24-2008,10:37:48 T:\DOCUMENT\932790\CIVIL\DGN\SU000SQA.DGN
B0N0HU0 0T0HU0 6263