F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	16
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

SUMMARY OF QUANTITIES

90% FED./10% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	WILL COUNTY: ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	90% FED./10% STATE: RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
					CONSTRUCTION TYPE CODE														
*	C2C05924	SHRUB, RHUS GLABRA (SMOOTH SUMAC), 2' HEIGHT, CONTAINER	EACH	200		200													
*	C2C06024	SHRUB, RHUS TYPHINA (STAGHORN SUMAC). 2' HEIGHT, CONTAINER	EACH	150		150													
*	D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	11								11							
*	D2003172	EVERGREEN, PSUEDOTSUGA MENZIESII (DOUGLAS FIR), 6' HEIGHT, BALLED AND BURLAPPED	EACH	8			5	3											
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	50					50										
	X0320816	SLEEPER SLAB	SQ YD	137					137										
	X0320887	POLYMER CONCRETE	CU FT	6.4								6.4							
	X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	19	19														
	X0321598	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1														
	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	340	170														170
	X0322042	STORM SEWER (WATER MAIN REQUIREMENTS) 54 INCH	FOOT	25	13														12
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	51	206													
*	X0322323	WEED CONTROL, TEASEL	GALLON	3		3													
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	45		45													
	X0323082	DRAINAGE SCUPPERS, DS-33	EACH	2							2								
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	35										35					
*	X0323670	PREFORMED DETECTOR LOOP	FOOT	210												210			
	X0323885	TRAFFIC SIGNAL BATTERY BACKUP SYSTEM	EACH	1												1			
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	583	307													276	
	X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	11	2		5	2	2										
	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	6	2				2	2									
*	X0326108	ELECTRICAL CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C #10 & 1C #10 GROUND	FOOT	400										400					
1 *	X0326164	PAINT NEW MAST ARM AND POLE, UNDER 40 FOOT	EACH	1															1 1
*	X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	83										83					
*	X0324413	CONDUIT EMBEDDED IN STRUCTURE, 2 1/2" DIA., PVC (SCHEDULE 40)	FOOT	420										420					
	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	300	100				100	100									
1 *	X0325035	PAINT NEW COMBINATION MAST ARM AND POLE, UNDER 40 FT	EACH	2															2 1
	X0325239	TEMPORARY PAVEMENT 10"	SQ YD	10,431	5,858				4,573										
1 *	X0325037	PAINT NEW SIGNAL POST	EACH	3															3 1
	X0325733	TEMPORARY ASPHALT WEDGE	SQ YD	305					305										
	X0325864	BRIDGE APPROACH PAVEMENT REMOVAL	SQ YD	438							182	256							
	X2800500	INLET PROTECTION, SPECIAL	EACH	8	2		1	1	4										
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	26	20				3	3									
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	13	9				4										
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	9				3										
	X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	785	785														

* DENOTES SPECIALTY ITEMS

1 Rev. 7-17-08

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 13

SCALE:
DRAWN BY: JB
DATE: 03/14/08
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
360 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\SU000R55.DGN,..\SU000R63.DGN,..\TEROORNO.DGN
3-24-2008, 10:37:46 T:\DOCUMENT\932790\CIVIL\DGN\SU000Z55.DGN
BONDHALIO 6575859 6016 6263