

## SUMMARY OF QUANTITIES

← 90% FED. / 10% STATE →

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	WILL COUNTY											TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	90% FED./10% STATE RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
				ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS				
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E				
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	34	34														
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	24	4	4	4	4	4	4									
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1													
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	273		273													
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48										48					
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1														1	
X8160395	UNIT DUCT, WITH 3-1/2" NO. 2 AND 1/2" NO. 4 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	17,100											17,100				
X8250110	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA	EACH	1										1					
X8420090	REMOVAL OF EXISTING SIGN LUMINAIRE	EACH	4										4					
X8420140	REMOVAL OF EXISTING LIGHTING UNIT, AND LUMINAIRE SALVAGE	EACH	12										12					
X8420200	REMOVAL OF EXISTING LIGHT TOWER AND SALVAGE	EACH	4										4					
X8420300	LIGHTING FOUNDATION REMOVAL, LIGHT TOWER	EACH	4										4					
X8450100	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1										1					
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	589												589			
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	313															313
XX003503	FLARED END SECTION REMOVAL	EACH	57	29		3		19	6									
XX004056	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	6,676								6,676							
XX004814	SILICONE JOINT SEALER, 3"	FOOT	162									162						
XX005631	UTILITY STRUCTURES TO BE ADJUSTED	EACH	7	7														
XX005656	INLET FILTER CLEANING	EACH	167	167														
XX005715	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	300	100				100	100									
XX006179	SANITARY MANHOLE REMOVAL AND REPLACEMENT	EACH	1															1
XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	1														1	
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	81											81				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	86,009	34,696	17,526	11,826	7,438	6,535	7,988									
Z0007601	BUILDING REMOVAL NO.1	L SUM	1	1														
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.2	0.2	0.2	0.1	0.1									
<del>Z0049901</del>	<del>REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS BUILDING NO.1</del>	<del>L SUM</del>	<del>1</del>															
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	110									110						
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1														
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	32	28														4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6	2	4													
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	16	8	6			2										

NP= Non-Participating  
 \* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59  
 SECTION: (26, 26HB-1&114) R-2

### SUMMARY OF QUANTITIES 14

SCALE: \_\_\_\_\_ DRAWN BY: JB  
 DATE: 03/14/08 CHECKED BY: ACL

**TENG**

TENG & ASSOCIATES, INC.  
 ENGINEERS ARCHITECTS PLANNERS  
 200 N. MICHIGAN AVE. CHICAGO, IL 60601  
 TELEPHONE: 312-666-9900

\S:\00000000\SS\00000000\... \TTEG00000000\...  
 11:00:00 AM 11/13/08 19:20:22 24 27282 72829 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63  
 11:00:00 AM 11/13/08 19:20:22 24 27282 72829 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63



Rev.