

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH										TOTAL 9,457 FOOT
LOCATION	"FROM STATION"	"TO STATION"	"LENGTH" FT	COLOR	X	LENGTH	%	MOT	STAGE	SUBTOTALS FOOT
LANE	LINES	10'	DASH 30'	SKIP						
I55 SB	79+24.96	98+00.00	1875.04	WHITE	2	3750.08	25%	STAGE 1		937.52
	98+00.00	111+00.00	1300.00	WHITE	2	2600.00	25%	STAGE 1		650.00
	111+00.00	113+74.07	274.07	WHITE	2	548.14	25%	STAGE 1		137.04
I55 NB	71+59.22	98+00.00	2640.78	WHITE	2	5281.56	25%	STAGE 1		1,320.39
	98+00.00	107+42.48	942.48	WHITE	2	1884.96	25%	STAGE 1		471.24
I55 SB	108+19.30	111+00.00	280.70	WHITE	2	561.40	25%	STAGE 4A		140.35
	111+00.00	126+00.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4A		750.00
	126+00.00	145+19.00	1,919.00	WHITE	2	3,838.00	25%	STAGE 4A		959.50
I55 NB	108+09.00	111+00.00	291.00	WHITE	2	582.00	25%	STAGE 4A		145.50
	111+00.00	126+00.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4A		750.00
	126+00.00	142+71.00	1,671.00	WHITE	2	3,342.00	25%	STAGE 4A		835.50
I55 SB	134+50.00	149+50.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4B		750.00
I55 NB	130+50.00	145+50.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4B		750.00

X0325841 WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH										TOTAL 407 FOOT		
LOCATION	"FROM STATION"	"TO STATION"	"LINE OFFSET"	"LINE TYPE"	LENGTH FT	MEASURED BY	CAD	"LINE WIDTH"	COLOR	MOT	STAGE	SUBTOTALS FOOT
IL 59	7528+77.00		RT	SOLID								
SEIL	4010+52.70	4010+97.00	RT	SOLID	44.30	39		2	WHITE	STAGE 2A		39
SEIL	4010+89.00		LT	SOLID				2	WHITE	STAGE 2A		44.3
IL 59	7496+00.00		RT	SOLID				2	WHITE	STAGE 2A		14
IL 59	7496+00.00		RT	SOLID				2	WHITE	STAGE 2A		18
IL 59	2983+56.00		LT	SOLID				2	WHITE	STAGE 2B		23
SEIL	4009+25.00		RT	SOLID				2	WHITE	STAGE 3B		20
SEIL	4010+44.00	4010+87.00	RT	SOLID	43			2	WHITE	STAGE 3B		43
SEIL	4010+99.00		RT	SOLID				2	WHITE	STAGE 3B		13
SEIL	4018+10.00		RT	SOLID				2	WHITE	STAGE 3B		61
IL 59	7475+34.00		RT	SOLID				2	WHITE	STAGE 3B		25
IL 59	7476+32.00		LT	SOLID				2	WHITE	STAGE 3B		33
PAVEMENT MARKING WEAR AND TEAR 10%												37

X0325837 WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH						TOTAL 2,097 FOOT
STA.	STA.	LENGTH	TYPE OF LINE	STAGE	SUBTOTALS FOOT	
7525+17.00	7527+68.00	251	2D-6S	PRESTAGE A	63	
7525+17.00	7527+68.00	251	2D-6S	PRESTAGE A	63	
7527+68.00	7528+77.00	109	SOLID	PRESTAGE A	109	
7527+68.00	7528+77.00	109	SOLID	PRESTAGE A	109	
7525+00.00	7527+68.00	268	2D-6S	PRESTAGE B	67	
7525+00.00	7527+68.00	268	2D-6S	PRESTAGE B	67	
1002+00.57	1003+33.61	133	2D-6S	PRESTAGE B	33	
7525+17.00	7527+00.00	183	2D-6S	STAGE 1	46	
7525+17.00	7527+00.00	183	2D-6S	STAGE 1	46	
7527+00.00	7527+68.00	68	SOLID	STAGE 1	68	
7527+00.00	7527+68.00	68	SOLID	STAGE 1	68	
7525+26.00	7527+00.00	174	2D-6S	STAGE 2A	44	
7527+00.00	7528+77.00	177	SOLID	STAGE 2A	177	
7527+00.00	7528+77.00	177	SOLID	STAGE 2A	177	
2983+56.00	2985+11.00	155	SOLID	STAGE 2B	155	
7525+64.00	7527+00.00	136	2D-6S	STAGE 2B	34	
7476+32.00	7477+50.00	118	SOLID	STAGE 3B	118	
4016+50.00	4018+09.00	159	SOLID	STAGE 3B	159	
8034+00.00	8036+10.00	210	SOLID	STAGE 3B	210	
7477+50.00	7480+71.00	321	2D-6S	STAGE 3B	80	
PAVEMENT MARKING WEAR AND TEAR 10%					205	

70400100 TEMPORARY CONCRETE BARRIER											TOTAL 7,375 FOOT
STAGE	LOCATION	STA	STA	LENGTH	NEW WALL NEEDED	WALL FROM PREVIOUS STAGE	"WALL FROM ON-SITE STAGE"	"RELOCATE WALL TO STORAGE"	"RELOCATED TO AND REMAINING IN STORAGE"	SUBTOTALS FOOT	
PRESTAGE B1	IL59	7520+45.00	7522+40.00	210	210					210	
PRESTAGE B2	IL59	7520+10.00	7522+47.00	240	30	210				30	
STAGE 1	I55 NB	82+47.00	85+00.00	260	260					260	
STAGE 1	I55 NB	85+00.00	105+00.00	2000	2000					2000	
STAGE 1	I55 NB	105+00.00	108+10.00	310	310					310	
STAGE 1	I55 NB	108+10.00	115+90.00	780	780					780	
STAGE 1	I55 SB	119+00.00	120+12.00	110	110					110	
STAGE 1	I55 SB	110+65.00	119+00.00	835	835					835	
STAGE 1	I55 SB	109+00.00	110+65.00	165	165					165	
STAGE 1	I55 SB	82+25.00	109+00.00	2675	2675					2675	
STAGE 2A	I55 NB	95+65.00	101+09.00	544		544					
STAGE 2A	I55 SB	103+70.00	109+25.00	555		555					
WINTER STAGE (SURPLUS STORE WINTER)											
STAGE 2A1	NBRP	150+12.00	152+48.00	240			240			240	
STAGE 2A2	NBRP	148+60.00	152+45.00	390			150			150	
WINTER STAGE (SURPLUS STORE WINTER)											
STAGE 3 PRE	RUNAROUND/SEIL	1011+87.00	1013+42.00	155				3475	3475		
STAGE 3A	I55 SB	103+70.00	109+25.00	REMOVE						240	
STAGE 3B	I55 NB	95+65.00	101+09.00	REMOVE						150	
STAGE 4A	I55 SB	111+00.00	130+55.00					555	555		
STAGE 4A	I55 NB	130+55.00	131+80.00							390	
STAGE 4A	I55 NB	111+09.00	112+50.00							155	
STAGE 4A	I55 NB	112+50.00	127+50.00								
STAGE 4A	I55 NB	136+65.00	137+05.00								
STAGE 4A	I55 NB	137+05.00	140+45.00								
STAGE 4A	I55 SB	139+65.00	141+25.00								
STAGE 4A	I55 SB	141+25.00	142+75.00								
STAGE 4B	I55 NB	137+14.00	141+00.00								
STAGE 4B	I55 SB	139+00.00	142+86.00								

X0325840 WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH									TOTAL 6299 FOOT
DIRECTION	LOCATION	"FROM STATION"	"TO STATION"	OFFSET	"LINE WIDTH"	COLOR	MOT	STAGE	SUBTOTALS FOOT
NB	IL 59	7519+20.00	7528+78.00	LT & RT	1	YELLOW		PRESTAGE A	540
EB	SEIL RD	4008+69.26	4010+06.13	LT	1	WHITE		PRESTAGE B	78
EB	SEIL RD	4010+90.22	4012+01.31	LT	1	WHITE		PRESTAGE B	41
EB	SEIL RD	4011+53.58	4014+00.00	LT & RT	1	WHITE		PRESTAGE B	103
NB	IL 59	7523+00.00	7528+77.00	LT & RT	1	YELLOW		PRESTAGE B	644
NB	IL 59	7522+42.00	7528+77.00	LT & RT	1	YELLOW		PRESTAGE B	690
NB	IL 59	7520+44.00	7528+77.00	LT & RT	1	YELLOW		STAGE 1	1714
SB	I-55	85+00	110+00	LT	1	YELLOW		STAGE 1	25
NB	I-55	85+00	110+00	RT	1	YELLOW		STAGE 1	29
NB	I-55	110+00	110+00	RT	1	WHITE		STAGE 1	15
NB	IL 59	7522+32	7528+77	LT & RT	2	YELLOW		STAGE 2A	837
NB	IL 59	7522+00	7528+77	LT & RT	2	YELLOW		STAGE 2B	420
NB	IL 59	7476+24	7479+60	LT & RT	1	YELLOW		STAGE 3B	319
NB	IL 59	7489+00	7492+22	RT	1	YELLOW		STAGE 3B	17
NB	IL 59	7488+50	7493+50	RT	1	WHITE		STAGE 3B	254
PAVEMENT MARKING WEAR AND TEAR 10%									572

70300550 WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 8 INCH							TOTAL 4,135 FOOT
DIRECTION	LOCATION	STA.	STA	CALC LENGTH (FT)	MOT	STAGE	SUBTOTALS FOOT
NB	I-55	68+29.00	77+01.00			STAGE 1	843
NB	I-55	71+59.00	77+01.00	542.00		STAGE 1	542
NB	I-55	71+59.00	81+76.00	1,017.00		STAGE 1	1,017
SB	I-55	74+30.00	75+06.00	76.00		STAGE 1	76
SB	I-55	74+30.00	75+06.00	76.00		STAGE 1	76
SB	I-55	75+03.00	78+03.00	300.00		STAGE 1	300
SB	I-55	78+03.00	82+00.00	397.00		STAGE 1	397
NB	IL 59	7493+17.00	7498+25.00	508.00		STAGE 3B	508
PAVEMENT MARKING WEAR AND TEAR 10%							376

REVISIONS	
NAME	DATE
JB	07/11/08

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59
 SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 23

SCALE: _____ DRAWN BY: JB
 DATE: 03/14/08 CHECKED BY: ACL

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS ARCHITECTS PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312.960.4000

I:\SC000\FF2.DGN ..TTBOORNDGN
 7-14-2008 8:02:02
 T:\DOCUMENT\932790\CIVIL\ADON\SC000\82.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63