

### SUMMARY OF QUANTITIES

IDOT CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	CMM		F 80% FED./20% STATE		CMM 80% FED./20% STATE		
				J000-2A ROADWAY 80% FED./20% STATE	ROADWAY 60% STATE 40% GURNEE	X271-2A BRIDGE	Y007 RETAINING WALLS	Y031-1F TRAFFIC SIGNALS	Y030-1E LIGHTING	J000-2A SIGNING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	862	862						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1159	1159						
20101100	TREE TRUNK PROTECTION	EACH	90	90						
20200100	EARTH EXCAVATION	CU YD	88824	88824						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4227	3854				373		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	580	207				373		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	934				934			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	19864	19864						
20800150	TRENCH BACKFILL	CU YD	11504	11486	18					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	43086	43086						
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	689	689						
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	43775	43775						
* 25000210	SEEDING, CLASS 2A	ACRE	6.5	6.5						
* 25000312	SEEDING, CLASS 4A	ACRE	0.04	0.04						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	730	730						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	730	730						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	730	730						
NP 25000750	MOWING	ACRE	8.9	8.9						
* 25100630	EROSION CONTROL BLANKET	SQ YD	17776	17776						
* 25200110	SODDING, SALT TOLERANT	SQ YD	11485	11485						
* 25200200	SUPPLEMENTAL WATERING	UNIT	5259	5259						
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	115	115						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	976	976						
28000300	TEMPORARY DITCH CHECKS	EACH	53	53						
28000510	INLET FILTERS	EACH	111	111						
28001000	AGGREGATE (EROSION CONTROL)	TON	2	2						
28100107	STONE RIPRAP, CLASS A4	SQ YD	215	215	△					
28200200	FILTER FABRIC	SQ YD	178	178						
35102100	AGGREGATE BASE COURSE, TYPE B 9"	SQ YD	1333	1333						
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	1208	1208						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	192	192						
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5043	5043						
40600300	AGGREGATE (PRIME COAT)	TON	42	42						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	729	729						
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	203	203						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	189	189						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	850	850						
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	6266	6266						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	29696	29696						
42001300	PROTECTIVE COAT	SQ YD	50778	50778						

● 100% Village of Gurnee - Y006  
 \* Specialty items  
 NP= Non-participating

PLAN  
 SUBMITTED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 PLOTTED BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_  
 ALIGNED BY \_\_\_\_\_  
 ANNOTATED BY \_\_\_\_\_  
 CADD FILE NAME \_\_\_\_\_  
 NO. \_\_\_\_\_

PROFILE  
 SUBMITTED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 PLOTTED BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_  
 GRADES CHECKED BY \_\_\_\_\_  
 STRUCTURE NOTATION CHECKED BY \_\_\_\_\_  
 NO. \_\_\_\_\_

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 U.S. 41 (SKOKIE HIGHWAY)  
 AT IL ROUTE 132  
 SUMMARY OF QUANTITIES  
 SHEET 1 OF 9  
 SCALE: NONE  
 DATE: MAY 12, 2008  
 DRAWN BY:  
 CHECKED BY:

△ Rev. 7-15-08 Rev.