

SUMMARY OF QUANTITIES

IDOT CODE NO.	ITEM DESCRIPTION	UNIT	UABAN TOTAL QUANTITIES	CMM		801.FED./201.STATE		CMM 801.FED./201.STATE		
				J000-2A		X271-2A	Y007	Y031-1F	Y030-1E	J000-2A
				ROADWAY 801.FED./201.STATE	ROADWAY 60% STATE 40% GURNEE	BRIDGE	RETAINING WALLS	TRAFFIC SIGNALS	LIGHTING	SIGNING
66410300	CHAIN LINK FENCE REMOVAL	FOOT	186	186						
67100100	MOBILIZATION	L SUM	1	1						
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1						
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1						
70102000	TRAFFIC CONTROL AND PROTECTION (DETOUR 2)	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	550	550						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7480	7480						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	8162	8162						
72000100	SIGN PANEL - TYPE 1	SQ FT	326							326
72000200	SIGN PANEL - TYPE 2	SQ FT	143							143
72000300	SIGN PANEL - TYPE 3	SQ FT	898							898
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	294							294
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	101							101
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	449							449
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3204							3204
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	323							323
73000100	WOOD SIGN SUPPORT	FOOT	163							163
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	5							5
73302110	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE I-C-A (24" X 4'-6")	FOOT	19							19
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	17							17
73400100	CONCRETE FOUNDATIONS	CU YD	10							10
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	5							5
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	88493	88493						
78008200	POLYUREA PAVEMENT MARKING, TYPE I - LETTERS AND SYMBOLS	SQ FT	820	820						
78008210	POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	34966	34966						
78008230	POLYUREA PAVEMENT MARKING, TYPE I - LINE 6"	FOOT	2222	2222						
78008240	POLYUREA PAVEMENT MARKING, TYPE I - LINE 8"	FOOT	7915	7915						
78008250	POLYUREA PAVEMENT MARKING, TYPE I - LINE 12"	FOOT	2553	2553						
78008270	POLYUREA PAVEMENT MARKING, TYPE I - LINE 24"	FOOT	223	223						
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	362	362						
78200410	GUARDRAIL MARKERS, TYPE A	EACH	28	28						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2						
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1						1	
81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	20					20		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1156					1156		
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	534					534		
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	37					37		
81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	20					20		
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	45					45		
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	108					108		

* specialty items

PLAN
 SURVEYS
 PLOTTED
 ALIGNED
 CHECKED
 CADD FILE NAME
 BY
 DATE

PROFILE
 GRADES
 CHECKED
 STRUCTURE
 NOTATIONS CHECKED
 BY
 DATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 U.S. 41 (SKOKIE HIGHWAY)
 AT IL ROUTE 132
 SUMMARY OF QUANTITIES
 SHEET 5 OF 9
 SCALE: NONE
 DATE: MAY 12, 2008
 DRAWN BY:
 CHECKED BY: