

CONCRETE BARRIER, SINGLE FACE, 32"

ALIGNMENT	FROM STA	TO STA	LENGTH (FT)
SB 41	526+09.09	530+08.46	400
SB 41	526+50.00	542+00.00	1550
SB 41	526+72.51	540+50.17	1377.54
SB 41	528+94.93	533+02.93	408.01
SB 41	538+00.00	546+84.89	884.24

TOTAL: 4620

STEEL PLATE BEAM GUARDRAIL, TYPE A

ALIGNMENT	FROM STA	TO STA	LENGTH (FT)
SB 41	511+69.45	519+88.01	822.4
SB 41	511+69.04	519+88.02	831.9
SB 41	526+43.35	526+91.97	50.0

TOTAL: 1704

CONCRETE BARRIER, DOUBLE FACE, 32"

ALIGNMENT	FROM STA	TO STA	LENGTH (FT)
SB 41	519+88.01	543+90.56	2405.43
NB 41	517+68.21	604+22.35	634.99

TOTAL: 3041

CONCRETE BARRIER, SPECIAL, 32"

ALIGNMENT	FROM STA	TO STA	LENGTH (FT)
SB 41	522+82.88	526+09.00	326.8
SB 41	528+00.00	528+94.93	94.93
SB 41	530+08.44	531+50.00	141.56
SB 41	537+88.11	538+00.00	11.89
SB 41	538+00.00	538+73.85	73.85

TOTAL: 649

HMA DRIVEWAY PAVEMENT

ALIGNMENT	FROM STA	TO STA	AREA (SY)
EB 132	15+91.12	16+59.33	86.48
EB 132	16+65.66	16+77.65	16.24
EB 132	17+87.16	17+97.28	18.52
EB 132	18+04.93	18+14.75	18.46
EB 132	18+62.13	18+73.28	18.83
EB 132	19+27.69	19+40.14	33.05

TOTAL: 192

IMPACT ATTENUATOR, TEST LEVEL 3

ALIGNMENT	FROM STA	TO STA	QTY (EACH)
SB 41	523+90.84	524+17.51	1
SB 41	526+22.70	526+49.37	1
SB 41	537+73.01	537+99.68	1
SB 41	538+00.51	538+27.10	1
SB 41	540+50.17	540+76.83	1
SB 41	543+91.94	544+18.17	1

TOTAL: 6

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

ALIGNMENT	STATION	OFFSET	QTY (EACH)
SB 41	511+69.04	23.02 LT	1
SB 41	511+69.45	6.48 LT	1
SB 41	519+88.01	6.48 LT	1
SB 41	519+88.02	19.58 LT	1

TOTAL: 4

PLAN
SURVEYED
PLOTTED
CHECKED
DATE
BY
NOTE BOOK NO.
CADD FILE NAME

PROFILE
SURVEYED
PLOTTED
CHECKED
DATE
BY
NOTE BOOK NO.
STRUCTURE NOTATIONS CHFD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. 41 (SKOKIE HIGHWAY)
AT IL ROUTE 132
**SCHEDULE OF QUANTITIES
PROPOSED QUANTITIES**
SHEET 2 OF 2
SCALE: NONE
DATE: MAY 12, 2008
DRAWN BY: AZ
CHECKED BY: ALB