

| SUMMARY OF QUANTITIES |  |       |                               | TOTAL QUANTITY | URBAN<br>CONSTRUCTION TYPE<br>CODE |
|-----------------------|--|-------|-------------------------------|----------------|------------------------------------|
| CODE NO.              | DESCRIPTION  | UNIT  | 100% STATE<br>ROADWAY<br>1000 |                |                                    |
| 20200100              | EARTH EXCAVATION                                   | CU YD | 105                           | 105            |                                    |
| 20201200              | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL        | CU YD | 200                           | 200            |                                    |
| 20800150              | TRENCH BACKFILL                                    | CU YD | 60                            | 60             |                                    |
| 21101615              | TOPSOIL FURNISH AND PLACE, 4"                      | SQ YD | 2,100                         | 2,100          |                                    |
| 25200110              | SODDING, SALT TOLERANT                             | SQ YD | 2,100                         | 2,100          |                                    |
| 28000250              | TEMPORARY EROSION CONTROL SEEDING                  | POUND | 75                            | 75             |                                    |
| 28000300              | TEMPORARY DITCH CHECKS                             | EACH  | 10                            | 10             |                                    |
| 28000400              | PERIMETER EROSION BARRIER                          | FOOT  | 2,000                         | 2,000          |                                    |
| 40600200              | BITUMINOUS MATERIALS (PRIME COAT)                  | TON   | 5                             | 5              |                                    |
| 40600300              | AGGREGATE (PRIME COAT)                             | TON   | 25                            | 25             |                                    |
| 40600400              | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS         | TON   | 10                            | 10             |                                    |
| 40600895              | CONSTRUCTING TEST STRIP                            | EACH  | 2                             | 2              |                                    |
| 40600982              | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT       | SQ YD | 175                           | 175            |                                    |
| 40600625              | LEVELING BINDER (MACHINE METHOD), N50              | TON   | 250                           | 250            |                                    |
| 40603335              | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50       | TON   | 600                           | 600            |                                    |
| 42300200              | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 110                           | 110            |                                    |
| 44000198              | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH    | SQ YD | 2,700                         | 2,700          |                                    |
| 44000200              | DRIVEWAY PAVEMENT REMOVAL                          | SQ YD | 120                           | 120            |                                    |
| 44201749              | CLASS D PATCHES, TYPE I, 9 INCH                    | SQ YD | 1,000                         | 1,000          |                                    |
| 44201753              | CLASS D PATCHES, TYPE II, 9 INCH                   | SQ YD | 200                           | 200            |                                    |
| 44201757              | CLASS D PATCHES, TYPE III, 9 INCH                  | SQ YD | 50                            | 50             |                                    |
| 44201759              | CLASS D PATCHES, TYPE IV, 9 INCH                   | SQ YD | 670                           | 670            |                                    |

| SUMMARY OF QUANTITIES |   |        |                               | TOTAL QUANTITY | URBAN<br>CONSTRUCTION TYPE<br>CODE |
|-----------------------|---|--------|-------------------------------|----------------|------------------------------------|
| CODE NO.              | DESCRIPTION   | UNIT   | 100% STATE<br>ROADWAY<br>1000 |                |                                    |
| 44300200              | STRIP REFLECTIVE CRACK CONTROL TREATMENT  | FOOT   | 1,600                         | 1,600          |                                    |
| 48101498              | AGGREGATE SHOULDERS, TYPE B4"   | SQ YD  | 1,500                         | 1,500          |                                    |
| 55019500              | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV12" | FOOT   | 230                           | 230            |                                    |
| 55037800              | STORM SEWERS TO BE CLEANED 12"  | FOOT   | 1,000                         | 1,000          |                                    |
| 55038000              | STORM SEWERS TO BE CLEANED 18"  | FOOT   | 200                           | 200            |                                    |
| 60201330              | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE                                  | EACH   | 2                             | 2              |                                    |
| 60237460              | INLETS, TYPE A, TYPE 23 FRAME AND GRATE   | EACH   | 1                             | 1              |                                    |
| 60500050              | REMOVING CATCH BASINS   | EACH   | 1                             | 1              |                                    |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A   | CAL MO | 6                             | 6              |                                    |
| 67100100              | MOBILIZATION  | L SUM  | 1                             | 1              |                                    |
| 70102620              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501   | L SUM  | 1                             | 1              |                                    |
| 70300100              | SHORT-TERM PAVEMENT MARKING   | FOOT   | 160                           | 160            |                                    |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL  | SQ FT  | 55                            | 55             |                                    |
| * 78000200            | THERMOPLASTIC PAVEMENT MARKING - LINE 4"  | FOOT   | 3,500                         | 3,500          |                                    |
| * 78000400            | THERMOPLASTIC PAVEMENT MARKING - LINE 6"  | FOOT   | 230                           | 230            |                                    |
| * 78000650            | THERMOPLASTIC PAVEMENT MARKING - LINE 24"   | FOOT   | 120                           | 120            |                                    |
| * 88600600            | DETECTOR LOOP REPLACEMENT   | FOOT   | 225                           | 225            |                                    |
| X0322256              | TEMPORARY INFORMATION SIGNING   | SQ FT  | 26                            | 26             |                                    |
| XX000671              | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-4.12   | FOOT   | 350                           | 350            |                                    |
| Z0013798              | CONSTRUCTION LAYOUT   | L SUM  | 1                             | 1              |                                    |
| Z0018500              | DRAINAGE STRUCTURES TO BE CLEANED   | EACH   | 7                             | 7              |                                    |
| Z0042200              | PORTLAND CEMENT CONCRETE PAVEMENT SURFACE REMOVAL   | SQ YD  | 850                           | 850            |                                    |

\* SPECIALTY ITEM

FILE NAME = N:\PROJ\3329\3329\_32\Design\ProposedPlan\3229\_32-#3-Quantities.dgn

**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4008 Fax 773.775.4014

|                           |                 |           |
|---------------------------|-----------------|-----------|
| USER NAME = jcoleman      | DESIGNED - NT   | REVISED - |
|                           | DRAWN - NT      | REVISED - |
| PLOT SCALE = 1:8000 / IN. | CHECKED - WBL   | REVISED - |
| PLOT DATE = 6/3/2008      | DATE - MAY 2008 | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 120 NORTH FRONTAGE ROAD  
WILL AVENUE TO KNIGHT AVENUE  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

|   |         |        |                    |           |
|---|---------|--------|--------------------|-----------|
| F.A.P. RTE.                                     | SECTION | COUNTY | TOTAL SHEETS       | SHEET NO. |
| 880   | 12 RS-3 | LAKE   | 21                 | 3         |
| FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT |         |        | CONTRACT NO. 60B45 |           |