

CONTRACT NO. 60C12

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	*	LAKE	19	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* SY-1-T-1				

SUMMARY OF QUANTITIES

ENGLISH CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY 100% STATE	ROADWAY QUANTITY Y007
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30
20800150	TRENCH BACKFILL	CU YD	209	209
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,388	3,388
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	30	30
25000210	SEEDING, CLASS 2A	ACRE	0.66	0.66
25000310	SEEDING, CLASS 4	ACRE	0.04	0.04
25100630	EROSION CONTROL BLANKET	SQ YD	3,388	3,388
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	210	210
28000510	INLET FILTERS	EACH	28	28
28100107	STONE RIPRAP, CLASS A4	SQ YD	24	24
28200200	FILTER FABRIC	SQ YD	24	24
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	26	26
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2	2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8	8
42001300	PROTECTIVE COAT	SQ YD	233	233
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	78	78
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	26	26
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	698	698
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	16	16
44002207	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 3/4"	SQ YD	19	19
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	18	18
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	2	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	100	100
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	15	15
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	55	55
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	30	30
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	325	325
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	25	25
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	185	185
550A1030	STORM SEWERS, CLASS A, TYPE 4 30"	FOOT	7	7
550A1080	STORM SEWERS, CLASS A, TYPE 4 48"	FOOT	599	599
55101400	STORM SEWER REMOVAL 30"	FOOT	10	10
552A0200	STORM SEWERS JACKED IN PLACE, CLASS A 12"	FOOT	54	54
552A0900	STORM SEWERS JACKED IN PLACE, CLASS A 24"	FOOT	85	85
552A1600	STORM SEWERS JACKED IN PLACE, CLASS A 48"	FOOT	169	169
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,027	2,027
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	14	14
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	4	4
* 66900200	NIN-SPECIAL WASTE DISPOSAL	CU YD	30	30
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1

ENGLISH CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY 100% STATE	ROADWAY QUANTITY Y007
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	4	4
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	6	6
60500040	REMOVING MANHOLES	EACH	2	2
60500050	REMOVING CATCH BASINS	EACH	1	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	698	698
66400305	CHAIN LINK FENCE, 6'	FOOT	326	328
66410300	CHAIN LINK FENCE REMOVAL	FOOT	335	335
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16
70300510	PAVEMENT MARKING TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	110	110
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6,697	6,697
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	104	104
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	758	758
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	371	371
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,271	3,271
70400100	TEMPORARY CONCRETE BARRIER	FOOT	265	265
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,490	5,490
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	825	825
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	290	290
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	117	117
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	36	36
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	997	997
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	38	38
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	153	153
B2005466	TREE, PRUNUS VIRGINIANA SCHUBERT (SCHUBERT CHOKECHERRY), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	2	2
C2002072	SHRUB, CORYLUS AMERICANA (AMERICAN FILBERT), 6' HEIGHT, BALLED AND BURLAPPED	EACH	4	4
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	755	755
XX005970	UNDERWATER STRUCTURE EXCAVATION PROTECTION	L SUM	1	1
XX006694	CLEARING (SPECIAL)	SQ YD	1,390	1,390
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	23	23
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEMS

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	FAP 334 (US 12 / RAND ROAD)
DATE	AT ELA ROAD
	SUMMARY OF QUANTITIES
	SCALE: NA
	DATE: 3/24/08
	DRAWN BY: WS
	CHECKED BY: RJS
	GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
	CHICAGO, ILLINOIS