F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	G-RS-4	LAKE	24	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT # 60C32

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000	1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	101	101					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	557		557	△1			
20800150	TRENCH BACKFILL	CU YD	37		37				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	60		60				
25200110	SODDING, SALT TOLERANT	SQ YD	60		60				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	360		360				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20					
40600300	AGGREGATE (PRIME COAT)	TON	100	100					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10					
40600995	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	33	33					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3	3					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	425	425		△1			
~~40603310~~	~~HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50~~	~~TON~~	~~4~~		~~4~~	△1			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2044 △1	2040	4	△1			
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	310		310				
44000100	PAVEMENT REMOVAL	SQ YD	310		310				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	24190	24190					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	180		180				
44002236	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 9"	SQ YD	817	817		△1			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	300	300					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	25	25					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	375	375					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	912	912					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000	1000				
50300300	PROTECTIVE COAT	SQ YD	40		40				
50800105	REINFORCEMENT BARS	POUND	55		55	△1			
54248510	CONCRETE COLLAR	CU YD	0.5		0.5				
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	6		6				
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	26		26				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	180		180				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		△1			
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	△1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14480	14240	240				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	568.2	508.2	60				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30100	26100	4000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2940	2540	400				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2800	2500	300				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	388		388				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	508.2	508.2					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26100	26100					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2540	2540					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2500	2500					

△1 Rev. 6-3-08

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 4/17/2008

4/17/2008
c:\projects\8412010\8ch_rdsv.dgn